


1112

**1st Boundary Increase**  
**VLR Listed: 7/2/1997**  
**NRHP Listed: 9/19/1997**



NPS Form 10-900  
(Rev. 8-86)

United States Department of the Interior  
National Park Service

**NATIONAL REGISTER OF HISTORIC PLACES  
REGISTRATION FORM**

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in Guidelines for Completing National Register Forms (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering the requested information. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets (Form 10-900-a). Type all entries.

**1. Name of Property**

Historic name Skyline Drive Historic District (Boundary Increase)  
Other names/site number N/A

**2. Location**

Street & Number Shenandoah National Park: Headquarters, Big Meadows, Dickey Ridge, Simmons Gap, Piney River areas [ ] Not for Publication  
City/town Luray [X] Vicinity  
State VA County Code Zip Code 22835  
Page 139  
Warren 187  
Madison 113  
Greene 079

**3. Classification**

Ownership of Property	Category of Property	No. Resources w/in Prop.	
		Contr.	Noncontrib.
[ ] Private	[ ] Building(s)		
[ ] Public-Local	[ X] District	<u>60</u>	<u>58</u> Buildings
[ ] Public-State	[ ] Site	<u>2</u>	<u>0</u> Sites
[ X] Public-Federal	[ ] Structure	<u>14</u>	<u>5</u> Structure
	[ ] Object	<u>8</u>	<u>0</u> Objects
		<u>84</u>	<u>63</u> Total

Name of related multiple property listing  
Historic Park Landscapes in National and State Parks  
Number of contributing resources previously listed in the National Register 175

**4. State/Federal Agency Certification**

As the designated authority under the National Historic Preservation Act of 1966, as amended, I hereby certify that this [] nomination [] request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion the property [] meets [] does not meet the National Register criteria. [] See continuation sheet.

*[Signature]*

7/18/97  
Date

Signature of certifying official  
Virginia Department of Historic Resources

State or Federal agency and bureau

In my opinion, the property [] meets [] does not meet the National Register criteria. [] See continuation sheet.

*Ronald M. Greenberg*

8/6/97  
Date

Signature of commenting or other official  
National Park Service

State or Federal agency or bureau

**5. National Park Service Certification**

I, hereby, certify that this property is:

[] entered in the National Register.

( ) see continuation sheet

[ ] determined eligible for the National Register. (see continuation sheet).

[ ] determined not eligible for the National Register.

[ ] removed from the National Register

[ ] other, (explain:)

*Patrick Andrews* 9/19/97

*[Signature]* Signature of the Keeper Date of Action

**6. Function or Use**

Historic Functions (enter categories from instructions)  
RECREATION & CULTURE: Outdoor Recreation  
DOMESTIC: Hotel & Single Dwelling  
COMMERCE: Restaurant  
GOVERNMENT: Government Office  
INDUSTRY: Industrial Storage

Current Functions (enter categories from instructions)  
RECREATION & CULTURE: Outdoor Recreation  
COMMERCE: Restaurant  
DOMESTIC: Hotel & Single Dwelling  
GOVERNMENT: Government Office  
INDUSTRY: Industrial Storage

**7. Description**

Architectural Classification  
(enter categories from instructions)  
Other: NPS Rustic Architecture

Materials (enter categories  
from instructions)  
foundation: Concrete  
walls: Wood, Stone  
roof: Concrete (shingles), Slate  
other: \_\_\_\_\_

Describe present and historic physical appearance. (See continuation sheet)

**8. Statement of Significance**

Certifying official has considered the significance of this property in relation to other properties:

nationally                       statewide                       locally

Applicable National Register Criteria A B C D

Criteria Considerations (Exceptions) A B C D E  
F G

Areas of Significance (enter categories from instructions)	Period of Significance	Significant Dates
--	------------------------	-------------------

<u>Politics/Government</u>	<u>1931-1952</u>	<u>1935</u>
----------------------------	------------------	-------------

<u>Architecture</u>	_____	_____
---------------------	-------	-------

<u>Entertainment/Recreation</u>	_____	_____
---------------------------------	-------	-------

<u>Landscape Architecture</u>	Cultural Affiliation	
-------------------------------	----------------------	--

_____	<u>N/A</u>	_____
-------	------------	-------

_____	Architect/Builder	
-------	-------------------	--

_____	<u>Wright, Marcellus, Jr.;</u>	
-------	--------------------------------	--

Significant Person	<u>Benson, Harvey; and Baughan, G.R.</u>	
--------------------	--	--

State significance of property, and justify criteria, criteria considerations, and areas and period of significance noted above.  
(See continuation sheet)

**9. Major Bibliographic References**  
(See continuation sheet)

Previous documentation on file (NPS):  
 preliminary determination of individual listing (36 CFR 67)  
 previously listed in the NR  
 previously determined eligible by the National Register  
 designated a National Historic Landmark  
 recorded by Historic American Buildings Survey #\_\_\_\_\_  
 recorded by Historic American Engineering Record #VA-119

See continuation sheet

Primary location of add. data:  
 State SHPO office  
 Other State agency  
 Federal agency  
 Local government  
 University  
 Other

Specify repository:  
Shenandoah National Park Archives

**10. Geographical Data**

Acreage of property Approximately 180 Acres

UTM References

A       
Zone Easting Northing

B       
Zone Easting Northing

See continuation sheet

Verbal Boundary Description

See continuation sheet

Boundary Justification

See continuation sheet

**11. Form Prepared By**

Name/title Carol Hooper, Architectural Historian  
Organization Robinson & Associates, Inc. Date April, 1997  
Street & Number 1909 Q Street, N.W. Telephone 202-234-2333  
City or Town Washington State District of Columbia  
Zip code 20009

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 1

---

## INTRODUCTION

This boundary addition to the Skyline Drive Historic District brings into the existing district approximately 180 acres of land, and approximately 147 resources located in five developed areas of Shenandoah National Park.<sup>1</sup> Most of the areas of the park included in this nomination were designed and constructed as part of National Park Service Master Plans dating from the mid- to late 1930s. They include recreational areas for visitors to the park (picnic grounds, campgrounds, lodges/cabin areas, waysides) and utility, residential, and administrative areas for park personnel. Most buildings contributing to the expanded district were constructed in the mid-1930s to the early-1940s and were designed in the Rustic style.<sup>2</sup>

The Skyline Drive Historic District, which this nomination expands, embraces the 105.5-mile-long Skyline Drive that roughly bisects the park, and a 125-foot strip on either side of the Drive. The area included in the original nomination contains 254 resources, a majority of which are structures. The present nomination will expand the boundaries of the Skyline Drive Historic District to add four areas adjacent to the Drive to the district: Piney River, Simmons Gap, Big Meadows, and Dickey Ridge. This nomination also includes the Park Headquarters area, which although not adjacent to the Drive is integral to the park and thematically ties the four separate areas, and the Drive, together.<sup>3</sup>

---

<sup>1</sup>Thirty-nine resources included within this nomination have already been determined to be eligible for the National Register.

<sup>2</sup>The period of significance, 1931 to 1952 embraces all buildings up to, and including, the immediate post-war period. At Shenandoah, like many other parks, there was a major period of construction during the Depression years. Thereafter, there was minor (but architecturally compatible) work done during the war (mostly by CPS workers) and minor work done in the years immediately following the war. Thereafter, there followed a long period, up to the 1960s when practically nothing was constructed in the park. Buildings that were a product of the Mission 66 initiative (see below) have been determined not to be eligible for the National Register.

<sup>3</sup>As discussed below, the area authorized by Congress for the park is larger than that owned by the National Park Service and currently within the actual park boundaries. Although the area between the Headquarters area and the rest of the park is outside the park boundaries it is within the legislatively authorized boundaries. See Section 10 of this nomination for additional information as to why a discontinuous district is appropriate in this case.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 2

---

### General Description of Shenandoah National Park

Shenandoah National Park consists of a 70-mile-long, irregularly shaped strip of land that follows the ridgeline of the Blue Ridge Mountains between the towns of Front Royal, Virginia (to the north), and Waynesboro, Virginia (to the south). The Blue Ridge Mountains form the division between the Piedmont region of Virginia to the east and the Shenandoah Valley region to the west. The park contains approximately 60 peaks higher than 3,000 feet. The 194,600 acres that today make up the park pass through Albemarle, Augusta, Greene, Madison, Page, Rappahannock, Rockingham, and Warren Counties. Most of the land is forest, with some 80,000 acres designated as wilderness.

The developed portions of the park are centered on, and accessed by, the 105.5-mile Skyline Drive. They include campgrounds, picnic facilities, visitor centers, other tourist-related facilities (lodges/motels, restaurants, stores, gas stations, etc.), and facilities related to park operations (offices, residences, utility buildings, etc.). These facilities date from 1932 to the present. Although when the park was established there were hundreds of extant buildings (mostly cabins and barns), today there are approximately 20 buildings that pre-date 1932. These include a few residences and associated outbuildings, a barn, tourist cabins at Skyland, and a mission building. Most of the Skyline Drive, which bisects the park at the ridge of the mountains, predates the establishment of the park by a few years. Since its inception, the Drive has been one of the most popular scenic drives in the country. It is known for its panoramic views of the mountains and the adjacent Piedmont and Valley areas.<sup>4</sup>

### **DESCRIPTION OF THE BOUNDARY ADDITION AREA**

The area to be added to the historic district consists of five concentrations of built resources that are adjacent to, or near, the Skyline Drive. Except for the Headquarters area (which is located in a lower area off a major road leading into the park), these areas are perched along the ridgeline of the Blue Ridge Mountains. All of the boundary addition area is in the midst of oak-hickory type forest. Three of the areas (Headquarters, Dickey Ridge, Big Meadows) were designed and constructed between 1936 and 1939 as part of the original master planning for the park. The other two areas (Simmons Gap and Piney River) were part of improvements that predate the park and were later developed by the National Park Service as maintenance areas.

---

<sup>4</sup>For more descriptive and historical information on Skyline Drive, see Lee Maddex et al, National Register of Historic Places Registration Form for Skyline Drive Historic District (1996).

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 4

---

constructed and used by the CCC. The majority of the buildings in this category, however, were constructed after the park came into existence in 1935. With the exception of the buildings constructed for use by the CCC, most of the buildings were designed by the National Park Service--oftentimes following slightly modified standardized plans. These buildings are in the "rustic" style as interpreted by the NPS. The Rustic style aimed at a connection with natural surroundings through the use of native materials in proper scale, and the avoidance of severely straight lines and over-sophistication. Although the use of materials varied between areas, in general the buildings utilized local materials: predominantly wood (mostly log) and stone (sandstone, fieldstone etc.). Many of the buildings have the unusual concrete shingles that are distinctive to the park. Buildings were simple in design and generally stained or painted brown to blend with their surroundings.

The third broad category of contributing buildings includes those constructed by the park's concessionaire. These too are largely in the Rustic style. All of the concessionaire's buildings constructed before World War II were designed by Richmond architect Marcellus Wright, Jr. Although certain of the buildings, such as cottages located at Big Meadows, are of log construction and are very similar to the National Park Service structures, others, such as the lodges at Big Meadow and Dickey Ridge, are quite different. In general, they are larger and more elaborate, with more sophisticated designs. The buildings feature a number of attached sections that are almost domestic in quality. These segmented designs allowed the buildings to follow the form of the landscape. In terms of materials, in addition to wood and stone, Wright also often used glass blocks and concrete shingles.

### **SUMMARY OF INTEGRITY ISSUES**

In general, the integrity of the boundary addition area is high. The five areas included in the nomination remain largely intact, maintaining their appearance during the period of significance. With few exceptions, changes to the exterior of buildings, to the landscape, and to the overall site plan (e.g., the location of roads) are small. Although in some cases new development has been located near the historic areas (for instance, the new housing area at Big Meadows), these areas are sufficiently distant that they do not affect the historic resources.

There are, however, a few areas where there has been new construction. As noted below, there have recently been major intrusions into the Headquarters maintenance area. One new building now dominates the setting and is significantly out-of-scale as compared with the surrounding buildings. Although on balance the area still maintains integrity, further intrusions could jeopardize the area's ability to convey its historic significance. Another area that has been altered adversely by new construction is the wayside area at Big Meadows. Here the wayside building has been significantly

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 3

---

The boundary addition area includes buildings, sites, structures, and objects. Over 90 percent of the contributing resources in the nomination date from between the mid-1930s and the early 1940s. All were constructed either by the federal government (most by the National Park Service) or by the park concessionaire, Virginia Sky-Line, Inc. Resources constructed by Virginia Sky-Line were designed by Richmond architect Marcellus Wright, Jr. They vary from cabins and multi-unit "cottages," to a lodge, and road-side restaurants/coffee shops. Resources built by the National Park Service (often with Civilian Conservation Corps [CCC] labor and funding from other Depression-era programs) include sites (picnic grounds, a campground), buildings (maintenance/utility buildings, residential buildings for employees, and an administration building), structures (various roads), and objects (water fountains). The few contributing resources constructed outside the mid-1930s to early-1940s period include 19th-century and early 20th-century residences at the Headquarters area and a mission at Simmons Gap. Most of the contributing resources are in the Rustic style.

The boundaries of the addition to the National Register district as described in this nomination, include an area 125 feet on either side of the pre-1950 roads in each of the five areas. (See Sketch Plans) For the Headquarters, Big Meadows, and Dickey Ridge areas this includes all roads shown on the 1930s-era master plans. For the Simmons Gap and Piney River areas this includes those roads leading to contributing resources.

### **SUMMARY ARCHITECTURAL DESCRIPTION**

The contributing buildings included in the boundary addition area may be grouped into three categories: 1) a small group of vernacular pre-park resources; 2) buildings constructed by the federal government (either the National Park Service or the CCC); and 3) buildings, largely accommodations and restaurants, constructed by the park's concessionaire, Virginia Sky-Line, Inc.

The pre-park resources date from the late 19th and early 20th centuries. They include two residences with outbuildings located in the Headquarters area, and a mission building at Simmons Gap. These resources are vernacular structures typically found in the mountain areas of Virginia but are more particularly characteristic of the many resources that pre-dated the park but were demolished within a few years of the park's opening. Materials used in the buildings include local stone (for walls and foundations) and milled lumber (for walls). Original roofing materials were generally standing-seam metal.

Most of the contributing buildings included in the nomination were constructed by the federal government between 1934 and 1943, with all but a handful being constructed in four years (1937, 1938, 1939, 1941). The earliest of these resources are a few offices, and/or utility buildings



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 5

---

altered, a new service station (1961) has been added and, most importantly, the large, modern, Byrd Visitor Center (1966) which now dominates the area, has been constructed. In other areas, intrusions have generally been of a similar scale and materials to the contributing resources. For instance, although there have been new multiple-unit accommodations built at the Big Meadows Lodge area, the scale, materials, and location of the units have minimized their effect on the historic district.

### **HEADQUARTERS AREA<sup>5</sup>**

The Headquarters area is located three miles west of Thornton Gap (and Skyline Drive) and four miles east of Luray, Virginia, on U.S. 211. It is approximately one mile outside the west boundary of the park. The various developed sections of the Headquarters area are largely open although surrounded by forest. The land is flat close to U.S. 211 but rises from U.S. 211 northward. The section of the Headquarters area embraced by this nomination includes approximately 24 acres. This constitutes only a portion of the 259.16-acre original parcel purchased for the administration area.

There are four sub-sections of the Headquarters area included in this nomination, all of which are contributing elements to the historic district. They include the administration area (including the Headquarters building), the residential area, the maintenance/subheadquarters area, and the Superintendent's residence area. A half-mile-long, curved, unnamed, access road (herein referred to as Headquarters Road) links the areas. This road, which leads north from Route 211, was part of the original master plan for the area and is a contributing feature to the historic district. On the east side of the road at its intersection with Route 211 is the administrative area. This area includes the Headquarters building, which fronts on Route 211, and two associated parking areas. Farther north, two side roads, both contributing elements to the historic district, branch off from either side of the Headquarters road. The side road to the east leads to the Superintendent's House and the associated ancillary buildings. The road on the west provides access to the residential area. The Headquarters Road terminates in a deadend at the maintenance area.

---

<sup>5</sup>Although nearly all built resources in the National Register boundary addition area have been specifically described below, some categories of small temporary noncontributing structures such as dog pens, hose houses, and pit privies (which date from after the period of significance) have not been individually mentioned.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 6

---

Headquarters Administration Area

The one contributing building within the administrative sub-area and one of the major contributing resources within the boundary addition, is the **Administration Building (HQ-0101) (1940) (Contributing)**.<sup>6</sup> The Administration Building, which is located approximately 175 feet to the north of U.S. Route 211, faces south and has a wide front lawn that extends to U.S. 211. The rear of the building is set into a small knoll. The building is a two-story stone structure with an attic and basement. It has concrete foundations, and a slate roof. It consists of a traditional "I" house central section and several separate one-story gable-roofed sections on either side. The central section of the building is five bays wide with a one-story wood porch. To the west of this section is a two-bay-long, one-story gable-roofed section. To the east of the central section is a longer section that in turn is composed of a narrow one-bay "hyphen," a projecting one-bay-wide, cross-gable section, and a final three-bay-wide, gabled-roof section. A long (five-bay) wood addition to the building extends from the rear of the west side of the building.<sup>7</sup> Windows on the first floor of the building are six-over-nine, double-hung wood sash. Windows on the second story of the building are six-over-six. Flat arches are used above all of the window openings.

The sandstone used in the building was locally quarried. It is rough-faced ashlar laid up in a random pattern. Interior bearing walls are brick and partition walls are concrete block. The central two-story section of the building has steel trusses and purlins. Flashing and gutters are of copper. The roof is of random-width slate shingles.

Major spaces in the building (all on the first floor) include the lobby, the conference room, and the superintendent's office. The interior of the building is distinguished by the use of chestnut wainscoting and paneling in the lobby, conference room, and the superintendent's office. The chestnut used in the building came from local trees killed by the chestnut blight, cut and milled by CCC labor. Other wood work is yellow pine. Floors are of terrazzo (bathrooms), flagstone (porch),

---

<sup>6</sup>Where resources have previously been determined eligible or not eligible for the National Register by the Virginia Department of Historic Resources this fact is noted as "**Determined Eligible**" or "**Not Eligible**." Where resources have not previously received determinations of eligibility, "**Contributing**" or "**Noncontributing**" has been noted. Discussion of integrity issues has been included only for resources which have not already been determined eligible or not eligible.

<sup>7</sup>The addition was constructed soon after the building was completed and is located on a site set out for a separate building with the same use in the original master planning of the area.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 7

---

and red oak (all other rooms).

The building has received minor alterations but its integrity remains unimpaired. The rear addition was constructed immediately after the construction of the main portion of the building and is a contributing element of the building.

Two parking areas are associated with the original design of the area and are contributing elements to the historic district. One, which is intended for public use, is located near an information kiosk directly off Route 211 slightly to the east of the Headquarters Road. The other parking area is located to the west of the addition wing of the Administration Building. (A parking area farther to the north is not part of the original plan and is not a contributing resource to the historic district.)

Other historic landscape elements associated with this area that are contributing features to the district include the large grassy area to the south of the Administration Building. Historic photographs of the area taken in the 1940s show that the area has always been open. The photographs also show the area behind the Administration Building heading towards the Superintendent's office was largely open with only intermittent trees.

### Headquarters Residential Area

The residential area is located on the west side of Headquarters Road, roughly halfway between the Administration Building and the end of the road. It consists of a kidney-shaped area surrounded by a loop road (a contributing resource to the historic district). Ten houses are located in alternating positions on either side of the road. Landscaping in the area consists of grassy lawns and a variety of small shrubs and both evergreen and deciduous trees. Many houses have foundation plantings. The area behind the open area around the houses on the exterior of the loop is wooded. Historic photographs suggest that soon after its creation the area was largely open both within and outside the loop. Primary contributing buildings at the Headquarters residential sub-area include one pre-park residence and three early 1940s houses.

The one pre-park resource is **Residence (HQ-0217) (1916) (associated Garage HQ-0324 and Storage/Shed HQ-0421)(All Determined Eligible)**. This is a two-story modified wood "I" house with both rear and front one-story projecting additions. The building has painted clapboard siding, stone foundations and a gable-end exterior chimney. The roof on the main part of the building and that on the addition are both standing-seam metal. The front facade features a covered porch that extends across half of the facade. Although the interior of the building has been altered, the exterior still retains much of its original appearance. This building was constructed outside of the district's

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 8

---

period of significance. However, the building is one of very few buildings that was not removed when the park was established. Thus it is significant as a tangible reminder of the effort to return the park to its condition before human occupation. The building has also been in continuous occupation for National Park Service functions since the establishment of the park. Because the building was present during the period of significance, relates to the documented significance of the district, and possesses historic integrity it should be considered a contributing resource to the historic district.

The three early 1940s houses in the residential area include: **Residence (HQ-0203) (1941) (and associated Garage HQ-0303) (Determined Eligible), Residence (now Offices) (HQ-0204) (1941) (and associated Garage HQ-0310) (Determined Eligible), and Residence (HQ-0208) (1942) (and associated Garage HQ-0308) (Determined Eligible).** Designed by the same architect -- G.R. Baughan -- and constructed around the same time, these three houses all are side-gable structures with wood siding, slate roofs, and prominent sandstone chimneys. All have identical wood frame garages with distinctive segmentally arched double doors and strap hinges. All three buildings also echo local building traditions. Two of the houses (HQ-0204 and 0203) were originally identical. They are small Colonial Revival, hall-and-parlor type structures<sup>8</sup> with an attached, recessed side section and a rear screened porch. HQ-0208, influenced by local traditional cabin designs, is a rectangular structure with an integral front porch that runs along five bays of the six-bay wide house. These three buildings have received very little exterior alteration.

Noncontributing resources at the Headquarters residential area include six ranch-style houses completed in the late 1950s and early 1960s. All have been evaluated by the NPS and VASHPO and found not eligible for the National Register. They include: **Residence (HQ-0202) (1959) (Not Eligible), Residence (HQ-0205) (1959) (Not Eligible) Residence (HQ-0207) (1959) (Not Eligible), Residence (HQ-0209) (1959) (Not Eligible), Residence (HQ-0225) (1960) (Not Eligible), Residence (HQ-0226) (1960) (Not Eligible).** These buildings are slab-on-grade wood frame buildings with attached carports. They were constructed as part of the Mission 66 program.

### Headquarters Superintendent's Residence Area

The Superintendent's Residence area is reached via a small road located on the east side of the

---

<sup>8</sup>The houses are similar in form to the "Cape Cod" cottages that were popular throughout the country.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 9

---

Headquarters Road.<sup>9</sup> It consists of the pre-park **Superintendent's Residence (HQ-0218) (19th c.) (Determined Eligible)** (now offices) and associated outbuildings (**Garage HQ-0323 and Storage/Shed HQ-0420) (Determined Eligible)**. The buildings are set in a grassy lawn area. Various shrubs are used as foundation plantings and two large trees frame the entrance to the building. Photographs taken soon after the construction of the rest of the Headquarters area show large trees clustered around the front (west) and south facades of the building. Aside from these, the area is largely open on both sides of the access road.

The front portion of the Superintendent's Residence is in the traditional "I" house form. However, the house extends to the rear in a two-story section with twin, cross-gable roofs. Beyond this section, projecting one-story additions house a covered porch and utility and conference rooms. The building has painted clapboard siding and a standing-seam metal roof. The building has been significantly altered in both the interior and exterior, however it retains sufficient integrity on the exterior to be considered an eligible resource. Although this building was constructed outside the district's period of significance, its significance relates to the fact that it is one of very few standing pre-park buildings and to the fact that it has been in continuous use by National Park Service. Most significantly, it served for many years as the park superintendent's residence. Because the building was present during the period of significance, relates to the documented significance of the district, and possesses historic integrity it should be considered a contributing resource to the historic district.

HQ-0323 and HQ-0420 are both outbuildings associated with the superintendent's residence. HQ-0323 is a wood frame garage/shed with board-and-batten siding and an open-air carport attached to the east facade. Building HQ-0420 is a one-room wood frame storage building with clapboard siding. These buildings have received only minor alterations.

### Headquarters Maintenance Area

The maintenance area is located at the end of the Headquarters Road and to the north of the other sections of the Headquarters area. It consists of a roughly rectangular, open area housing a collection of 15 rectangular buildings, most dating from the late 1930s and early 1940s. Many of these buildings are of random rough-faced ashlar sandstone that echoes that used in the

---

<sup>9</sup>Although not part of the original National Park Service master planning of the area, the road, like the Superintendent's residence, has been used continuously for park purposes since the early days of the park, and thus should be considered a contributing feature of the historic district.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 10

---

**Administration Building.** Two buildings have recently been added to the area. The large Maintenance Building (HQ-0457) located in the center of the area now dominates the complex. It is located on the site of what was to be the machine shop. The I&M/Archives Building (HQ-0103) is a smaller building located to the east of the main maintenance area. In terms of historic landscaping, early photographs of the maintenance area show it to be open as it is today.

Contributing resources in the maintenance area include eight buildings constructed on-site or moved to the location for use as maintenance buildings. Most of the buildings have received only minor alterations, and all still retain the elements of integrity.

The **Equipment Storage and Workshop (HQ-0401) (1940) (Determined Eligible)** is a long, gable-roofed garage structure with exterior walls of random (rough-faced) ashlar sandstone. It has concrete foundations and concrete roof shingles. The building is composed of three sections, the end sections of which are slightly recessed and slightly lower than the central section. The central section consists of five bays, four of which were infilled in the 1940s. Each of the side sections consist of four bays one of which has been infilled. Bays that are not infilled have wood overhead garage doors. Despite the alterations to the bays, the building still retains much of its original appearance.

The **Equipment Storage Shed (HQ-0403) (1940) (Determined Eligible)** is a simple, long, garage-type structure of random (rough-faced) ashlar sandstone. It has concrete foundations and its shed roof is covered with metal roofing. It has 12 open vehicle bays.

The **Warehouse (HQ-0406) (1940) (Determined Eligible)** is of rough-faced ashlar sandstone with random-width concrete roof shingles, and concrete foundations. It consists of a one-and-one-half-story rectangular section (originally housing offices, a tool room, a stock room, a checking room, a receiving room, a bathroom, and a large storage room) and a one-story ell section originally intended to store lumber. The attic of the main section of the building originally was used for storage. Windows throughout the building are multipane steel sash. Floors are concrete or wood, and window sills are pre-cast concrete. Partition walls are hollow concrete blocks. The main section of the building is 12 bays long (160 feet). Minor alterations were made to the attic storage room of the building for use by the Smithsonian Institution during World War II.

The **Gas & Oil Storage (HQ-0409) (1943) (Determined Eligible)** is a small, square, concrete-block building. Its pyramidal roof is covered with concrete shingles and features a tall ventilator at the peak. The building was intended to have a stone exterior similar to other buildings in the area, and the ties intended to fasten the stone to the exterior are still visible. Windows in the building are

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 11

---

fixed-pane steel sash. Part of the front of the building is an open porch area that houses gasoline pumps. The building was designed to store flammable materials including oil and paint.<sup>10</sup>

The **Workshop/Garage (HQ-0422) (1933?/38) (Determined Eligible)** is a long, narrow, frame building with five vehicle bays with hinged double doors. The walls are of wood lap siding. The building has a gable roof covered with rolled asphalt. The building was constructed by the CCC and moved to its present location. The building has achieved significance at its current location and therefore retains integrity of location.

The **Sign Shop (HQ-0426) (1942) (Determined Eligible)** is a long, narrow, frame building that has been added onto numerous times. The original portion of the building was a 20' x 20' square building with a partial porch. Later additions have lengthened the building by approximately 26 feet. The original portion of the building has a gable roof and other portions of the building have gable or shed roofs. All of the roofs are covered with rolled asphalt. Although the building apparently was constructed by the CCC as a pay masters office and moved to its current location, it has achieved significance at its current location and retains integrity of location.

The small, frame **Paint Shop (HQ-0427) (1935) (Determined Eligible)** consists of an original gabled-roof section and a shed-roofed addition. The building is covered with German siding. The original section of the building, which was moved from the Pinnacles area, consisted of three bays -- two windows on either side of a central wood entrance door. The building was altered by the addition of a wood sliding garage door that replaced the wood door and one window. Windows on the addition are six-over-six, double-hung wood sash.

The **Storage Building (HQ-0440) (c.1925) (Determined Eligible)** is a small vernacular frame structure with an overhanging gable forming an open porch. The building has stone piers and lap siding. The building may have originally been located near the Superintendent's house.

Noncontributing resources in the Headquarters maintenance area date from the 1950s, 1960s, 1980s, and 1990s. A majority of the buildings have been evaluated by the NPS and VASHPO and found not eligible for the National Register. Most are small utilitarian structures. One of the more

---

<sup>10</sup>The building was originally intended to house a heating system for the storage area of the warehouse which was being used to house the Smithsonian collection. The two buildings were to be connected via an elevated pipe conduit. However, the heating plant was not available and the building never functioned as such.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 12

---

substantial structures is the **Office (HQ-0102 1989) (Not Eligible)**, a 50' x 24' modern frame structure constructed on temporary blocks. The largest structure in the grouping is the **Maintenance Building (HQ-0457) (1995)(Noncontributing)**. The building is located in the center of the complex on the site of what was to be the machine shop. It is a tall, steel-frame building with a large gable roof and large flat-roofed dormers. An unusual feature of the building is that although the roof extends the length of the building, the walls of the northern half of the building are not enclosed and this portion of the building is used as a storage shed for large equipment. (This area may be enclosed later.) The enclosed portion of the building has stone veneer siding. The height and massive footprint of this steel-frame building make it the dominant feature of the maintenance complex. A third major noncontributing building is the **I & M/Archives Building (HQ-0103) (1995)(Noncontributing)**. It is located slightly to the east of the main portion of the maintenance area. This modern rectangular building of frame construction is built into a hill so that the rear of the building (facing the rest of the maintenance area) has two stories above ground and the front facade consists of a single story. The building has a gable roof and wood siding at the first-floor level and stone veneer at the basement level. Windows throughout are one-over-one double-hung sash. The front facade has six nonsymmetrical bays. A simple, one-bay-wide porch shelters the front door.

The following noncontributing structures at the Headquarters maintenance area are small modern wood frame structures: **Storage Shed (HQ-0477) (1961) (Not Eligible)**; **Materials Storage (HQ-0478) (1962) (Not Eligible)**; **Hose Shed (HQ-1602) (1950) (Not Eligible)**; **Chlorinator (HQ-1722) (post-1966) (Not Eligible) Shed for Sign Shop (HQ-0490)(1970) (Noncontributing)**. The **Community Dial Office (HQ-0454)(Noncontributing)(1957?)**, a concrete-block building housing telephone-related equipment is located slightly to the south and west of the main portion of the maintenance area.

## **BIG MEADOWS AREA**

The Big Meadows area is located at Milepost 51, in the central district of Shenandoah National Park, 20 miles south of Thornton Gap. The area included in the nomination -- the developed section of Big Meadows -- consists of approximately 118 acres. The site was named for the open meadows in the area that were historically used for grazing. The Big Meadows area, which lies on the south slope of Black Rock Mountain, ranges in elevation from approximately 3,720 to 3,570 feet. There are important views of the meadowland (from the wayside) and of the valley to the west (from the Lodge, and Doubletop, and Rapidan dwelling units).

There are five sections of the Big Meadows area included in this nomination: the Lodge/cabin area, the campground area, the picnic area, the Visitor Center/Wayside area, and the maintenance area.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 13

---

These areas are linked to each other via an unnamed access road (hereinafter "Big Meadows Road") that extends from Skyline Drive, to the Lodge and campground areas. The Big Meadows Road is part of the original master planning for the area<sup>11</sup> and is a contributing resource to the historic district. It is approximately a mile long and 20 feet wide. Adjacent to the road's intersection with the Drive is the Wayside/Visitor Center area. Slightly beyond this is the intersection with a separate curvilinear road that provides access to the parking areas for the Visitor Center/Wayside and then leads back to the west side of the Drive. Farther along, the next road intersecting Big Meadows Road leads to the sewage treatment plant. The sewage treatment area dates to 1978, and is not included in this nomination. The next intersection is with a side road that leads to the maintenance area<sup>12</sup> on one side and a road that leads to a housing area for park employees on the other.<sup>13</sup> Slightly farther on is an intersection where the side road that leads to the campground/picnic area splits off and the end of the loop road from the Lodge/cabin areas intersects Big Meadows Road. Both of these intersecting roads are contributing resources to the historic district. Big Meadows Road ends at the circular drive in front of the Big Meadows Lodge. On the other side of the circle is the parking area for the Lodge and cabin area. The parking area is divided by an island and on its far side the loop road leads off which provides access to the employee housing area and later intersects Big Meadows Road.

#### Big Meadows Wayside/Visitor Center Area

The Wayside/Visitor Center area is located along the west side of Skyline Drive. It consists of the Byrd Visitor Center to the north, the Wayside complex in the middle, and the service station to the south. Behind this grouping to the west is a parking area consisting of two areas separated by an island planted with trees and low vegetation. The Wayside area originally consisted only of a (smaller) wayside building and an accompanying gas pump area. With the construction of the large, modern, Byrd Visitor Center in 1966, the general appearance of the area has been significantly altered. In terms of historic landscaping, contemporary photographs show a variety of foundation

---

<sup>11</sup>Early (1937, 1940) plans of the area illustrate a different road pattern around the wayside area. They show Big Meadows Road intersecting Skyline Drive to the north of the wayside area with the wayside area being accessed via a separate semi-circular drive from Skyline Drive.

<sup>12</sup>The road is a contributing feature of the historic district.

<sup>13</sup>This area was developed in the 1990s for employee housing. Because of its late date, it is not included in this nomination.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 14

---

planting around the Wayside Building and mature trees and bushes planted in the island between the parking areas.

The only contributing resource in the Wayside/Visitor Center area is the Wayside itself.

The **Wayside (BM-0113) (1939) (Contributing)** is a wood-frame building with an irregular footprint and complex massing that reflects the many alterations made to the building since its construction in 1939. The building is entered through the west side, which consists of cross-gabled sections at either end and a center low section that houses the dining room. Portions of this facade, along with portions of the south facade, are covered with horizontal wood slab siding. The only original portion of the building that is now visible is located on the southwest corner of the building. This wing has always housed the bathrooms. Windows on this facade are varied, some being six-over-six double-hung sash and some being fixed single-pane glass. The other major facade of the building -- the east facade that faces Skyline Drive -- is entirely post-1950 construction and the most visible portion of the building is covered with modern horizontal siding. It also features small, high, single-pane fixed windows. Major additions/alterations to the building were made in 1957, 1959, and 1961. In general these changes have added to all sides of the building and have more that doubled the area of the building. Although the building's integrity has been seriously compromised by its many alterations, the original sections of the building remain largely intact and the alterations are considered reversible as the original structural frame is still in place. Overall, the building, even in its altered condition, still conveys much of the original design intent. The building retains integrity of location, setting, feeling, and association.

Although today the plan of the Wayside Building has been altered so that it no longer has views of the meadows, the building was sited specifically to take advantage of such views. Originally, the lunch room was located on the south facade and diners could enjoy views of the meadowland while eating. For this reason, the vista from the south facade of the building across Skyline Drive to the meadows area is an important element of the historic district.

Noncontributing resources in the Wayside area include two buildings both of which fall outside the period of significance.

The **Byrd Visitors Center (BM-2302) (1966) (Noncontributing)** is one of the largest of the recent buildings constructed at the park. This modern split-level building which dates to 1966, features a low pitched roof and large, sealed, plate-glass windows. The facade of the west (main entrance) side of the building is of exterior plywood and stone construction. It is largely "closed" with few windows or openings aside from the main entrance. On the east side of the building on this floor, the main

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 15

---

visitor areas look out through large glass windows over the meadowland. This facade of the building is largely glass and stone.

The **Service Station (BM-0374)(1961) (Noncontributing)** is a small, modern, concrete-block building with a shallow hipped roof. The front facade consists of four, large, plate-glass panels, and a single central entrance. The side and rear facades consist largely of concrete blocks.

Two small storage buildings for ice and garbage are located immediately adjacent to the wayside building. Both are recent and are of concrete-block construction: **Ice Storage (BM-0381) (1971) (Noncontributing)** and **Wayside Garbage Storage (BM-0390) (Noncontributing)**.

### Big Meadows Campground Area

The picnic/campground area is reached by a spur road off Big Meadows Road. This spur provides access both to the campground area and the picnic grounds and amphitheater. It is a contributing resource to the historic district.

The campground area has two major loop systems that create separate but adjacent camping areas (Area P-T and Area U-Y). Both areas, which are located off a common entrance road, consist of a major one-way loop road crossed by multiple one-way roads that divide the areas into separate tiers.

The original campground area -- a contributing feature to the historic district-- is the more northerly loop. It consists of a generally fan-shaped peripheral loop bisected by four parallel loop roads. The five camping areas are now called areas "U," "V," "W," "X," and "Y." An unusual feature of this campground area is the fact that rather than having pull-in car parking areas for each site, most sites have parking areas that span the width of the loop and provide access to campsites from two roads. This design allows use by travel trailers, which can pull into the sites and exit without backing up. The most northerly tier (certain "X" and "Y" sites) have the more traditional pull-in spots. There are scattered other pull-in sites at the far northern and southern ends of the loop. Original log comfort stations are located in the third ("W") and fourth ("X") tiers. All sites include wood picnic tables with metal supports, and a firegrate. The picnic tables and firegrates are replacements and are not original to the site. The four water fountains in this area, which appear to be original to the site, are of the "boulder" type. They consist of a single large boulder through which a pipe and bubbler have been added. (Some also include a spigot for water.) Trees and shrubs are used to screen and provide privacy between campsites. At the time it was constructed, the campground

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 16

---

included 50 trailer sites, 20 tent sites, 20 firegrates, 50 tables, and 6 fountains. In addition to the general layout of the original campground area (including the location of the checking station, roads, camp sites, and comfort stations) contributing landscape features include paths and the fountains/water pumps. Historic photographs reveal that as the time it was constructed, many of the loops in the campground area, like the rest of the meadow area, were largely open.

In the 1960s, an additional loop of camping sites was added to the south of the original loop. This area falls outside the period of significance and does not contribute to the historic district. The loop, which is larger than the original loop, is divided into four tiers (incorporating areas "P," "Q," "R," "S," and "T"). It consists entirely of sites with pull-in parking. Walk-in sites are located off the peripheral loop to the east and the south. With the new loop and additional walk-in sites, the campground now has over 200 tent sites and 20 recreational vehicle sites.

Contributing buildings to the historic district in the Big Meadows campground area include a visitor contact station and two comfort stations.

The **Campground Contact Station (BM-0705) (1939) (Contributing)** is a small log building with stone and mortar foundation. The walls of the building are of squared, v-notched logs with mortar chinking. The building's pitched roof, originally covered with chestnut shakes, now has replacement asphalt shingles. The building features a large fieldstone exterior chimney on the south side. The front (west) facade of the building has two low window openings and a door. The middle window currently functions as the service window. An employee's entrance to the building is also located on the north side of the building. A porch, supported by metal poles, covers the entrance area of the building. This porch is not an original feature of the building. In addition, changes have also been made to the fenestration pattern. (The front elevation originally held a central entrance and two flanking windows). Original plans for the building indicate that the chimney was intended to be on the opposite (north) side of the building. Overall, the building still retains much of its original exterior appearance.

The identical **Campground Comfort Stations (east) (BM-0509) (1937)** and **(west) (BM-0508) (1937) (Contributing)** are located on the campground's "W" and "X" tiers respectively. They are rectangular log structures with pitched roofs. The exterior walls are of squared logs, joined using V-notches. Their roofs, originally of chestnut shake shingles, were replaced with concrete shingles in 1949. The entrances to the buildings are located on their two long sides. Walls, also constructed of squared logs, screen the entrances to the buildings. Each of these facades also features multi-pane windows that are hinged at the bottom to swing inward. Windows are also located on the side elevations. The buildings have stone and concrete foundations. Plans for the buildings, entitled "Standard

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA  
Section number 7 Page 17

---

Comfort Station, Shenandoah National Park" were drawn by A. Paul Brown. Although they have been altered in the interior (for instance, replacement of plumbing fixtures, etc.), on the exterior the buildings are basically unaltered.

Noncontributing resources in this area include modern comfort stations and other utilitarian buildings. **Comfort Stations Campground (BM-0541, 0542, 0543) (1961) and Comfort Stations Campground (BM-0551, 0552, 0553) (post-1966) (All Noncontributing)** are all undistinguished, modern, concrete-block buildings. There are also three noncontributing buildings located in an area between the campground and picnic areas. The **Laundry & Service Building (BM-0356) (1966) (Noncontributing)** is a modern, L-shaped one-story concrete-block building housing a laundry, a store, and other campground-related functions. The **Wood Sales Building (BM-0393) (Noncontributing)** is a wood, shed-type building used to store firewood. The **Shower Building (BM-0398) (Noncontributing)** is a modern concrete building which houses showers for the use of campers.

### Big Meadows Picnic Area

The picnic ground, a contributing element to the Historic District, is a roughly circular area located off the spur road leading to the campground. It is located to the north and west of the campground. The circular road that surrounds the picnic area has three parking areas distributed around it. The picnic sites, most of which are located inside the loop road, include non-original picnic benches and fireplace units in a semi-wooded setting. The modern (noncontributing) amphitheater is located roughly 150 feet from the picnic area, and is reached by footpath. In addition to the general layout of the picnic area (including the location of the access road, parking areas, and comfort station) contributing landscape features include the path system and the boulder drinking fountains. Historic photographs indicate that when it was created, the picnic area was largely open.

Contributing resources in the Big Meadows picnic area include a single comfort station.

The **Picnic Area Comfort Station (BM-0507) (1937) (Contributing)** is located roughly in the center of the picnic grounds. It is a rectangular log structure with a pitched roof. The exterior walls are of squared logs, joined using V-notches. The roof, originally of chestnut shake shingles, was replaced with concrete shingles in 1949. The entrances to the building are located on the two long sides of the building. Each of these facades also features two fixed multi-pane windows. Two such windows are also located on the sides of the building. The building has stone and concrete foundations. The building has received few alterations.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 18

---

Noncontributing resources include the modern, open-air **Amphitheater (BM-AMPH)(c.1978) (Noncontributing)**, the **Projection Booth (BM-0467)(1956)(Noncontributing)** and a **Pit Privy (BM-2464)**.

Big Meadows Lodge/Cabin Area

The Lodge/cabin area of Big Meadows has the largest number of built resources of any section of Big Meadows. The area is accessed via Big Meadows Road, which ends at the circular drive in front of the Lodge. On the opposite (northwest) side of the circle is a parking area that incorporates a segment of the road that eventually leads back to Big Meadows Road. The parking area, which is divided in the center by a wooded island, provides parking for the Lodge, for the cabins and multi-unit accommodations located to the north, and for the multi-unit accommodations to the south. The road curves back around the end of the multi-unit accommodations and provides access to employee housing that is located on both sides of the road to the east of the multi-unit housing. The road continues and intersects Big Meadows Road across from the campground/picnic area entrance. The road system in the Lodge area is part of the original master planning for the site and is a contributing element to the historic district. As was apparently true when the site was developed, the Lodge/cabin area is largely wooded, with openings around the buildings. The Lodge Building, and the Rapidan and Double Top multi-unit guest accommodations are at the western edge of the ridge and have views into the valley. The vistas were primary determinants of the siting of each of these buildings and they are important elements of this portion of the historic district. A playground is located to the south and west of the Lodge entrance circle. It is not part of the original master planning for the site and is not a contributing feature of the historic district.

Contributing resources in the Big Meadows Lodge/cabin area include the Lodge and a number of smaller cabins.

The **Lodge (BM-0114) (1938-39) (Determined Eligible)** is the primary resource in this area and one of the major resources included in this nomination. It, like the Dickey Ridge Lodge, was designed in a rustic style by Marcellus Wright, Jr. Like Wright's other buildings at the park, this building is characterized by complex massing incorporating a number of component parts of different materials and with varying roof forms. These elements are attached to form a curved composition that echoes that of the entrance drive. The effect of the massing and materials is to lend a domestic quality to the design. The building is two stories high (with a partial basement) and is of masonry and wood frame construction. The foundations of the building are concrete, and the exterior walls are of sandstone and wood siding. Concrete shingles (original to the building) are used on all original

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 19

---

sections of the building.

The main entrance to the building is the central front-gabled section located in the middle of multiple side-gabled components. To the east, three sections each with dormers and end gable chimneys step downward. To the west, the portion of the building adjacent to the entrance consists of a long area housing the dining room. This area has an overhanging roof that forms an integral porch and a massive central chimney running parallel to the roof gable that pierces the roof. At the end of this area is the projecting cross-gabled store area. Two smaller stepped segments of the building lead off to the east of this section.

The entry area of the building is of stone construction at the first-floor level and of horizontal (flitched) siding at the second-floor. On either side of the entrance are a single (vertical) row of glass blocks. The judicious use of glass blocks is characteristic of Wright's work at Shenandoah. Above the entrance doors at the second-floor level is a narrow decorative wood balcony. A single 12-over-12 double-hung sash window is centered above the balcony.

The rear elevation, facing the valley, features a flagstone terrace that runs most of the length of the building. Part of the structure rests on masonry piers and part is supported by the basement level walls.

The building contains 62 guest rooms and 32 baths, in addition to the registration, dining, gift shop, and lobby areas. Materials used in the interior include chestnut paneling and stone masonry for the walls, chestnut sheathing for the ceiling, and tongued and grooved oak and/or waxed flagstone flooring. The major spaces include the lobby, the sitting room (labeled "concessions" in the original drawings) located off the foyer at the rear of the building, and the dining room located off the foyer to the west. Both the sitting room and the dining room are open to the second-floor ceiling and the building's massive scissor-trussed chestnut timbers. These rooms also feature ten-foot-long stone fireplaces with heatilators.

The Lodge has received a number of alterations since its construction. Most of the alterations, however, were made to areas of the buildings not visible from public spaces. Alterations to the kitchen area, including the addition of a preparation room were made in 1959-1960 and exterior stairways were added to meet life and safety codes in 1994-95.

Immediately adjacent to the Lodge is the small, frame, **Can Storage Building (BM-0382) (1961) (Noncontributing)**.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA  
Section number 7 Page 20

---

Other contributing resources in the Lodge area include a group of five cottages that were the first built resources in the area. They are located to the south and west of the Lodge. Designed by Marcellus Wright, Jr., these include **Petersburg Cottage (BM-0149) (1938)**, **Bridesburg Cottage (BM-0153) (1938)**, **Blacksburg Cottage (BM-0152) (1938)**, **Lynchburg Cottage (BM-0155) (1938)**, and **Mountain View Cottage (BM-0154) (1938) (all contributing)**. These simple wood frame cottages -- originally identical -- include two separate housing units. The T-shaped buildings have hipped roofs on the main section of the building and a separate hipped roof on the wide "T" section. The entrance to the buildings is also through this section. Windows on the buildings are eight-over-eight double-hung sash. The buildings were constructed with flitched-edge wood siding and masonry piers. On the interior, the buildings feature a large stone chimney with hearths opening into both main rooms. The Mountain View cottage is the most altered of the five cottages. A covered porch has been added to one side of the building, and a bedroom and bathroom were added onto the other side. The siding on the Blacksburg and Petersburg cabins has been replaced with standard horizontal wood siding but otherwise the buildings are little altered on the exterior.

The **Linen Storage Building (BM-0324) (Pre-1939) (contributing)** is a very small, frame structure used for storage and located near the cabin area.

A series of multiple-unit accommodations are located in a line to the south of the Lodge and on the opposite side of the parking area from the cabins. Three of the four eight-unit structures (**Piedmont Cottage (BM-0115) (1941)**, **Blackrock Cottage (BM-0116) (c.1946)**, and **Hawksbill Cottage (BM-0117) (c.1946)**) are contributing resources to the historic district. All are wood frame buildings with concrete foundations. The buildings have gable roofs with cross gabled sections on either end and a porch running along most of the length of the building. The units are covered with vertical board-and-batten siding. The buildings, which were designed by the Richmond firm of Ballou and Justice, have not been altered significantly.

Located near the point where the loop road returns to Big Meadows Road are a group of five small cabins that are currently used for storage but previously were used as employee housing. All were moved from the Swift Run area, located in the park's central section.<sup>14</sup> Four of the cottages,

---

<sup>14</sup>Swift Run Gap was one of three major historic routes across this section of the mountains. When the park was established, there were a number of commercial operations located at the Gap (by this time U.S. 33's crossing of the mountains). Tourist cottages from one of these establishments were eventually moved by the National Park Service to the Big Meadows site.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA  
Section number 7 Page 21

---

**Employee Cottage "B" (BM-1157) (Pre-1933), Cottage "C" (BM-0314) (Pre-1939), Cottage "D" (BM-0315) (Pre-1939), and Cottage "E" (BM-0316) (Pre-1939) (all contributing)** are identical, frame, two-room cottages with an attached bathroom in the rear. All are side-gable structures with double entrances on the long side and either six-over-six or replacement one-over-one double-hung windows. The frame buildings have concrete-block foundations and are covered with horizontal wood siding. Small porches supported by thin posts which were original features of the buildings, have been removed. In addition, the current bathrooms, added to the rear of the building, replaced smaller bathrooms located inside the buildings. **Employee Cottage "A" (BM-1156) (Pre-1933)** is similar to the other four cabins in most respects, but has only a single room and bath. Despite the minor alterations, this group of small cottages is largely intact and they still retain much of their original appearance. The buildings have achieved significance at their current location and therefore retain integrity of location.

Noncontributing resources in the Big Meadows Lodge/cabin area include resources that fall outside the period of significance.

The **Double Top Cottage (BM-0118) (1959)** and **Rapidan Cottage (BM-0344) (1963)** (both **Noncontributing**) are multiple-unit accommodations located to the west of the cottages -- toward the edge of the ridge. These units are similar in their layout to traditional motel units. The units have wood siding and concrete-block foundations. Rooms are reached through a single flight of stairs.

**Crescent Rock (BM-0397) (1986)** is another multi-unit guest accommodation of recent construction. It is similar in appearance to the Piedmont/Blackrock/Hawksbill grouping.

Five 1960s-era employee housing units (three of concrete-block and two of frame construction) are located on the loop road after it curves back around to meet Big Meadows Road. **Employee Quarters (BM-0326) (1961), Employee Quarters (BM-0327) (1961), Employee Quarters (BM-0320) (1963), Employee Quarters (BM-0396) (c. 1970s), Employee Quarters (BM-0319) (1966)** (All **Noncontributing**) are all pitched-roof, modern buildings.

Other noncontributing buildings include a small, modern storage building located near Blackrock Cottage: **Storage & Service Building (BM-0385) (Noncontributing)**

#### Big Meadows Maintenance Area

The maintenance area is located on the east side of Big Meadows Road. In addition to the cluster of maintenance-related structures, this area also includes employee apartments, a freestanding

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 22

---

employee residence, and a group of three buildings that were formerly used as stables and tackrooms. The area is reached via an access road located roughly half way between Skyline Drive and the Lodge. The access road, which is a contributing element to the Historic District, curves around to the south and ends close to the service area. Immediately to the north, a smaller road provides access to the employee housing (including BM-0214, the former Hoover School). Immediately to the south, a small road provides access to the stables area. The maintenance area, which consists of seven buildings (two of which are now attached), is a large, open, rectangular area, with buildings in a roughly U-shaped configuration. The stable area consists of four buildings (two of which are attached) also positioned in an U-shaped configuration. The original master planning for the area includes the current layout of the access road and the location of the maintenance area, employee housing area, and the stables area (originally set out as the location of the employee garage). Early photographs reveal that at least part of the maintenance area was enclosed by a wood fence.

Contributing resources in the maintenance area include most of the maintenance buildings, one of the stables-complex buildings, and the former Hoover School Building.

In general, the buildings in the maintenance area were designed with consistent rustic styling and a common palette of materials.<sup>15</sup> They are rectangular one-story frame buildings with concrete floors and footings. Their most distinctive feature is their vertical slab siding -- 3- to 4-foot vertical half-round boards arranged in multiple parallel horizontal rows. The buildings have gable roofs that were originally covered with random-width hand-riven wood shingles and most are now covered with green, roll-asphalt roofing. The gable ends of the buildings are covered with horizontal lap siding. The buildings have copper gutters and multiple-pane steel casement windows, some of which open out and some of which are fixed. Garage doors are of vertical wood board construction and have side steel strap-hinges.

**The Equipment Shed/Garage (BM-0410) (1939) (Determined Eligible)** is a garage with five vehicle bays. The bays have double doors with fixed, multi-pane windows in each door. The building has not been significantly altered.

**The Maintenance/Vehicle & Equipment Storage (BM-0411) (1939) (Determined Eligible)** is a three-part garage originally with nine vehicle bays. Although the north section was significantly altered

---

<sup>15</sup>The Office/Ranger's Quarters and the stables buildings were not designed as part of the architectural set, and use different materials and design elements.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 23

---

in 1966, the south and middle sections of the building are still intact. The bays in this section have been infilled with windows and vertical siding so the original use is no longer apparent. In the 1980s, a two-bay section connecting BM-0410 and BM-0411 was constructed using materials salvaged from the no-longer-exposed side of BM-0410.

The main section of the **Blacksmith Shop/Storage Shed (BM-0412) (1939) (Determined Eligible)** is a garage with two vehicle bays and two regular entrance doors (only the central door is original). A small section of the building that originally housed the steel sharpener and furnace is set back from the rest of the building.

The **Storage Shed (Ranger's Office) (BM-0413) (1939) (Determined Eligible)** is a long rectangular building designed as a storage facility. It originally consisted of a central open storage area with sections on either side which had two vehicle bays with double hinged doors. The end sections of the building have been altered by the infilling of the bays with vertical siding, windows and entrance doors. The center section has been altered by the cutting back of a portion (five feet) of the roof/overhang.

The **Carpenter Shop/Storage Building (BM-0414) (1939) (Determined Eligible)** is another garage-type structure with six vehicle bays. It uses the same palette of materials as the other maintenance buildings. The building is basically unaltered on the exterior.

Although **Warehouse/Storage (BM-0415) (1939) (Determined Eligible)** has a similar footprint to the other buildings in the maintenance area, it is not a garage-type structure. The west side of the building has six asymmetrical bays that include two entrance doors and three windows. The east side features a concrete loading platform that leads to two large bays with double-hinged doors. The building has a finished attic.

The **Gas/Oil Building (BM-0416) (1939) (Determined Eligible)** although employing different materials from other buildings in the area, still clearly was designed for this location. The use of random-cut ashlar stone for the walls was a function of the building use -- to house flammable materials, such as oil and paint. The building has a pyramidal roof crowned by a square ventilator. The roof, originally of chestnut shakes, is now covered with asphalt shingles.

**Stables (BM-1158) (1939) (Determined Eligible)** This building originally served as an employee garage and the front of the building had five open bays to house cars. When it was converted to a stable, the open bays were enclosed with Dutch doors. Like the other utility area buildings, this building has vertical slab siding. The stable is built into a hill and its foundations are of stone. It

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 24

---

has wood roof shingles.

**Office/Ranger's Quarters (BM-0214) (c.1930) (Previously Found Not Eligible, Now Contributing)<sup>16</sup>**

Like many other buildings in the park, this building was moved from another location. Originally constructed as a school in the south district of the park, the building was moved and altered for use as a residence in 1945. It is a frame, gable-roofed building with wood siding and concrete-block foundations. Windows are six-over-six double-hung wood sash. The building was originally constructed as the Hoover School and significantly altered for use as an employee residence.<sup>17</sup> Photographs of the school show that it was originally a narrower building with long double-hung windows and stone foundations. A small gabled porch protected the entrance. Although the exact manner of alterations is not clear, it appears that the building was added to on part of the front and the rear. Original building fabric is located on the sides and part of the front of the building. In addition, interior partition walls apparently were added.

Noncontributing resources in the Big Meadows maintenance area include apartment buildings constructed in the 1960s and stable buildings constructed in the late 1950s. All have been evaluated by the NPS and VASHPO and found not to be eligible for the National Register.

**The Apartments (BM-0725) (1966) (Not Eligible) and Apartments (BM-0726) (1966) (Not Eligible)** are identical modern apartment units constructed in 1966 for employee housing. Each long (84'8"), narrow (24'8") building houses four apartment units. The buildings are of concrete masonry construction and have low, gable roofs.

**The Tackroom-Office (BM-0321) (1959) (Not Eligible)** is a narrow rectangular concrete-block

---

<sup>16</sup>Previously this building was considered not to be eligible for listing on the National Register due to the fact that it had been significantly altered (and moved) since it functioned as a schoolhouse. However, the building has had its current appearance and current location for at least 50 years, during which time it has served various park-related functions. Given the fact that the building has achieved significance at its current location, it appears that the building, as it currently exists, should be considered a contributing resource to the historic district.

<sup>17</sup>Plans showing this early alteration have not been located. Descriptions of the original building, however, suggest that it had a schoolroom, as well as a living room, bedroom, and kitchen on the first floor.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 25

---

structure consisting of two parts attached at the roof. It was constructed in 1959.<sup>18</sup> Nearby, the **Stables (BM-0379) (1959) (Not Eligible)** is a wood frame structure with five horse stalls. The building's exterior walls are of rough-hewn boards.

### **DICKEY RIDGE AREA<sup>19</sup>**

The Dickey Ridge site is located on the west side of Skyline Drive, 4.6 miles south of Front Royal (Milepost 4.6). The developed area contains approximately 15 acres that were, at the time the area was developed, lightly wooded. The area ranges in elevation from 1920 feet to 1940 feet. It is a relatively flat area of the Drive in the middle of the continuous four-mile rise from Front Royal. There are views of the Valley and the Blue Ridge (mostly to the north and west) from the visitor center .

Developed areas within the Dickey Ridge area include three sub-areas all of which contribute to the historic district: a lodge (now a visitor center) area with associated roads and parking lots; a vacant area that was originally the location of guest cabins; and a picnic area. All areas can be reached via an unnamed road (hereinafter Dickey Ridge Road). Dickey Ridge Road is a 20-foot-wide, semicircular road located on the west side of Skyline Drive. It intersects Skyline Drive, curves around to provide access to the visitor center and parking areas, intersects with the picnic area loop, and then returns to the Drive farther to the south. Before reaching the visitor center, a road providing access to the cabin area branches off to the north. Although the cabins are no longer located on the site, the circular drive that originally provided access to them is still extant. The picnic area is also surrounded by a semicircular drive that on the north end shares a common entrance with the Dickey Ridge Road.

The area between the visitor center and Skyline Drive is open and the visitor center is visually prominent from the Drive. The area where the cabins were located is largely open inside the access road (trailers housing employees were recently parked there) and forested to the outside of the circle. The picnic area is a slightly hilly, elongated area, which rises in elevation from the access loop

---

<sup>18</sup>The two pieces of the building were constructed at different times and the two parts of the building are occasionally referred to by separate numbers. The section to the west is sometimes referred to as the Hay Storage Shed (BM-0323).

<sup>19</sup>A number of resources in the area were previously included in the Skyline Drive Historic District National Register nomination.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 26

---

and then drops down again to the Drive. It is semi-wooded with stone outcroppings. Several footpaths, which are original to the area and contributing site features, provide access from the two parking areas. Picnic tables and the accompanying firegrates are dispersed throughout. Random ashlar stone drinking fountains date to the construction of the picnic area, and are contributing elements to the historic district. The comfort station (described below) is located roughly in the middle of the picnic area.

Significant contributing buildings to the historic district in the Dickey Ridge area include the lodge building and a comfort station in the picnic area.

**The Visitor Center (Lodge) (DR-2301) (1938) (Determined Eligible)**, a one-story (plus partial attic) multi-section building, is the main built resource at the Dickey Ridge area. It was constructed in 1938 by Virginia Sky-Line, the park concessionaire, and designed by Marcellus Wright, Jr. It was built as a restaurant for visitors staying at the nearby cabins and for visitors in the north district in general. It was converted into a visitor center in 1958 at which time the projection room on the northwest was added. It is a frame building with concrete and stone foundations. The exterior walls are of local stone and wood siding and the roof is covered with concrete shingles. Most windows in the building are six-over-six double-hung sash, although there are also a number of large picture windows consisting of fixed multi-pane windows.

Like much of Wright's other work in the park, the building was sited to take advantage of views off of the mountain. Also like Wright's other work, it uses somewhat complicated, additive massing to achieve a vernacular domestic quality that fits into the landscape. Fundamentally, the building consists of four side-gabled sections with roofs of slightly different heights and two end cross-gable sections. On the front (east) facade, the central section that houses the main entrance is of random ashlar stone. This section also features large ashlar stone chimneys on either end of the building at the roofline. Sections of the building on either side of this section have horizontal wood siding. The end gable sections have ashlar up to the level of the window ledges and horizontal wood siding above. The southern cross-gable section also has a large stone exterior chimney. On the rear (west) facade of the building, a covered porch supported by posts covers the facade between the cross-gabled sections. This section of the facade is covered with horizontal wood siding. As on the front facade, the cross-gabled sections are stone ashlar up to the window ledges and horizontal wood siding above this level. The interior of the building features chestnut paneling, craftsman-style wall sconces, and large stone fireplaces. One of the main rooms features barrel vaulting, although Wright's original design called for the scissor-trusses to be exposed.

Originally, a stone terrace was located at the west end of the large open area on the rear (west side)

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 27

---

of the building,

The **Picnic Grounds Comfort Station (DR-0501) (1938) (Contributing)** is the other contributing building in the Dickey Ridge area. It is a rectangular log structure with a gabled roof. The exterior walls are of squared logs, joined using V-notches. The roof is of concrete shingles. The entrances to the building are located on the two long sides of the building. Privacy walls, also constructed of squared logs, screen the entrances to the building. Each of the long facades also features multi-pane windows that are hinged at the bottom to swing inward. Windows are also located on the ends of the building. The building has stone and concrete foundations. It is in good condition.

Noncontributing resources include the **Visitor Center Comfort Station (DR-0563) (1984) (Not Eligible)**. This is a modern wood frame structure with a concrete foundation. Exterior walls are vertical (board-and-batten) siding and stone veneer. The gable roof is covered with cedar shingles.

### **SIMMONS GAP AREA**

The Simmons Gap area is located off Skyline Drive at approximately Milepost 73. It is the former site of an Episcopal Mission and is now the maintenance area for the south district of the park. The portion of the Simmons Gap area included in this nomination contains approximately nine acres. The site is reached by a short paved access road that branches off from the east side of Skyline Drive. The land on either side of the curved road before the developed area is largely forested. The access road comes to a dead end in the maintenance building area. Just prior to the end of the road, a side road leads off to the south. This short road leads to the rest of the developed area that includes the remaining mission building, new residential buildings, and a handful of 1930s and 1940s storage buildings and offices associated with the maintenance area. A stone bridge over a small creek provides access to this part of the area.<sup>20</sup> Although the Simmons Gap area is surrounded on all sides by trees, the immediate area around the buildings is open.

Contributing resources in the Simmons Gap area include the Mission Building, a number of maintenance buildings constructed in the 1930s, and the access roads.

The **Mission/Residence (SG-0711) (1925) (Determined Eligible)** is also known as the Simmons Gap Mission Community Hall. This simple rectangular one-story building is of fieldstone construction.

---

<sup>20</sup> No information is available about the date of the bridge; however, the stonework appears to date from the at least the 1930s, and it is considered a contributing element to the historic district.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 28

---

The building has a gabled roof with asbestos shingle covering and nine-over-six double-hung sash windows. A central stone chimney is located in the center of the building at the roofline. The entrance to the building is through the west side and is reached via a raised open porch. A wood porch with a garage below located on the south side of the building is believed to date from the late 1930s. Although there is not extensive information about the original design of the building, some alterations are apparent. On the north facade of the building, a Gothic-arched entrance been filled in. Although the ghost of the former entrance is visible, the patching was competently done and does not significantly affect the integrity of the structure. The structure as it now stands was heavily modified by the National Park Service for its use as a residence. The building has been in use by the National Park Service since the park's opening, and the building's significance is tied to its association with the park. It, like the handful of other pre-1930s buildings in the park, illustrates the effort to return the park to its condition before human occupation. Because the building was present during the period of significance, relates to the documented significance of the district, and possesses historic integrity it should be considered a contributing resource to the historic district.

The other contributing elements to the historic district are five small utilitarian wood frame buildings with gable roofs and German siding. All have green roll asphalt roofing, are painted brown, and are relatively unaltered.

The **Fire Cache (SG-0329) (1937) (Determined Eligible)** is a small wood building with a shed roof. Three sides of the building have vertical siding. The front of the building features a large plywood utility door that pivots from the top, a front entrance door, and a fixed-pane window. Surrounding these is vertical board-and-batten siding. The building was originally used as a garage, and this facade of the building had two sets of paired doors that opened together.

The **Gas/Oil Building (SG-0431) (1934) (Determined Eligible)** is a small utilitarian wood frame building with a gable roof and German siding. It has concrete-block foundations and a fixed nine-pane wood frame window. The building has green roll asphalt roofing and has been painted brown. A small roof supported by brackets protects the front entrance door.

The **Maintenance Shed (SG-0448) (1937) (Determined Eligible)** consists of the original garage structure and an addition. The addition, a second garage added onto the side of the original building, roughly doubled its size. Both parts of the building are wood-frame. The original section of the building has German siding and three vehicle bays each with double hinged doors. The new section of the building is roughly four feet higher than the original section. It has a single entrance bay and horizontal wood siding. The two sections of the building have separate gable roofs.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 29

---

The **Storage Shed (SG-0449) (1939) (Determined Eligible)** is a small utilitarian wood frame building with a gable roof and German siding. The building has a standing-seam metal roof and has been painted brown. A cross-gabled addition to the rear of the building roughly doubled the size of the building. The addition was constructed before 1966.

The **Maintenance Shop (SG-0466) (1939) (Determined Eligible)** is a small, rectangular, wood frame building with a gable roof and German siding. The building has green roll asphalt roofing and has been painted brown. The building is constructed on concrete-block foundations. The front of the building has been altered and is now covered with vertical board-and-batten wood siding. It now has a large wood sliding door on one side and the entrance door and a window on the other. The building was moved in 1975 from Swift Run. Prior to that it was located at Dundo Camp.

The **Ranger Office (SG-0611) (1948) (Contributing)**<sup>21</sup> is a small, rectangular, wood frame building with German siding on three sides. The front of the building has apparently been altered, and it is covered with vertical board-and-batten siding. The gabled roof is covered with asbestos shingles.

Noncontributing resources include two recently constructed employee houses and a number of recent utilitarian structures. All fall outside the period of significance for the Historic District. They have been evaluated by the NPS and VASHPO and found not eligible for the National Register. Among these are two residences: **Residence (SG-0263) (1986) (Not Eligible)** and **Residence (SG-0268) (1990) (Not Eligible)**. These are pre-fabricated, wood frame, ranch style-buildings. The **Rescue Cache (SG-1656) (1978) (Not Eligible)** is a frame structure originally constructed as an open carport. It was enclosed in the 1980s. Three small utilitarian sheds (SG-0451, SG-0478, SG-0488) are of recent construction, as are two pit privies (SG-2426 and SG-2460).

## PINEY RIVER AREA

The Piney River area is located off Skyline Drive at approximately Milepost 22. It is reached via an approximately 400-foot-long paved access road from Skyline Drive. The road, which leads off from Skyline Drive to the west, branches at the major resource in the area -- a former CCC technical office. From that point, spur roads lead both to the north and south. Most of the older resources are located to the north. A large new maintenance building is located off a short drive to its south,

---

<sup>21</sup>This resource was previously considered not eligible for the National Register. However, given that the building falls within the period of significance of this nomination and retains its architectural integrity it seems appropriate to consider it a contributing element of the historic district.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 30

---

as is a modern residence. The area around the buildings is largely open except for a few isolated deciduous trees located along the road. Piney River is the former site of a CCC camp.

Significant contributing resources to the historic district are associated with the CCC's use of the site.

The **Maintenance Office/CCC Technical Office (PR-0712) (1935) (Determined Eligible)** is a one-story frame structure constructed in 1935 as the technical quarters office of CCC Camp NP-12. As such, it is one of the two primary surviving resources associated with the many CCC camps that were once located in the park. Typical of CCC buildings, it is a long (77' x 21') rectangular building with a gabled roof. A 21' x 15' section projects out from the building's southwest side (currently the front facade). The building has a standing-seam metal roof, and board (with tar-paper) and batten walls. (On the east facade of the building the original wall material is covered with asphalt shingles.) The east facade of the building includes a 7' x 41' porch, located in roughly the center of the building. Windows in the building are six-over-six double-hung sash.

In 1943, when the building was converted into use as a ranger station, a number of alterations were made to it. On the exterior, these include the replacement of chestnut-post foundations with stone foundations and the addition of a small porch at the intersection between the main portion of the building and the extension. On the inside, alterations include moving the bathroom from in front of the living-room area on the porch to its current location, partitioning off a small laundry room in the extension area, constructing a new brick chimney in the southeast corner of the dining room, and replacing a number of doors and windows to accommodate these changes.

The **Maintenance/Equipment Shed-CCC (PR-0437) (1937) (Determined Eligible)** is a one-story frame shed. It consists of a small closed office section on the east end of the building, three open bays in the center, two bays with sliding doors and a small section at the west end that is set back from the rest of the facade. Early (pre-1950) photos show that the building has been significantly altered. The small addition on the east end of the building apparently dates from the 1950s. The central open bays represent either the addition of a building moved from a different location or the opening out of the existing building. The sliding bay doors date from the 1950s. The building is in very poor condition.

Other eligible resources include the small, one-story, frame **Naturalist's Office-CCC (PR-0439) (1935) (Determined Eligible)**. This simple rectangular gable-roofed building has walls of tar paper and batten, and a single entrance on the short side of the building.

Noncontributing resources at the Piney River area include resources that fall outside the period of

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 31

---

significance. All have been evaluated by the NPS and VASHPO and found not eligible for the National Register. The **Residence (PR-0264) (1987)(Not Eligible)** is a pre-fabricated, wood frame, ranch-style building. The **Maintenance Building (PR-4101) (1984)(Not Eligible)** is a large, concrete-block garage-type structure with five vehicle bays. The gabled roof is covered with asphalt shingles and the walls are covered with vertical wood siding. The **Old Gas/Oil Building (PR-0436) (1960?) (Not Eligible)** is a small (8' x 10') concrete-block building with a gabled roof covered with asbestos shingles. The **Gas/Oil Building (PR-4108) (1993) Not Eligible** is a small (8' x 8') utilitarian concrete-block structure with a gabled roof.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 32

**LIST OF RESOURCES INCLUDED IN THE NOMINATION**  
**PARK HEADQUARTERS**

STATUS	NAME	NUMBER	DATE
Contributing Building*	Superintendent House/N.R. Office	HQ-0218	19th c.
Contributing Building*	Residence	HQ-0217	1916
Contributing Building*	Garage for HQ-0217	HQ-0324	?
Contributing Building*	Storage/Shed HQ-217	HQ-0421	?
Contributing Building*	Garage for HQ-0218	HQ-0323	?
Contributing Building*	Storage/Shed for HQ-0218	HQ-0420	?
Contributing Building*	Employees Residence	HQ-0203	1941
Contributing Building*	Garage for HQ-0203	HQ-0303	1941
Contributing Building*	Employees Residence/Offices	HQ-0204	1941
Contributing Building*	Garage for HQ-204	HQ-0310	1941
Contributing Building*	Residence	HQ-0208	1942
Contributing Building*	Garage for HQ-0208	HQ-0308	1942
Non-contributing Building*	Residential	HQ-0202	1959
Non-contributing Building*	Residential	HQ-0205	1959
Non-contributing Building*	Residential	HQ-0207	1959
Non-contributing Building*	Residential	HQ-0209	1959
Non-contributing Building*	Residential	HQ-0225	1960
Non-contributing Building*	Residential	HQ-0226	1960
Contributing Building*	Equip.Storage/Workshop/Carpentry-Weld.	HQ-0401	1940
Contributing Building*	Equipment Storage Shed	HQ-0403	1940
Contributing Building*	Warehouse	HQ-0406	1940
Contributing Building*	Gas & Oil Storage Building	HQ-0409	1943
Contributing Building*	Workshop/Garage	HQ-0422	1933?/38
Non-contributing Building*	Office	HQ-0102	1989
Contributing Building*	Sign Shop	HQ-0426	1942
Contributing Building*	Paint Shop	HQ-0427	1935
Contributing Building*	Storage Building	HQ-0440	c.1925
Non-contributing Building*	Storage Shed	HQ-0477	1961
Non-contributing Building*	Materials Storage	HQ-0478	1962
Non-contributing Building*	Hose Shed	HQ-1602	?
Non-contributing Building*	Chlorinator	HQ-1722	post-1966
Contributing Building	Administration Building	HQ-0101	1940
Non-contributing Building	Archives Building	HQ-0103	1995
Non-contributing Building	Maintenance Building	HQ-457	1995
Non-contributing Building	Community Dial Office	HQ-0454	1957
Non-contributing Building	Shed for Sign Shop	HQ-0490	1970
Non-contributing Structure	Barbecue Hut	HQ-4112	1990s?
Contributing Structures (2)	South and East Administration Building Parking Areas		
Non-contributing Structure	North Administration Building Parking Area		

\*Indicates resources that have previously been determined eligible/non-eligible by the VASHPO

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 33

**HEADQUARTERS (Continued)**

STATUS	NAME	NUMBER	DATE
Contributing Structure	Headquarters Road		
Contributing Structure	Spur to Superintendent's House		
Contributing Structure	Spur to Residential Area		
Contributing Structure	Spur to Maintenance Area		

**BIG MEADOWS**

Contributing Building	Lodge	BM-0114	1938-39
**	Office/Ranger's Quarters	BM-0214	c.1930
Non-contributing Building*	Apartments	BM-0725	1966
Non-contributing Building*	Apartments	BM-0726	1966
Non-contributing Building*	Tackroom-Office	BM-0321	1959
Non-contributing Building*	Stables	BM-0379	1959
Contributing Building*	Stables	BM-1158	1939
Contributing Building*	Equip. Shed/Workshop/Repair/Garage	BM-0410	1939
Contributing Building*	Maintenance/Vehicle & Equip.Storage	BM-0411	1939
Contributing Building*	Blacksmith Shop/Storage Shed	BM-0412	1939
Contributing Building*	Storage Shed (Rangers Office)	BM-0413	1939
Contributing Building*	Carpenter Shop/Storage Building	BM-0414	1939
Contributing Building*	Warehouse Sub. HQ/Storage	BM-0415	1939
Contributing Building*	Gas/Oil Building	BM-0416	1939
Non-contributing Building	Byrd Visitors Center	BM-2302	1966
Contributing Building	Wayside	BM-0113	1939
Non-contributing Building	Wayside Ice Storage	BM-0381	1961
Non-contributing Building	Wayside Garbage Storage	BM-0390	?
Non-contributing Building	Can Storage	BM-0382	1961
Non-contributing Building	Service Station	BM-0374	1961
Contributing Building	Campground Contact Station	BM-0705	1939
Contributing Building	Employee Cottage "A"	BM-1156	Pre-1933
Contributing Building	Employee Cottage "B"	BM-1157	Pre-1933
Contributing Building	Cottage "C"	BM-0314	Pre-1939
Contributing Building	Cottage "D"	BM-0315	Pre-1939
Contributing Building	Cottage "E"	BM-0316	Pre-1939
Contributing Building	Linen Storage	BM-0324	Pre-1939
Contributing Building	Petersburg Cottage	BM-0149	1938
Contributing Building	Bridesburg Cottage	BM-0153	1938
Contributing Building	Blacksburg Cottage	BM-0152	1938
Contributing Building	Lynchburg Cottage	BM-0155	1938
Contributing Building	Mountain View Cottage	BM-0154	1938
Non-contributing Building	Double Top Cottage	BM-0118	1959
Non-contributing Building	Rapidan Cottage	BM-0344	1963
Contributing Building	Piedmont Cottage	BM-0115	1941
Contributing Building	Blackrock Cottage	BM-0116	c.1946
Contributing Building	Hawksbill Cottage	BM-0117	c.1946

\*Indicates resources that have previously been determined eligible/non-eligible by the VASHPO

\*\*Contributing Building [Change from SHPO determination]

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 34

**BIG MEADOWS (Continued)**

STATUS	NAME	NUMBER	DATE
Non-contributing Building	Crescent Rock	BM-0397	1986
Non-contributing Building	Employee Quarters	BM-0326	1961
Non-contributing Building	Employee Quarters	BM-0327	1961
Non-contributing Building	Employee Quarters	BM-0320	1963
Non-contributing Building	Employee Quarters	BM-0319	1966
Contributing Building	Campground Comfort Station (east)	BM-0509	1937
Contributing Building	Campground Comfort Station (west)	BM-0508	1937
Contributing Building	Picnic Area Comfort Station	BM-0507	1937
Non-contributing Buildings (3)	Comfort Stations Campground	BM-0541 -43	1961
Non-contributing Buildings (3)	Comfort Stations Campground	BM-0551 -53	post-1966
Non-contributing Structure	Amphitheater	BM-Amphi	c.1978
Non-contributing Building	Laundry & Service Building	BM-0356	1966
Non-contributing Building	Projection Booth	BM-0467	1956
Non-contributing Building	Storage & Service Building	BM-0385	
Non-contributing Building	Employee Dorm	BM-0396	1987
Non-contributing Building	Shower Building	BM-0398	
Non-contributing Building	Wood Sales	BM-0393	
Non-contributing Buildings (2)	Pit Privies (Campground)	BM-2422-23	
Non-contributing Building	Pit Privy (Picnic Area)	BM-2464	
Contributing Site	Picnic Grounds		
Contributing Site	Campgrounds		
Contributing Structure	Big Meadows Road		
Contributing Structure	Wayside Loop/Parking		
Contributing Structure	Campground Loop		
Contributing Structure	Picnic Loop		
Contributing Structure	Spur to Maintenance Area		
Non-contributing Structure	Spur to New Housing Area		
Non-contributing Structure	Spur to Sewage Treatment Plant		
Contributing Structure	Parking Area/Loop Road from Lodge		
Contributing Objects (6)	Campground Water Fountains		
Contributing Objects (2)	Picnic Grounds Water Fountains		

**DICKEY RIDGE**

Non-contributing Building*#	Visitor Center Comfort Station	DR-0563	1984
Contributing Building*#	Visitor Center (Lodge)	DR-2301	1938
Contributing Building*#	Picnic Grounds Comfort Station	DR-0501	1938
Contributing Objects (5)*#	Picnic Grounds Water Fountains		
Contributing Site*#	Picnic Grounds		
Contributing Structure	Dickey Ridge Road		

\*Indicates resources that have previously been determined eligible/non-eligible by the VASHPO

\*\*Contributing Building [Change from SHPO determination].

#These resources were included in the Skyline Drive Historic District Nomination, and thus are not included in the count of resources for this nomination.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 7 Page 35

---

**PINEY RIVER**

STATUS	NAME	NUMBER	DATE
Contributing Building*	Maintenance/Equip. Shed-CCC	PR-0437	1937
Contributing Building*	Naturalist's Office-CCC	PR-0439	1935
Contributing Building*	Maint.Office/Station/CCC Barracks	PR-0712	1935
Non-contributing Building*	Residential	PR-0264	1987
Non-contributing Building*	Maintenance Building	PR-4101	1984
Non-contributing Building*	Old Gas/Oil Building	PR-0436	1960?
Non-contributing Building*	Gas/Oil	PR-4108	1993
Contributing Structure#	Access road from Skyline Drive		

**SIMMONS GAP**

Contributing Building*	Mission/Residence	SG-0711	1925
**	Ranger Office	SG-0611	1948
Non-contributing Building*	Residence	SG-0263	1986
Non-contributing Building*	Residence	SG-0268	1990
Contributing Building*	Fire Cache	SG-0329	1937
Contributing Building*	Gas/Oil Building	SG-0431	1934
Contributing Building*	Maintenance Shed	SG-0448	1937
Contributing Building*	Storage Shed	SG-0449	1939
Contributing Building*	Maintenance Shop	SG-0466	1939
Non-contributing Building*	Rescue Cache	SG-1656	1978
Non-contributing Building	Shed	SG-0451	
Non-contributing Building	Maintenance Yard	SG-0487	
Non-contributing Building	Maintenance Yard	SG-0488	
Non-contributing Building	Pit Privy	SG-2426	
Non-contributing Building	Pit Privy	SG-2460	
Contributing Structure	Bridge		
Contributing Structure#	Access Road from Skyline Drive		

\*Indicates resources that have previously been determined eligible/non-eligible by the VASHPO

\*\*Contributing Building [Change from SHPO determination].

#These resources were included in the Skyline Drive Historic District Nomination, and thus are not included in the count of resources for this nomination.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 36

---

## INTRODUCTION/SUMMARY

The areas included in this addition to the Skyline Drive Historic District constitute a majority of the historic developed areas of Shenandoah National Park including the park Headquarters. The resources included within this nomination, like those included in the original nomination, exemplify the park, and its singular history.<sup>22</sup> The park -- and thus the boundary addition's -- significance falls under both National Register Criterion A (properties significant for their association with events) and Criterion C (properties significant as representatives of the manmade expression of culture or technology). The area is significant in the areas of Politics/Government, Architecture, Entertainment/Recreation, and Landscape Architecture for the period of 1931-1952. The park's historical significance relates in part to the fact that it was one of the first eastern national parks and as such, the nation's most visited national park in the years immediately prior to World War II. In addition, it is significant as the site of the Skyline Drive and as a primary example of artificial efforts to return a developed area to its natural state. The park, while initiated during the administration of Herbert Hoover is an example of the many accomplishments of Franklin Roosevelt's Depression-era programs, in particular the Civilian Conservation Corps. The park's design is characteristic of the outstanding landscape design and master planning of the National Park Service's Branch of Plans and Designs. It features a notable collection of buildings designed in the rustic style (by the National Park Service and, for the concessionaire's buildings, Richmond architect Marcellus Wright, Jr.). Further discussion of the overall significance of the park can be found in the 1996 Skyline Drive Historic District National Register Nomination.

In addition to significance related to the park as a whole, the boundary addition area also conveys significance relating to the specific areas within the addition. In particular, the Headquarters area has significance as the temporary home of much of the Smithsonian Institution's collection during World War II. The Simmons Gap area is significant as the site of one of the last remaining Episcopal Church mission buildings in this section of the Blue Ridge Mountains. The Piney River area is one of two areas within the park that were the site of CCC camps and that still retain CCC buildings. The Big Meadows area is the largest of the historic developed areas in the park and in many ways is the one which best illustrates the range of National Park Service design work.

---

<sup>22</sup>In addition to Skyline Drive, Camp Hoover, Corbin Cabin and ten prehistoric archeological sites already represent the park on the National Register. A draft nomination has also been prepared for Skyland. At a later time, other resources, for instance the Lewis Mountain area which was the officially racially segregated lodging area, will likely be added to the Skyline Drive Historic District.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 37

---

As discussed in Section 7, most of the park's historic resources date from the mid-1930s to the early 1940s. When the park was established, it included thousands of built resources (mostly dwellings and outbuildings) associated with mountain residents, nearly all of which were removed prior to World War II. In the meantime, resources catering to visitors to the park (lodges, waysides, campgrounds, etc.) and buildings associated with the maintenance and administration of the park (storage and shop buildings, offices, etc.) were constructed. With the exception of those constructed by the park concessionaire, Virginia Sky-Line, Inc., most of the historic resources in the park today were in some way associated with Depression-era agencies.<sup>23</sup> Chief among these agencies was the ECW/CCC which provided the manpower for much of the landscaping and utility work as well as some of the construction work. Both the landscaping and the architectural design at the park are generally in the Rustic style.

The major relevant Virginia Department of Historic Resources historic contexts for this nomination are: *Settlement and Agriculture in the Blue Ridge Mountains*<sup>24</sup> 1865-1917 and *Federal Government-sponsored Architecture, Landscape Architecture, and Planning from 1917-1945 in the Blue Ridge*. Significant property types include: park roads, park headquarters, maintenance areas, concessionaires' developments, picnic areas, campgrounds, comfort stations, and former CCC camps.<sup>25</sup>

---

<sup>23</sup>Although buildings constructed by the concessionaire were privately funded, the utilities and site development were completed by a combination of federal agencies.

<sup>24</sup>Virginia's geographical regions include the "Valley" area and the "Upper Piedmont" area. Shenandoah National Park literally straddles the line between the two areas. (The boundaries between counties on either side is often the ridge of the Blue Ridge.)

<sup>25</sup>These property types are based on the types described in the *Historic Park Landscapes in National and State Parks Multiple Property Listing*.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 38

---

## **PRE-PARK DEVELOPMENT, c. 1890-1935<sup>26</sup>**

### Early Development and Agriculture

Settlement of the National Register boundary expansion area tended to be closely linked to means of transportation, as well as to access to water and fertile land. Mountain passes, or "gaps" as they are referred to in Virginia, channeled development in the area. They funneled people and traffic through specific routes and spawned development in their immediate vicinity. This growth, which developed to service travelers, included inns, blacksmith shops, and related settlement.

Although many of the earliest occupants in the vicinity of the park were of English ancestry, by the mid-eighteenth century German, and to a lesser extent Scotch-Irish immigrants, also came in increasing numbers to the valley area. Some of the German immigrants had ties to the settlement established at Germanna, Virginia. Most of those with German and Swiss backgrounds, however, came to the park area, as they did to the rest of Virginia, by way of Pennsylvania. A majority had strong farming backgrounds and held firmly to their traditional language and religion. Beginning around 1830 and peaking after the Civil War, the valley farmers/grazers (mostly German in background) began replacing those of British descent as owners of the fertile sections (especially along the Blue Ridge crest) of the park land. The Germans used the land for pasturage for their cattle. The change in land use and ownership accelerated as a result of the Civil War, and the British dominance of land ownership in the future park lands was effectively terminated by this time.

Grazing soon became the major agricultural activity in the Blue Ridge. Particularly after 1830, valley landowners purchased the richer future park land to graze cattle. Until 1845, Virginia raised more cattle than any other state or territory in the country.<sup>27</sup> Accompanying the use of the land for grazing was an unusual land tenancy system that embraced about half of the population in the area

---

<sup>26</sup>The story of the area that was to become the park also includes much in the way of pre-history. There have been a number of studies regarding archeological resources in the park, and additional studies are ongoing. This information is beyond the scope of this nomination, which concentrates on built resources. Later nominations to the National Register relating to archeological resources will be forthcoming and will address the site's rich pre-history.

<sup>27</sup>Darwin L. Lambert, *The Undying Past of Shenandoah National Park*, Boulder, Colorado: Roberts Rinehart, Inc. Publishers, 1989, p. 137.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 39

---

that was to become the park.<sup>28</sup> Cattle ranchers in the valley who owned mountain plots usually established a tenant on the tract to help care for the herds. In some cases, the tenant was originally a squatter on the property. The tenancy was unofficial and without any written agreements. The arrangement generally permitted the tenant to stay on the land, to use some of it for gardens and orchards, to graze small herds, gather chestnuts, and harvest a small amount of timber. Many tenants also maintained droves of pigs, which fed on the chestnuts that were plentiful until the chestnut blight. In exchange, the tenants helped herd the cattle (including "salting" the cattle -- that is, putting out salt for them to lick), repaired fences, and to some extent protected the landowner's property rights. In addition, the tenants/squatters often cleared additional land, thereby creating new grazing areas. In some cases, the owner may have received a share of the tenant's profits as payment for the use of the land. The unofficial relationship between the landowner's family and the family of the tenants/squatters continued for generations. In many cases, these longterm relationships ended only with the acquisition of the land for the park. A high percentage of the occupants of the area (60 percent) had no legal title to their land; therefore when the land was acquired for the park they often received little or no compensation for their property.<sup>29</sup> This created particular hardships and was a major source of conflict when land was condemned for the park by the Commonwealth of Virginia.

Although much of the park land had always been part of large tracts, there were many smaller-scale landowners. These mountain residents generally had small gardens, often including corn, rye, and vegetables, and frequently a small orchard. (Today, apple and peach trees are often the only visible indication of an old home site in the park.) They often also had pigs and a milk cow. In 1934, 90 percent of the people occupying park land cultivated at least some land.<sup>30</sup> Many grew corn and/or wheat, which was milled at the local gristmills. A typical family that lived in the Swift Run area raised green beans, which they dried ("hay beans"), and grew apples in their orchard, some of which they dried, some of which went into apple butter or were stored. They also had cows for milk, butter, and cheese. The family's food supply was supplemented by gathering berries and nuts. With the exception of chestnuts, which were often sold for cash, for the most part the food produced was

---

<sup>28</sup>Lambert, *The Undying Past*, p. 139.

<sup>29</sup>Because many of the residents were on the property with the permission of the legal owners, they could not claim adverse possession of the land.

<sup>30</sup>Lambert, *The Undying Past*, p. 175; and Steere, Edward, "Historical Study of Park," United States Department of the Interior, National Park Service, Shenandoah National Park, p. 16.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 40

---

enough for little more than feeding the family through the winter.<sup>31</sup> The summer's excesses were preserved, or in the case of corn or fruits, turned into alcohol. Without rotation methods or fertilizers, the corn and wheat fields had to be left fallow every few years. Many farmers cleared land by cutting a ring around the bark of the trees, thereby killing them, but permitting the dead trees to stay in place until there was sufficient time or need to cut them down.

By 1900, there were approximately 6,000 people living within what is now the park.<sup>32</sup> By this time the size of the mountain population, as well as other factors, were straining life on the ridge. With the development of railroads and other economic changes, services and industries upon which residents relied moved into nearby towns such as Front Royal. These changes forced mountain residents to have a greater dependence on a cash economy. As a result, people followed jobs to the towns and the population of the rural areas declined. Between 1900 and 1920 about half of the mountain population left, and in 1936, when the park was dedicated, only 2,250 people remained within its boundary. Of those who remained, most no longer could rely on the land to support their families. In 1934, 331 of 465 park families received cash from working either at the Skyland resort (located within what became the park lands) or in the farms in the valley.<sup>33</sup>

Two pre-twentieth-century houses and associated outbuildings located in the Headquarters area remain as reminders of the area's early development and agriculture. (Although the buildings' significance in large part relates to a later period.) The houses appear to have been constructed and occupied by farm families. Although in some ways representative of farm groupings, in other ways the buildings are not typical of most of the residential buildings that were originally located within the park boundaries. The buildings' size and design, as well as their location (close to Luray), and the fact that they were owner-occupied, set them apart from the majority of houses in the park area.

---

<sup>31</sup>Carolyn Reeder and Jack Reeder, *Shenandoah Secrets: The Story of the Park's Hidden Past*, Washington, D.C., The Potomac Appalachian Trail Club, p. 23.

<sup>32</sup>John A. Conners, *Shenandoah National Park: An Interpretive Guide*, Blacksburg, VA., McDonald and Woodward Publishing Co., p. 89.

<sup>33</sup>Lambert, *The Undying Past*, p. 179.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 41

---

Religion

Although the mountain area was physically isolated, there were strong outside connections, especially to the Shenandoah valley.<sup>34</sup> Particularly in the late nineteenth and early twentieth centuries, some of these ties were religious.

The first missionaries to concentrate their efforts on the residents of what was to become the park area -- and those with the greatest impact on the area of the Blue Ridge -- were the Episcopalians, who began work in the area in the early 1880s. Frederick William Neve, an Englishman, was assigned in 1888 by his church to a parish in Albemarle County. After meeting some of the Blue Ridge Mountain residents in his church, the people of the Blue Ridge became his personal crusade. Neve preached throughout the mountain areas and brought back stories of the people's impoverished condition (in terms of both physical and spiritual needs). These stories helped to raise money for his cause. In 1904 he became archdeacon of a newly established diocese that covered the Blue Ridge.

By 1900, Neve had raised enough money through donations to hire a teacher, Angeline Fitzhugh. She taught local children first in a donated cabin and later in a small frame schoolhouse at Simmons Gap. The schoolhouse doubled as a church on those occasions when a minister was available. Between 1900 and 1928, Neve expanded facilities at Simmons Gap and in 1906, a masonry chapel was added to the collection of frame buildings at Simmons Gap.<sup>35</sup>

The Simmons Gap Mission Hall, the only standing religious structure in the park today, was erected around 1925. This building was used by parishioners for various church functions as well as community meetings and social activities including square dances. With various church-related structures, Simmons Gap by the 1920s and 1930s became a thriving community that featured a

---

<sup>34</sup>See generally, Audrey J. Horning, "From Hollow to Valley and Back Again: Historical Anthropology of Nicholson Hollow in Regional Context." Paper presented at "After the Backcountry: Rural Life and Society in the Nineteenth Century Valley of Virginia" Conference, March 1995.

<sup>35</sup>Although some sources have indicated that this was a stone building, photographs (c. 1904-13) of what was called "Holy Innocent's Church" at Simmons Gap show a rock-faced concrete block building. Around this time a rock-faced concrete block school house was also built. See "Protestant Episcopal Mission Activities: 1904-10," (Lot 6986), Prints and Photographs Division, Library of Congress.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 42

---

general store and post office in addition to the church buildings. After the park was established, the stone chapel was moved to a location near Free Union. With the exception of the Mission Hall, which is used as the administrative offices for the park's South District, other church buildings were dismantled or fell down. Aside from the Mission Hall, all other structures now at Simmons Gap were built after the establishment of the park and are not associated with the mission. The mission's importance relates primarily to the fact that it is one of a handful of buildings, and the only religious structure, to survive the extensive demolition that occurred when the park was established.

Neve's 1900-28 expansions at Simmons Gap were echoed all along the ridge at a number of different missions of various denominations.<sup>36</sup>

### Architecture

With a few possible exceptions, buildings in the National Register boundary expansion area that existed when the park was established were not architect-designed. For the most part they were practical vernacular structures that represented a range of periods of construction, material, and styles similar to nearby mountain areas of Virginia. In terms of building type, buildings standing at the time of the opening of the park in the boundary expansion area included, churches, schools, stores, houses, barns, and a variety of outbuildings. Of these, dwellings were the predominant building type. In the park as a whole, in 1934 there were more than 400 houses in the park area. In general, the houses were small vernacular buildings, typically log cabins.<sup>37</sup> A number of outbuildings/structures typically ringed the dwelling, including barns, sheds, cribs, springhouses, stone walls, and fenced enclosures.

For more affluent owners in the park area, the predominant house type was the two-story, side-gable farmhouse, often referred to as an I-house. I-houses are a housing type found throughout the country. They are usually described as a mid-nineteenth- to early-twentieth-century symmetrical, two-story, one-room-deep building with central hall/stair. In this category are two houses located in the Headquarters area. The first of these (HQ-0217) is located in the residential area. Although

---

<sup>36</sup>Neve did live to see the creation of Shenandoah National Park. He died on November 19, 1948.

<sup>37</sup>Two vernacular houses, Corbin Cabin and the Jones Mountain Cabin survive in the park but are located outside of the area included in this nomination. Corbin Cabin has been separately listed on the National Register.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 43

---

little or no historical information is available about this house, it is believed to date from 1916.<sup>38</sup> The other surviving I-house type building in the park is HQ-0218 which is currently the Center for Resources. Like HQ-0217, little or no historical information is available about this house; however, it was apparently constructed before 1900.<sup>39</sup> After establishment of the park, the building was used for a number of years as the superintendent's residence. Around 1942, the building was reconditioned using Emergency Conservation Work/Civilian Conservation Corps foremen and technicians who remained in the park after official projects were completed.<sup>40</sup>

The two I-houses in the Headquarters area of the park are representative of a number of larger homes that were extant when the park was created.

The land around most of the houses within the park area was involved in some way in agricultural production, and most houses had a number of associated outbuildings to accommodate these activities. Originally, houses were surrounded with a variety of outbuildings, typically including barns, or sheds, corn cribs, smokehouses, outhouses, and springhouses. Both of the Headquarters area I-houses still have one or two frame outbuildings, now used as sheds or garages.

## **ESTABLISHMENT OF SHENANDOAH NATIONAL PARK AND EARLY PARK DEVELOPMENT, 1933-1942**

### The Establishment of Shenandoah National Park

The nation's first national park, Yellowstone, was established in 1872, 44 years before the creation

---

<sup>38</sup>"Determination of Significance" statement, 1994, Administrative Files, Shenandoah National Park (DSC Facility Development Plan Project). According to the 1973 Sellars Report, the building was constructed by the family of Mrs. John Shenk of Luray, VA.

<sup>39</sup>The 1973 Sellars Report states that the house was constructed "about 80 years ago" by the father of Mrs. John Shenk of Luray. Changes to the building include various additions and the removal of the front porch.

<sup>40</sup>Darwin Lambert, "Shenandoah National Park: Administrative History 1924-1976." Luray, Virginia, 1979, p. 287.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 44

---

of the National Park Service in 1916.<sup>41</sup> It, as well as later parks, had a number of common characteristics. All were western parks located in relatively undeveloped places of immense natural beauty.<sup>42</sup> As an eastern park and one established in an area that had been significantly impacted by human occupation for generations, Shenandoah National Park represented a major change from the parks which had preceded it. Its quite different nature played a role in the particularly long and convoluted process of establishing the park which involved the work of dozens of dedicated individuals and groups working at the local, regional, and national level.<sup>43</sup>

On the national level, as early as 1901, there was legislation in Congress proposing the idea of an eastern national park in the southern Appalachian mountains. This solidified an idea that had surfaced in the 1880s. The idea languished, however, and only in the 1920s was there real movement to achieve this objective. Stephen T. Mather, the first director of the National Park Service, in his 1923 *Annual Report*, again suggested an eastern national park, more specifically, one located in the Appalachian Mountains. His interest in an eastern park was partially in response to the large number of national parks already located in the west and the lack of parks within easy reach of residents of the eastern seaboard. The next year, the Southern Appalachian National Park Committee, which was organized by Secretary of the Interior Hubert Work, began to actively seek sites for such a new park. There were so many areas interested in becoming the first southeastern national park that the committee devised a survey form to screen the large number of competing sites.

On the local level, the Skyland resort and its colorful founder, George Freeman Pollock, were major

---

<sup>41</sup>Prior to this, in 1864 the federal government had given Yosemite Valley and the Mariposa Grove of Big Trees to the State of California for scenic purposes. This area was later added to the Yosemite National Park which was established in 1890.

<sup>42</sup>There were certain exceptions, however. These include Hot Springs National Park which was created in 1921, and Maine's Acadia National Park. The latter was proclaimed as Sieur de Monts National Monument in 1916, established as Lafayette National Park in 1919, and renamed Acadia National Park in 1929.

<sup>43</sup>See the Skyline Drive National Register nomination for additional information about the creation of the park.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 45

---

forces behind the creation of Shenandoah National Park.<sup>44</sup> From the founding of the Skyland resort in the 1888-89, Pollock had been a strong advocate for his corner of the Blue Ridge. Harold Allen, a friend of Pollock's and frequent guest at Skyland, initially apprised Pollock of the work of the Southern Appalachian National Park Committee and, later, with fellow Skyland resident, George H. Judd, helped Pollock complete the survey form. Pollock, thereafter began a full-fledged campaign to bring the park to Skyland. He personally visited members of the committee in Washington and brought with him glowing letters about the spot from his many well-placed guests. Pollock's efforts, in combination with those of Shenandoah Valley, Inc., as discussed below, were successful in attracting the committee to come view the area and ultimately endorse the Blue Ridge area as the national park site. Although the closeness of the site to such a large portion of the population was persuasive, Pollock's salesmanship also played an important role in winning the support of the committee. His efforts to win the committee's support varied from orchestrating moonlight horseback rides, to constructing viewing towers and paths to make the vistas more easily visible to park committee members. Pollock spent \$7,000 of his family funds on these improvements.

The push to create the park also had a regional component. In January 1924, a group of local chambers of commerce banded together to form Shenandoah Valley, Inc., the purpose of which was to "proclaim to all the world the material resources and scenic attractions of the area."<sup>45</sup> L. Ferdinand Zerkle, the director of the new organization, with the help of Pollack, managed to convert part of the group which initially advocated that the park be located on the Massanutten range. Thereafter, the group became vital to the success of the park. Specifically, they aided the effort initiated by Pollock to secure the committee's endorsement of a Blue Ridge location for the park. Zerkle in particular helped orchestrate the effort to acquire the land to establish the park.

With the selection of the Shenandoah site, by February 1925, Congress approved a bill providing for a commission to recommend park boundaries and to arrange to acquire land at Shenandoah. It specified that a minimum of 385,000 acres would have to be donated before the park could be accepted into the national park system. In the following years, the acreage required to establish the

---

<sup>44</sup>What was eventually to become the Skyland resort, a collection of cabins and a dining hall, was established at the site of the current Skyland area. The resort had many ups and downs and it was well into the twentieth century before the resort became a going concern. For more in-depth information on Skyland and its resources see, Reed L. Engle, "Skyland Historic District National Register of Historic Places Nomination Form," [draft] 1995.

<sup>45</sup>Lambert, *Administrative History*, p. 14-15.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 46

---

park was reduced (twice) to 160,000 acres.<sup>46</sup> The effort to acquire land and to change the minimum acreage was only the first of many hurdles that the project had to face. It took ten additional years before the park officially came into existence. The delays were due to a number of factors, including a lawsuit relating to the condemnation of land for the park, the need to set up a program to help resettle the former residents of the park area, and the overall difficulty in getting donations to fund procurement of the land.

Meanwhile, in 1926, Harry Byrd, newly elected governor of Virginia and a strong supporter of the park, persuaded Will Carson, a businessman and civic leader, to become chairman of the newly created Virginia State Commission on Conservation and Development. In this position, Carson became responsible for furthering the cause of the park, and, in particular, with coming up with the funds necessary to buy the land. One of his major accomplishments was his role in bringing Herbert Hoover to the park. Less than two months after Herbert Hoover's inauguration as president, Carson managed to convince him to establish a fishing camp on a stretch of the Rapidan River within what was to become the park boundary. Hoover quickly became a devotee of the place and perhaps more importantly, the major force behind the construction of a "skyline drive" along the mountains.<sup>47</sup> According to one version of the story, in late 1930, President Hoover was riding horseback along the crest of the mountains with the director of the National Park Service, Horace Albright. Hoover remarked on the beauty of the views along the ridge and his desire to share them with the public. He then directed Albright to undertake a survey in preparation for construction of a skyline drive.<sup>48</sup>

The National Park Service obtained title to the land that was to become the drive (along with a 100-foot right-of-way) and construction of Skyline Drive was started July 18, 1931 on the section of the road from Thornton's Gap (Panorama) to Swift Run Gap with a smaller road to Fish Rack (south

---

<sup>46</sup>In addition to setting a minimum acreage for the park, the bill also set the legal maximum acreage for the park at 521,000 acres. This represented areas where the park could expand if land was acquired. This figure was reduced and the authorized area now stands at 196,000 acres.

<sup>47</sup>Hoover ended up donating his 166-acre camp in Madison County to the park.

<sup>48</sup>Horace M. Albright, "My Trips With Harold Ickes," *Washington History*, Spring 1990, p.39. Although Albright dates the trip to May 1931, other sources give different dates for the trip. The concept of a skyline drive did not start with Hoover, but goes back at least to 1924. The questionnaire produced by Pollock and the report of the committee charged with selecting an Appalachian Mountain park site both mentioned the idea -- although where the idea came from is unclear.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 47

---

of Camp Hoover). Although still unfinished, a special advance opening of the drive, from Lee Highway (Route 211) to Skyland was held between October 22 and November 30, 1932 -- during which time 30,837 persons in 7,891 cars used the then-unpaved road.<sup>49</sup> The central section of the drive from Thornton Gap to Swift Run Gap (incorporating the Rt. 211/Skyland section) also opened before the park on September 15, 1934. The north section of the drive, from Front Royal to Thornton Gap, opened October 1, 1936 (after the establishment of the park), and the south section, from Swift Run Gap to Jarman Gap, was completed August 29, 1939. The segment of the road from Jarman Gap to Rockfish Gap was constructed in 1936-37 as part of the Blue Ridge Parkway and incorporated into the park and Skyline Drive in 1961.

Although approximately one-third of the Skyline Drive was open and already in use, it was only on December 26, 1935 that three deeds transferring a total of 176,429.8 acres from Virginia to the United States government were finally accepted, and Shenandoah National Park officially came into existence.<sup>50</sup> This expanded the National Park Service's jurisdiction, which had previously been limited to the drive and the associated right-of-way. The first park employee came on staff in March 1936 and the dedication of the park occurred on July 3, 1936. Thousands of visitors and hundreds of CCC participants attended the proceedings that were broadcast on national radio. President Roosevelt, in addition to a number of others, addressed the crowd. His speech discussed the related goals of preservation and development of the country's natural and human resources and how these goals were being accomplished through the CCC program at the park. In addition, Roosevelt spoke of the importance of recreational opportunities:

*All across the nation at this time of the year people are starting out for their vacations in national and state parks. They will set up roadside camps or pitch their tents under the stars, with an open fire to cook by, with the smell of the woods and the wind in the trees. They will forget the rust and the strain of all the other long weeks of the year, and for a short time at least, the days will be good for their bodies and good for their souls. Once more they will lay hold of the perspective that comes to men and women who every morning and every night can lift up their eyes to Mother Nature.*

*There is merit for all of us in the ancient tale of the giant Antaeus, who every time he touched*

---

<sup>49</sup>Lambert, *Administrative History*, p. 117.

<sup>50</sup>The deeds had been delivered over a year before, in August 1934. The delay in the acceptance of the deeds was a function of problems related to the resettlement of the residents.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 48

---

*his mother earth, arose with strength renewed a hundredfold.*

He also spoke of the need throughout the country for "recreational areas for parkways which will give to men and women of moderate means the opportunity, the invigoration and the luxury of touring and camping amid scenes of rare natural beauty."<sup>51</sup>

Those who struggled to bring the park into existence did not have to wait long to see the success of their efforts. With the official opening of additional segments of Skyline Drive and the completion of some services for visitors, visitorship at the park soared. Thousands of visitors poured into the park, used existing recreational facilities, drove on the scenic Skyline Drive, and enjoyed the out-of-doors at picnic areas. By September 1937, the yearly visitation reached one million, a first for any national park.

#### Depression-Era Programs at Shenandoah

With the transfer of ownership of the park land to the National Park Service in December 1935, the official administrative wheels of the park began to turn. On March 1, 1936, permanent park staff began work at temporary offices at Luray. The first chief ranger, R. Taylor Hoskins, was sworn in on that day, as was the first park employee, Darwin Lambert (later, historical chronicler of the park).

However, in regard to physical improvements, the beginning of direct control over the park area by the National Park Service represented more of a transition than a major change. Work on the Skyline Drive and associated projects (such as the construction of waysides and picnic areas) by CCC workers continued irrespective of the change in ownership. In addition, National Park Service personnel who had been working on the site in a number of capacities (in particular, supervising CCC workers) continued their work.

The change in ownership did mean that certain other types of projects, specifically construction projects, could start up. Without doubt, Skyline Drive and the development necessary to establish facilities at Shenandoah National Park constituted the right projects at the right time. Both were perfect activities for the various federal New Deal works programs. Without the influx of money and labor that accompanied these projects, many of the improvements could not have been accomplished for many years. The drive, and the park-related improvements were completed using a combination of types of federal funding programs. Although in theory the different programs/funding sources

---

<sup>51</sup>Quoted in Lambert, *Administrative History*, p. 145.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 49

---

were separate and had quite distinctive differences in terms of their program goals, in practice, these goals became blurred. It appears that to accomplish any one particular project at the park, in many cases funds and/or labor were used from whatever program had money or workers available. For instance, although CCC labor supposedly was not to be used for large construction projects, the CCC often worked on such projects if men were available.<sup>52</sup>

### The Civilian Conservation Corps

The Civilian Conservation Corps, initially part of the Emergency Conservation Work initiative, existed for nine years and three months. During virtually the entire period of its operation, the organization conducted work at Shenandoah National Park (or what was to be the site of the park). The work that it accomplished pushed the park years ahead in terms of physical development than would otherwise have been possible. A considerable portion of the current infrastructure of the park, from trails and picnic shelters to sewage and water systems, is attributable to the work of the CCC.

The CCC/ECW was one of Franklin Delano Roosevelt's "pet" programs. Roosevelt, as former chairman of the New York State Legislature's Committee on Forest, Fish and Game, had a strong interest in, and commitment to, conservation work. After his election as president in November 1932, and prior to taking office, Roosevelt asked staff to come up with plans for a national program to employ unemployed men in projects in federally owned forests. Soon after taking office, Roosevelt held a conference to discuss the outline of the program. In endorsing the Federal Unemployment Relief Act, the bill that eventually went through Congress, Roosevelt emphasized the bill's beneficial effect of conserving natural resources, and the "moral and spiritual value" of the work. He also emphasized that the work done by the corps would be "simple work, not interfering with normal employment, and confining itself to forestry, the prevention of soil erosion, flood control, and similar projects."<sup>53</sup> Roosevelt signed the legislation on March 31, 1933, just 22 days after

---

<sup>52</sup> Oral interview with G.L. "Hop" Baughan, September 21, 1995.

<sup>53</sup> U.S. House of Representatives, Committee on Labor, Message from the President of the United States on Unemployment Relief, Doc. 6, 73rd Cong., 1st sess., March 21, 1933, p. 2, quoted in John C. Paige, *The Civilian Conservation Corps and the National Park Service, 1933-1942*, National Park Service, 1985, p. 8.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 50

---

assuming the presidency. The legislation specified that the program would expire after two years.

Because Roosevelt wanted to see the program put the unemployed to work for the summer months of that year, a stepped-up effort began to get the program -- officially called Emergency Conservation Work -- up and running. Under the plans, the Department of Labor would help select recruits, the Army would train and transport the recruits and operate the work camps, and the National Park Service and Forest Service would direct their work assignments. The ECW officially began operation on April 5 and within one week, representatives from many established national parks and (in the case of Shenandoah) planned national parks had contacted the ECW requesting enrollees. In general, projects were selected that did not call for large quantities of material or equipment, and that did not require skilled workers. Many types of projects were limited to \$1,500 without the specific authority of the Washington office of the National Park Service.

Franklin Delano Roosevelt without doubt personally ensured that Shenandoah received support from CCC camps. In April 1933, Roosevelt visited Hoover's camp, and although the terrain of the site was too rough for him to consider for his own use (he instead went to what was later known as Camp David), he was impressed with the area and with Skyline Drive. He became convinced that the park area was the perfect site for the first of the CCC camps. Although, as it turns out, the first CCC camp was not located in the future park area, camps within the area of the park soon followed. On April 25, the Director of the ECW announced that ECW camps would be located in the proposed Shenandoah National Park at Skyland and Big Meadows. On May 11, the first three National Park Service camps, including NPS-1 located at Skyland, opened their doors. Land was donated or leased within the park, and two camps (NPS-1/Skyland and NPS-2/Big Meadows) were set up in May 1933. These were the first camps to be managed by the National Park Service. One month later, two more camps were opened: NPS-3 was established beside the drive north of Swift Run Gap, and NPS-4 was located near Front Royal.<sup>54</sup> In August, 1933 Roosevelt came to personally

---

<sup>54</sup>The official names of the camps at Shenandoah were Skyland (NP-1), Big Meadows (NP-2), Bald Face (NP-3), Harmony Hollow (NP-4), and Grottos (NP-5). Later camps were located at Sperryville (NP-9), Sexton Shelter/Pinnacles (NP-10), and Rattlesnake Point/Piney River (NP-12). NP-9 (which operated only for a few months in 1934-35) and NP-10 were transferred to the National Park Service in 1934. NP-12 was moved from Sperryville in 1935 (where it had been called NP-9). NP-26 and NP-27 operated only briefly for part of 1939 (NP-26) and 1940-41 (NP-27).

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 51

---

inspect the progress of the camps. He met with enrollees and ate lunch at one of the CCC camps.<sup>55</sup>

The early work of the CCC in the area included within this nomination preceded the establishment of the park by two years. One of the first tasks was the construction of camp buildings and the utilitarian CCC camp buildings are the earliest group of buildings in the expanded boundary area from this period. CCC workers were housed in camps located close to the project sites. Initially, the camps were composed entirely of tents. However, given the short lifespan of the tents, the effort involved in setting them up and taking them down, and their unsuitability during the winter months, the tents were soon replaced with wooden buildings. Tents began to be replaced by permanent wooden buildings in late 1933 and early 1934. This change to permanent structures was part of a nationwide effort. According to one press release:

*Forty thousand carpenters, working in 46 states and utilizing 300 million feet of lumber, are rushing to completion a record-breaking camp construction program for the Civilian Conservation Corps. On over 1,400 camp sites, a total of nearly 15,000 buildings are being constructed to take care of housing and recreation needs for the 300,00 men of the CCC for the winter and spring months.*<sup>56</sup>

By 1934, there was considerable experimentation with "portable" CCC buildings and by around 1936 they had become the CCC standard building type. The Army's design was for an inexpensive, easily constructed, partially prefabricated wood building with interchangeable parts that could be used for any of a variety of buildings. Constructed of standard size units, the buildings in many cases were held together by long bolts. The buildings were generally arranged in a U-shaped configuration, with the open central area used for central assemblies or other group activities. Buildings housing a recreation hall, a garage, a dispensary, administrative buildings, a mess hall, officers' quarters,

---

<sup>55</sup>Lambert, *Administrative History*, p. 145. Although in the years following its dedication Roosevelt's involvement in the park lessened (especially as the war consumed more of his energy) he still retained a strong interest in it. So for instance, when a major dispute arose between the National Park Service and local interests concerning opening roads through the park, he vetoed a bill which would have established two additional access roads.

<sup>56</sup>Press release dated November 3, 1933: pp.1-2. Located at: Franklin D. Roosevelt Presidential Library, Hyde Park, NY; Official File 268, 2, quoted in, Alison Otis, William D. Honey et al, *The Forest Service and Civilian Conservation Corps: 1933-42*, U.S. Department of Agriculture, Forest Service, 1986, p. 74.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 52

---

barracks, and a school house were standard in the camps. The buildings were covered with tar paper, clapboard sheathing (painted brown or green), or were creosoted. The standard plans for the camps changed slightly in 1939, when separate buildings for the camp superintendent, the dining room, and the recreational hall were added.

Although most of the CCC camp buildings in the park were either torn down or disassembled and moved to military bases during the war years, in the National Register boundary addition area, CCC buildings still survive at their original location at Piney River.<sup>57</sup> Camp NP-12, which operated from 1935 to 1941, included more than 20 buildings, including barracks, a mess hall, an educational building, offices, equipment storage buildings, and maintenance sheds. Of these, the major building that remains is a wood frame building of modular construction. It was built in 1935 and used as technical quarters for the CCC camp. The parade ground and most of the buildings at the camp were located to the south and west of the technical quarters.

Other early CCC work consisted mostly of fire protection, erosion control, landscaping/contouring along Skyline Drive and trail construction including work on relocating the Appalachian Trail. In addition, enrollees worked on picnic areas and construction projects such as construction of shelters, and landscape furnishings (including drinking fountains, picnic tables, and fireplaces). The CCC also conducted a "landscape naturalization" program which involved moving native plants that were located on construction sites to a temporary nursery at Big Meadows before they were replanted at other sites. They also gathered seed from many native trees and shrubs and started their own seedlings.<sup>58</sup> The number and variety of stock raised at the nursery was impressive. In addition to operating the nursery, the CCC also did extensive transplanting of the stock from the Big Meadows nursery.

In the National Register boundary expansion area, CCC workers developed the Dickey Ridge (1938), and Big Meadows (1939) Picnic Grounds along with the parking lots, fire grates, tables, water fountains, comfort stations, and the utility systems necessary to operate them. Big Meadows campground, the first in the park, was completed by the CCC in 1937 and included 20 camping sites and 50 sites for trailers. Other amenities included 20 fireplaces, 50 tables, and 6 drinking fountains

---

<sup>57</sup>Outside of the National Register boundary increase area, CCC buildings also still survive at their original location at Pinnacles. In addition, two buildings at the Headquarters maintenance area (HQ-0427, HQ-0426) appear to have been constructed for use by the CCC and later moved.

<sup>58</sup>Oral history interviews with CCC members conducted by the park in 1994 and 1995.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 53

---

all completed by the CCC.

Especially after the opening of the park, CCC workers were also involved in more elaborate construction projects. They for instance worked on the construction of maintenance area buildings at Big Meadows. Plans for the Blacksmith Shop (BM-0412) and the Repair Shop and Garage (BM-0410) both give CCC or ECW job numbers. CCC labor was also used in the construction of the Headquarters building.<sup>59</sup> Given the CCC's general charge of working on smaller projects, its excavation of the basement of the Administration Building was justified as "a borrow pit for grading a parking area in front of the building."<sup>60</sup> CCC enrollees also made construction material for park buildings including concrete shingles, and chestnut timbers and fence rails. The lumber was produced in a sawmill operated by the CCC.<sup>61</sup>

The saga of the decline of the ECW was a long one. When the ECW was re-authorized under the Emergency Relief Appropriation Act of 1935 (April 8, 1935), Roosevelt issued a directive calling for the doubling of the program to 600,000 workers. At the same time, however, he was beginning to plan for reducing the size of the program and making it permanent. He instructed the director of

---

<sup>59</sup>Oral interview with G.L. "Hop" Baughan, and "Final Construction Report Warehouse Project - 752-02-256," January 2, 1941. National Archives and Records Administration [NARA], RG 79, Entry 81, Box 120 (at Mid-Atlantic Regional facility in Philadelphia).

<sup>60</sup>To avoid competition with private sector enterprises, enrollees were not supposed to be used for the construction of larger buildings. A February 5, 1934 memorandum from the ECW stated, "Enrollees of the Civilian Conservation Corps will not be used in the construction of buildings of a permanent or semi-permanent nature except temporarily in an emergency which does not permit obtaining other labor." (Quoted in Otis, *The Forest Service and the CCC*, p.74. p. 74.) This prohibition may not have applied to skilled locally employed men (LEMs) who were hired by the ECW for their knowledge of local conditions.

<sup>61</sup>The chestnut timbers were known to have been used in the interior of the Administration Building. See, NARA RG 79, Entry, 42 Box 33 ("Virginia-Washington") (at NARA II, College Park, MD). Regarding concrete shingles, an oral history of CCC enrollee Benjamin Silvestri (available at the Shenandoah National Park Archives, Shenandoah National Park, Virginia) indicates that the CCC made concrete shingles for most of the buildings in the park. According to the construction report for the Headquarters' Warehouse project, the shingles were reinforced with galvanized wire and colored to imitate local chestnut shakes. See, "Final Construction Report Warehouse Project - 752-02-256."

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 54

---

the ECW to begin reducing the program to 300,000 by June 1, 1936. On June 28, 1937, Congress passed legislation reauthorizing and changing the name of the agency to the Civilian Conservation Corps. Although it was not made a permanent agency (it was to end three years later) Roosevelt signed the bill. In 1939, under legislation aimed at consolidating federal relief programs, the CCC came under the Federal Security Agency. By this time men were either taking jobs in better-paying defense-related jobs or were joining the military and it was becoming increasingly difficult to get CCC recruits. CCC programs became increasingly connected to the military, with some camps located at military bases, and certain defense-related training taking place at the camps. As of the bombing of Pearl Harbor (December 7, 1941), all CCC projects that did not directly relate to the war effort were terminated. The program ended completely on June 30, 1943.

#### Other Depression-Era Agencies

The Works Progress Administration (as of July 1, 1939, the Works Projects Administration) (WPA) was established in 1935 as part of the second wave of New Deal work relief programs. It was the successor organization to the Federal Emergency Relief Administration and the Civil Works Administration, both of which date to 1933. Unlike many other New Deal programs, the WPA supported skilled labor in a wide variety of fields, varying from art and theater to engineering. WPA projects varied from murals in post office buildings, to public highways and travel guides. Within the boundary addition area, the WPA is known to have supported the development of Big Meadows through construction of the water and sewer systems.<sup>62</sup> In addition, stone used for the Administration Building was quarried and hauled to the site by WPA workers.

The Public Works Administration (PWA) was initially established in 1933 as the Federal Emergency Administration of Public Works under the authority of the National Industrial Recovery Act. In 1939, it became a part of the Federal Works Agency. Its function was to plan, help construct, and finance a comprehensive program for federal and nonfederal governmental public works projects. The overall goals of the program included reducing unemployment, increasing consumers' purchasing power, improving standards of labor, and conserving natural resources. The organization acted to some degree like a bank or building and loan association, supplying funding, but at the same time employing inspectors to ensure that the project was being constructed according to plans and

---

<sup>62</sup>Harvey P. Benson, "Report of Harvey P. Benson, Resident Landscape Architect, July 1936." NARA RG79, Finding Aid 166, Entry 30, (NARA II, College Park, MD.) Lodges, waysides, and cabins were constructed by Shenandoah's concessionaire, Virginia Sky-Line. The buildings were, and are today, owned by the concessionaire.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 55

---

specifications. The PWA also supervised the bidding process, and dictated the price to be paid for labor. The type of projects funded by the PWA varied widely, and a 1939 PWA summary lists over 120 different types of buildings, varying from abattoirs to windmills, that were constructed using the funds. The National Park Service was a major recipient of PWA funds -- receiving some \$17,059,450 in the first year of the program. For projects located within parks, the National Park Service reviewed and supervised construction projects.

In the area included in this nomination, major projects known to be funded by the PWA include construction of the Headquarters Building and a warehouse building at the Headquarters maintenance area. The latter two projects were completed in 1940 for a total of \$76,659.42.<sup>63</sup> An addition to the Headquarters Building also was funded by the PWA.

Detailed reports of PWA projects were required, and reports for two projects in the boundary addition area shed light on the PWA construction process. In the case of the Administration Building (PWA Official Project 752-02-255), funds came from the Department of Interior allotment for 1938-41 under the PWA Act of 1938. Construction of the project, which was completed by force account, began December 22, 1938, and was completed July 15, 1940. Local laborers were employed by the park at wages varying from 35 to 75 cents per hour. The architect in charge (likely G.L. Baughan) recorded the timekeeping and provided semi-monthly time sheets to the park office for payrolls. Building materials came from suppliers in Virginia and Washington, D.C. Most millwork with the exception of window sash, was completed in the Headquarters carpenter shop. Stone for the walls was hauled to the site (by the WPA) and cut and shaped by local stonemasons.

National Park Service Planning, Landscape Design, and Architecture: The Work of the Branch of Plans and Designs<sup>64</sup>

All of the master planning and landscape design and most of the architectural design in the expanded boundary addition area during this period of the park's history was completed by the

---

<sup>63</sup>"Final Construction Report Administration Building - 752-02-255," January 2, 1941. NARA, RG 79, Finding Aid 166, Entry 81, Box 120 (at Mid-Atlantic Regional facility in Philadelphia).

<sup>64</sup>In 1933, what had previously been the Landscape Architecture Division of the National Park Service was renamed the Branch of Plans and Designs. Design work for Shenandoah was completed by the Eastern division, located in Yorktown, Virginia.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 56

---

National Park Service's Branch of Plans and Designs.<sup>65</sup> Headed up by Thomas C. Vint, the role of the Branch of Plans and Design was as follows:

*Functioning not unlike a private professional office, the Branch of Plans and Design . . . serves as professional adviser to the Service in matters of architecture and landscape architecture. The park superintendents and public utility operators are in the position of clients, while the Branch of Engineering and Bureau of Public Roads are collaborators.*

*Although not assuming direct charge of construction funds, the branch is vitally concerned with all phases of park development. Its function is to prepare a practical, well considered course of development for every park and monument (as represented on the Master Plan), which includes determination of the most appropriate type of architecture, and the preparation of a general plan of development for each community and administrative center. The problems to be solved in that plan are the protection of the landscape, location of buildings, bridges and parking areas, selection of type of architecture and restoration of natural features which may have been destroyed. The branch prepares the landscape and architectural plans for the Government facilities contracted through or constructed by the park superintendent's organization. It reviews the plans submitted by the park operators for tourist accommodations and the plans for road projects, preparing the architectural plans and specifications for bridges, guard rails, tunnel portals, and other structures constructed by the Bureau of Public Roads as adjuncts to the major road system.<sup>66</sup>*

Prior to the dedication of the park in 1936, one major responsibility of the Branch of Plans and Design (and the Branch of Engineering) was to supervise CCC workers in the park area.<sup>67</sup> The Branch of Plans and Design, which had chief responsibility for master planning and building design

---

<sup>65</sup>As discussed below, buildings constructed for the park concessionaire, Virginia Sky-Line, were designed by Richmond architect Marcellus Wright, Jr.

<sup>66</sup>Thomas Vint, "Report of the Branch of Plans and Design" (August 29, 1933), NARA, Record Group 79, Finding Aid 166, Entry 7B (at NARA II, College Park, MD).

<sup>67</sup>The CCC program as a whole placed heavy demands on the National Park Service, which expanded greatly to administer the program and other New Deal programs. In June 1940, 3,956 of 7,340 National Park Service employees were paid out of WPA, CCC, and/or PWA funds. Paige, *The Civilian Conservation Corps*, p. 46.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 57

---

in the park, was organized with a number of "resident landscape architects" who had responsibility for individual parks.<sup>68</sup> From 1935 to World War II, the resident landscape architect for Shenandoah was Harvey P. Benson. Benson was born April 25, 1905 in Matlock, Iowa. He received a BS in landscape architecture from Iowa State University in 1927 and after graduating worked in private practice in Illinois and Colorado for six years. He started working for the National Park Service in 1933 at Rocky Mountain National Park and shortly after was transferred to Chattanooga. He came to Shenandoah in 1935 and left it for duty with the Army during World War II. Following the war he continued working for the National Park Service in the regional office in Omaha, Nebraska, where he was involved in planning Bureau of Reclamation water projects. Still working for the National Park Service, he moved to San Francisco in the 1950s. He died, while residing in Sun City, California, around 1968.<sup>69</sup> At Shenandoah, in addition to supervising a substantial staff, Benson also was involved in the design of some buildings and in the final check on, for instance, master plans.

During the heyday of Depression-era work at the park at least a dozen individuals worked under Benson. Other "assistant" landscape architects or technicians who are known to have worked at the park during this time include: G.E. ("Hop") Baughan, M.J. Orcutt, Scudder Griffing, George C. Knox, Wallace G. Atkinson, Henri Charbanne, James K. Somerville, and James T. Swanson. The resident landscape architects were generally either landscape professionals or engineers; Baughan was reportedly the only architect in the group.<sup>70</sup> The planning work of the resident landscape architects was done in cooperation with the park superintendent and the regional National Park Service officials, who also had to sign off on the plans. The available reports of the landscape architects indicate that most planning decisions went through both the regional office and the park superintendent.

Although the park's landscape architects appear to have been responsible for many decisions regarding landscape design, others clearly played an important role. For instance, according to one report, National Park Service Chief Landscape Architect Thomas Vint was the source for a

---

<sup>68</sup> In 1934, Vint, as head of the division, moved to Washington as the work was divided between an eastern (Yorktown) office and a western (San Francisco) office.

<sup>69</sup>Biographical material on Benson is based on information supplied by Iowa State University Alumni Association, various oral interviews, and material accompanying an article by Benson. See, Harvey P. Benson, "The Skyline Drive," *The Regional Review*, February, 1940.

<sup>70</sup>Oral interview with G.E. Baughan.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 58

---

suggestion that more grass, annual and perennial flowers, and weeds (and fewer trees and shrubs) be planted in nondeveloped areas of the park. Vint also suggested that vines such as Virginia creeper, bittersweet, wild grape, and clematis be used on rock cuts and along guardwalls. Along the drive he favored opening up important vistas more and creating bays to "lighten up the ever-encroaching tree growth . . . thereby making the existing forest outline less monotonous and more interesting."<sup>71</sup>

As to architectural design, resident landscape architect G.E. Baughan recalls that most working drawings for park buildings were drawn up at the regional headquarters.<sup>72</sup> Preliminary sketches for some or all of the buildings, however, originated at the park.<sup>73</sup> These were sent to Region I of the National Park Service where the Branch of Plans & Design developed working drawings. Plans and details related to heating, plumbing and electric lighting were furnished by the Branch of Engineering. Some final plans however, apparently were completed at the park. Baughan recalls completing plans for park comfort stations in the mid-1930s. According to the title blocks on the plans, other buildings designed by the resident landscape architects included a pumphouse, Imhoff tank, and temporary fire towers -- all of which were prepared in the Luray offices. Baughan's name, as well as Harvey Benson's, appears on many of the plans for the buildings at the Headquarters maintenance area. From the regional office, during 1936-37, A. Paul Brown's initials appear on a

---

<sup>71</sup>Report of Harvey P. Benson. The issue of the degree to which vistas should be opened was a continuing one. By the end of the war years, many previously open areas had grown up, and it became necessary to again institute a program of vista clearing. There were objections from a number of sources to the cutting, but the idea prevailed that having outlooks with no views was nonsensical.

<sup>72</sup>Oral interview with G.E. Baughan. Baughan was a Virginia native who graduated from the University of Virginia School of Architecture in 1934. After graduation he took a job in Luray but soon after, in August 1936, went to work for the National Park Service at Shenandoah as the "camp technician junior architect." Thereafter, he did mostly engineering work, during the war with the Army Corps of Engineers. He eventually set up his own engineering and contracting firm, in Luray, which constructed a number of buildings at the park including Byrd Visitor Center.

<sup>73</sup>"Final Construction Report Administration Building - 752-02-255," January 2, 1941. NARA RG 79, Finding Aid 166, Entry 81, Box 120 (at Mid-Atlantic Regional facility in Philadelphia).

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 59

---

number of drawings, most located at the Big Meadows maintenance area.<sup>74</sup> Other named individuals that appear to have been specifically involved in the design of buildings included in this nomination are "architects Good and Higgins" (the Headquarters Administration Building).<sup>75</sup>

### Master Planning

As mentioned above, one of the most important tasks of the Branch of Plans and Designs was master planning. By the early 1920s, master planning had become one of the cornerstones of park development. Annual reports from this time emphasized the need for such plans to precede both National Park Service and concessionaire construction. By the early 1930s, plans for each National Park had been developed. Master plans were seen as a means to ensure that a park would develop in a rational manner that both preserved outstanding scenery and provided for public facilities.<sup>76</sup> Under National Park Service's design theory, park buildings were subordinate to the overall plan for the park. Buildings were to "bow deferentially before the park plan" rather than become a "feature." The park plan was supposed to determine the "size, character, location, and use" of every structure. Elements of the plan were interrelated to ensure the plan's "workability and harmony." Although much of the planning work related to the Skyline Drive was completed before the development of a master plan, all post-1935/36 development at Shenandoah was closely tied to plans both for the park as a whole and for individual "developed areas."<sup>77</sup>

---

<sup>74</sup>Brown apparently worked for the San Francisco office of the Branch of Plans and Design in the late 1920s during which time he designed buildings at Yakima Park in Mt. Rainier National Park. By the end of the 1930s he was working in the eastern region. Later, in the 1940s, he did planning for Big Bend National Park. (See Linda Flint McClelland, *Presenting Nature: The Historic Landscape Design of the National Park Service*, Washington, D.C.: National Park Service, United States Department of the Interior, 1993, p. 189). Brown's initials also appear in what apparently is an early sketch for the design of Big Meadows Lodge and a drawing of a standard comfort station design for the park.

<sup>75</sup>"Final Construction Report Administration Building - 752-02-255," The construction report states that Good & Higgins were involved in the inspection and approval of the stone construction. No additional information has been located concerning these architects.

<sup>76</sup>McClelland, p. 179.

<sup>77</sup>There was continuity before and after the establishment of the park because the ECW/CCC work done prior to the development of the master plans was supervised and/or designed by the same individuals

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 60

---

The Shenandoah master plans generally included a title sheet, index map, roads and trails map, fire control map, a general plan of the entire park that showed the location of "developed areas," and individual plans for developed areas. The earliest plans, in addition to showing the broad outlines of the park and the route of the Skyline Drive, provided detailed information on areas that were scheduled to be developed in the near future, such as Big Meadows. In addition to a 1935 plan, pre-World War II master plans are known to exist for at least 1936, 1937, 1938, 1939, and 1940.

Generally the plans grouped buildings together by function. These groupings were to be aesthetically pleasing and in harmony with the natural surroundings. A specific architectural theme for each grouping, drawn from local materials or architectural designs, was also selected.<sup>78</sup> One example of such a functional grouping was maintenance areas. In the 1920s, the concept of clustering all maintenance-related facilities together in a single location gained favor and resulted in preliminary schemes to be used in parks. Charles PUNCHARD came up with a typical ensemble that included stables, equipment sheds, a garage, a warehouse, shops for machinery, blacksmithing, electrical work, painting, plumbing, and carpentry. The buildings themselves were arranged for maximum efficiency and were usually located on side roads, out of the way of the park visitors. Most often, the maintenance area was located within the headquarters area.<sup>79</sup> In the National Register boundary expansion area, the Big Meadows and Headquarters maintenance areas followed these guidelines.<sup>80</sup> In general, both areas are rectilinear with (mostly long, narrow) buildings located around the periphery of the rectangle and within the rectangle in parallel rows.<sup>81</sup> The two areas had distinctive

---

from the National Park Service's Branch of Plans and Design who were involved in the master planning process after the creation of the park.

<sup>78</sup>McClelland, p.142.

<sup>79</sup>McClelland, p. 86.

<sup>80</sup>The Piney River and Simmons Gap maintenance areas were not included in the master plans and apparently were informally sited to take advantage of the pre-park facilities at these locations. At Piney Branch, a temporary ranger station for the district was needed so an existing CCC building was put into service. Thereafter maintenance facilities were also located at the site.

<sup>81</sup>Historic photographs of the area (and original plans) show the Big Meadows maintenance area enclosed by a wood fence. The rectilinear scheme may have its source in Charles PUNCHARD's 1919 scheme for the design of park administrative areas. He called for structures to be located around three



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 61

---

architectural themes -- the Headquarters area employing local sandstone for exterior walls and the Big Meadows area employing flitched-edge vertical siding.

Campground design followed a different path. In the early 1920s, with the increasing popularity of automobile travel, national parks enlarged their campgrounds to accommodate the growing number of motorists/campers. At the time, campgrounds were located in open fields or forest clearings, and provided at most water, fireplaces, and a comfort station. However, individual camp sites were generally not well defined and overall the campgrounds were not well organized. Cars were haphazardly parked, tents were hung from the sides of vehicles, and campers set up portable tables.<sup>82</sup> Camping areas became increasingly unattractive as standing wood was cut down for fires, the remains of campfires were located randomly throughout, automobiles dripped oil into the soil, and campers' constant trampling on the ground killed off vegetation, in particular harming trees by damaging their roots. As a result of these problems, by the late 1920s, a number of campgrounds were abandoned.

The solution to the problems were to come from an unexpected source. In 1932, the U.S. Forest Service introduced the Meinecke plan for campground development, whose application resulted in the modern campground. E. P. Meinecke was a plant pathologist who had studied at length the problems of the Forest Service campgrounds which were similar to those of the National Park system. His theory of campground design was premised on providing a naturalistic campground environment for the camper, while preserving the existing natural plant life.

To implement this, Meinecke first urged that more attention be paid to where campgrounds were located. To ensure that sites could withstand intense use, he proposed that they be selected based on soil type, projected length of seasonal use, type of vegetation, and altitude. The heart of the Meinecke plan, however, was campground design. Fundamental to his plan was the dividing of the campground into individual campsites. Each campsite would consist of a parking space and a clearing equipped with a fireplace, a fixed picnic table, and a tent site.<sup>83</sup> Vegetation would be protected from automobiles by strategically placed boulders and logs. Permanent paths to comfort stations and other locations were employed to prevent a proliferation of different trails. Trees and

---

sides of a centrally located open square. Later industrial groupings "were arranged to form enclosed compounds." See McClelland, p. 87, 142.

<sup>82</sup>McClelland, p. 161.

<sup>83</sup>McClelland, p. 162.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 62

---

shrubs between campsites served as screens, providing privacy and a naturalistic setting. Amphitheaters and campfire circles were also included as essential elements of the new campground. The design allowed for parking in parking spurs adjacent to the individual campsites along one-way loop roads, which limited the amount of automobile-related damage to the site. It took several years for the Meinecke plan to be successfully implemented, because of the slow nature of clearing vegetation and building roads. However, his ideas soon became so widely adopted that park planners referred to the "meineckizing" of campgrounds.<sup>84</sup>

In the National Register boundary addition area, the Meinecke plan was clearly the starting place for the design of the Big Meadows campground. The use of a one-way road system and individual campsites provisioned with fixed tables, a tent site, fireplaces, and parking spurs comes directly from Meinecke. A later innovation, however, were the camping sites that span the width of the loop and provide access to campsites from two roads. The arrangement, which was designed for use by travel trailers, appeared in the National Park Service publication, *Park and Recreation Structures*, a year after the opening of the campground in 1937.<sup>85</sup>

Meinecke also addressed the design of picnic areas. For these also, he advocated a one-way loop road system with off-road parking and fixed fireplace areas. In the boundary addition area, both the Big Meadows and Dickey Ridge picnic areas generally follow this plan. Both employ pull-in parking areas, a one-way traffic pattern, and fixed sites for fire grates. Both picnic areas were designed with permanent paths leading to and from comfort stations and parking areas. The two areas differ significantly in their topography and therefore in their individual design. The Dickey Ridge picnic area is built around a small knoll, and a central path runs along the ridge with side paths connecting to the parking areas. At Big Meadows, the site is largely flat and a cloverleaf pattern was selected for the layout of the paths.

The National Park Service also approved the design of concession facilities and generally decided on the appropriate location for facilities (as consistent with the park master plan). In general, concessionary facilities followed the overall National Park Service design principles (use of native materials, fitting buildings to the setting, etc.). The National Park Service initiated the concept of

---

<sup>84</sup>McClelland, p. 163.

<sup>85</sup>McClelland, p. 222.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 63

---

waysides -- an idea that originated with landscape architect Jens Jensen.<sup>86</sup> As seen at Dickey Ridge and Big Meadows, waysides were areas located along a parkway that included visitor services such as gasoline stations, comfort stations, stores, restaurants, and often picnic areas. The concept of combining a number of functions in a single building and in grouping buildings together to make the least impact on the landscape was consistent with the National Park Service's naturalist design ideal.

The design of "housekeeping cabins" like those at Big Meadows were also the subject of study by the National Park Service.<sup>87</sup> Cabin areas first were established in national parks in the mid-1920s. Their popularity, and the desire of concessionaires to greatly expand the number of such cabin camps sparked a 1929 study of housekeeping cabins and resulting standards for housekeeping cabins. The standards prescribed the size of the cabin as well as specifics such as the number of windows. The placement of cabins was also somewhat controversial, as concessionaires in other parks were anxious to squeeze as many into a small area as possible. This oftentimes conflicted with the National Park Service principle of integrating buildings to sites. At Big Meadows, although an extensive collection of cabins was planned, only seven cabins were built, and these were grouped together in a loose circular arrangement in a wooded area facing Black Rock.

### The Rustic Style

National Park Service landscape and architectural design at Shenandoah took much from the rustic style -- what is often referred to as the National Park Service's "official" style. One of the most basic tenants of the style, however, was to draw upon existing local design. At Shenandoah, an obvious precedent for National Park Service designers to look to, especially for recreational buildings, were the existing buildings at Skyland. In particular, the common rustic vernacular vocabulary seen in the cabins at Skyland, was a design source for other structures throughout the park. Pollack had initially specified that dwellings at Skyland be "rustic cabins." They were to be either of log construction or, if of frame construction, they were to be covered with wood shingles or (later) chestnut bark siding. Not surprisingly, the typical cabin at Skyland closely resembled the cabin designs of the permanent residents of the mountains who built the Skyland houses.<sup>88</sup> The latter -- local vernacular design --

---

<sup>86</sup>McClelland p. 224.

<sup>87</sup>See generally, McClelland, p. 142. A group of cabins were also constructed at Dickey Ridge; these were later moved to Lewis Mountain and other areas.

<sup>88</sup>Reed Engle, "Skyland Historic District National Register Nomination [draft], 1995, page 9.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 64

---

represented another major design source for National Park Service designers.

On an academic level, the rustic style had its roots in the naturalistic work of Andrew Jackson Downing. His work, in turn, was built on eighteenth- and early nineteenth-century British landscape designers of the "picturesque" school (including Humphrey Repton, William Kent, and Capability Brown). Downing published his ideas in a periodical (*The Horticulturalist*) and a number of books including *Cottage Residences*, *The Architecture of Country Houses* and *Treatise on the Theory and Practice of Landscape Gardening*. In general, the ideal of the picturesque involved an emphasis on irregularity and variation. Downing's landscape work is characterized by a sequence of changing vistas, and variations in topography and natural features. Specific elements included winding paths and drives, open meadows, groves of evergreens, natural water elements (including waterfalls, bubbling brooks, etc.), and rock outcroppings. Downing paid particular attention to the design of the man-made elements and advocated a common design initiative behind major built elements and the garden. Architectural features, although important elements of the design, were to be subordinate to, and blend with, the natural surroundings. The use of native materials, including logs and rocks, helped to accomplish this goal. Structures designed to be set in the landscape -- bridges, pavilions, etc. -- were simple structures typically of (unpeeled) logs and branches, or unfinished stone.<sup>89</sup>

In architecture, aside from Downing's work, the rustic design impetus owes debts to a number of different sources. The first and strongest concentration of buildings in the rustic "camp" style, was in the camps of the Adirondacks constructed in the 1880s through the 1920s. Located in natural settings often close to lakes, the camps usually consisted of a number of separate buildings including cabins, lodges, and boat houses. The buildings were positioned to take advantage of views and to fit comfortably in the landscape. Buildings were constructed of chinked logs and set on stone foundations that were often battered. The oversized timbers used for the roofs and beams were exposed. Large stone chimneys, often protruding high above the roof ridge, were typical. The houses often incorporated stylistic elements from a variety of European vernacular styles as well as the vernacular log cabins native to the area.

The Adirondack "camp" style although dating to somewhat earlier, was first documented in 1889 in

---

<sup>89</sup>After Downing's untimely death in 1852, his style was adopted and his teachings were followed by a variety of landscape designers. The most notable of these were Calvert Vaux (his partner for a short period of time) and Frederick Law Olmsted, Sr.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 65

---

*Log Cabins: How to Build and Furnish Them*, by William Wicks. In addition to discussing the construction of the camp buildings, Wicks also emphasized the concept that the buildings should "grow out of" of the site. Some of the best examples of the camp style are the buildings of William West Durant, one of the major architects of lodges and camps in the Adirondack area.

Major characteristics of the Adirondack version of the style that were incorporated into the design of recreational buildings in the National Register boundary expansion area include the reliance on native materials, the emphasis on fitting the buildings to the site, and the use of porches, outdoor decks, stone chimneys, exposed interior beams, and casement windows.

Major precursors and/or contributors to the "rustic" or "camp" style are the Arts and Crafts movement (of which it is arguably a part) and the earlier Shingle Style, and Richardsonian Romanesque movements. The Shingle style came into prominence in the 1870s. The ultimate expression of the style was along the East Coast, particularly in seaside resort communities such as Newport, Rhode Island. The Shingle style shared the Victorian emphasis on variety in massing, pattern, and texture. It is characterized foremost by the use of wood shingles on walls, its asymmetrical facades, and complicated massing (often including towers, porte cocheres, etc.). Another influence on the Rustic style was Richardsonian Romanesque, a stylistic spinoff of the work of Henry Hobson Richardson (1838-86) whose work was most popular from 1880-1900. Like the Shingle style, Richardsonian Romanesque shared some of the Victorian emphasis on variation in pattern, color, and massing; however, these elements became greatly simplified. Its key characteristics include heavy stonework and rounded arches resting on short, thick columns.

Another important antecedent of the Rustic style was the Arts and Crafts movement, which had its basic philosophical roots in the works of English craftsman/designer and writer William Morris. The movement influenced a number of important regional styles and nationally prominent architects. In terms of architecture -- the movement was as strong or stronger relative to the decorative arts -- the underlying tenets of the style include an emphasis on craftsmanship (often by hand), strong connections to the natural world through the use of intermediate areas (such as pergolas and porches) between building and grounds, and an overall horizontal emphasis in design. Although certain of these characteristics were revealed on the exterior of a building, much of what truly characterizes an Arts and Crafts-influenced structure was seen in the interior. Here an emphasis on craftsmanship tended to be revealed in materials (wood, stained glass, metal work) and workmanship/decorative treatment. The diverse influence of the Arts and Crafts movement can be seen in the work of the Bernard Maybeck and Greene and Greene in California, in the work publicized by Gustave Stickley in *The Craftsman* magazine, in the widespread popularity of the bungalow form, and in the Prairie-style work that originated in the mid-west.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 66

---

### Landscape Design

Landscape design of this period in the park area was a product of well-developed National Park Service design theory.<sup>90</sup> Much of this theory (such as the use of curvilinear design) had its origin in the naturalistic landscape design of Downing. Perhaps the most significant component of the design theory was the importance of preserving existing landscape and restoring landscape altered by man to its original condition. National Park Service landscape design theory emphasized the complete understanding of particular landscapes and plants within them as the foundation of good design. For instance, the restoration of native flora and fauna required specific knowledge about the conditions under which specific plants thrived. Echoing Downing, National Park Service design theory emphasized the opportunity for a series of unfolding scenes threaded together, for instance, by roads or paths. Trails were to be designed so that important views were viewed at turns in the path at rising grades. Smaller-scale scenes such as those of specific objects were best viewed straight ahead and from a distance. Broad vistas were best seen at an angle. The scenery was to be allotted along the trail in a variety of settings. Roads, trails, and buildings while being positioned to take advantage of views, were at the same time placed so as to be as inconspicuous as possible.

Much of the landscaping around developed areas in the park was completed by CCC workers. Among the CCC landscape-related activities were the previously mentioned "landscape naturalization" program. Fraser fir (*Abies fraseri*), red spruce (*Picea rubens*), and Canadian yew (*Taxus canadensis*) were especially singled out for cultivation. These declining species in the park were started via transplants and seeds, and studies were made about their germination and growth to determine their appropriateness for the area. Stock was planted on slopes to control erosion, around picnic areas and campgrounds for screening (for privacy or to conceal "undesirable" objects), to frame vistas, and for transplanting to heavily used areas to replace mature stands in the future. Under this project, 300,000 trees or shrubs were transplanted.<sup>91</sup>

One of the first systematic studies of the landscaping needs of the park was completed in June 1938. R.B. Moore, a forester, conducted a field survey of the entire park area to determine the location of areas that were in need of planting, erosion control, etc. The overall conclusions of the report were threefold. First, that approximately 245 acres of eroded cultivated areas or pastures and 10

---

<sup>90</sup>For a thorough discussion of all aspects of National Park Service design theory, see generally, Linda McClelland, *Presenting Nature*.

<sup>91</sup>Lambert, *Administrative History*, p. 198.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 67

---

miles of eroded paths should be replanted with native species. Second, that areas with dense sod, which would not easily revert to woods, be replanted with trees. Third, that indigenous species, in particular trees and shrubs that were uncommon in the park (including fir, spruce, fringe tree, Canadian yew, rosebay rhododendron, catawba rhododendron, mountain ash, and pines other than Virginia pine) should be underplanted (that is, planted in existing forested areas) on chosen sites. The second suggestion, of replanting on sod areas was not approved, but the other two suggestions were followed.

In the boundary addition area, landscape design closely followed the National Park Service's naturalistic style. Although detailed original planting plans have not been located, in general the designs followed the basic principle of preserving (or restoring) the natural surroundings through the use of native species, and de-emphasizing man-made intrusions.

### Architectural Design

As discussed above, National Park Service buildings of this era, were in the Rustic style. The elements of the style were formalized in a 1938 NPS publication entitled *Park and Recreation Structures*. Like the earlier *Park Structures and Facilities* (1935) upon which it was based, the book incorporated the design philosophy of the National Park Service as developed by Thomas Vint, Herbert Maier, and others.<sup>92</sup> Although the style basically served as the National Park Service's "national style," it was considered to be best suited to wilderness park areas. The aim of the style as interpreted by National Park Service designers, was to achieve "sympathy with natural surroundings and with the past" through the use of native materials in proper scale<sup>93</sup> and the avoidance of severely straight lines and over-sophistication.

The successful use of native materials depended on both the use of local materials and on the way in which the materials were used. Stonework and log construction were particularly emphasized. Rock work first was required to be of the proper scale. (Generally small rocks were not appropriate.) The proper construction of rock walls was set out for particular attention, the overall aim being a look of informality. To achieve this, it was recommended that larger rocks predominate

---

<sup>92</sup>Many cornerstones of the style of course, have their immediate source in the work of Downing and Vaux.

<sup>93</sup>More specifically, structural elements, logs, timbers, and rocks should be matched to the scale of the surrounding environment.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 68

---

at the bottom of a wall and smaller sizes predominate at the top. A mix of sizes of rocks was seen as necessary to add variety and interest. In general it was suggested that rock work not be laid in courses. For log construction, logs were selected that were "pleasingly knotted" rather than uniform. In general, the textural surface of the log was maintained, although bark was stripped from logs to avoid insects, wood rot, and litter (when the bark fell off).

To further aid in the important concept of subordination of a structure to its environment, five principles were followed. As to the first of these -- the use of existing natural screening -- the structure was to be located to take advantage of extant plant material or natural features. Lacking these, screening was developed by using local plant materials. (However, "planting out" -- totally hiding structures behind plantings -- was avoided). Signs showing the way to a less visible building were preferable "to the shock of finding a building intruding at a focal point or visible for great distances."

According to National Park Service design theory, the second factor important in "assimilating" a structure into its environment was the use of color. The appropriate color of a building was dictated by the colors of the immediate surroundings. In general, warm browns helped "retire" a building in a wooded setting. Light driftwood grey was also recommended. Where a contrasting color was necessary (i.e., for window muntins) a light buff or stone color was endorsed. Green, although relating well to the forest colors, was avoided because it was a difficult color "to get right" and because of its tendency to fade. Brown or weathered gray roofs were seen as blending better with the earth colors and tree trunks than other colors, in particular green, which was seen as being too solid and monotonous.

Another principle used to assimilate a building to a site was the use of foundation plantings (i.e., plantings that cover the "otherwise unhappy line of demarcation between building and ground.") Rock footings served the same purpose, as did the addition of a batter to a stone wall. The latter, if done well, gave the building the appearance of "having sprung from the soil. Park structures giving that impression are of the elect."

The other principles related to the design of the building. In contrast to urban forms, an emphasis only on the front facade of the building was to be avoided since park buildings were generally viewed from all sides. Where necessary, service functions were screened by a palisade. A final factor important in subordinating a building to its environment was a low silhouette and an overall emphasis on horizontal lines. A low roof pitch (less than one-third where practical) kept the roof from dominating the structure and the setting.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 69

---

The National Park Service buildings of this era in the National Register boundary extension area follow these tenets. A majority are low gabled structures of wood (including log) construction. Most are painted brown.<sup>94</sup> Some employ uncoursed native stone. Another common characteristic is that in general, buildings within a particular geographic/use "grouping" share common materials and/or design elements (i.e., "architectural theme"). For instance, buildings of this era in the Headquarters maintenance area were mostly constructed of local sandstone and buildings at the Big Meadows maintenance area all have vertical slab siding and had wood shingle roofs (now being restored).

#### Virginia Sky-Line and Concessionaire Construction

With its opening in 1936, thousands of visitors poured into the park and utilized the existing recreational facilities, driving on the scenic Skyline Drive, and enjoying the out-of-doors at picnic areas. Additional picnic areas were soon opened (including Dickey Ridge, Pinnacles, and Big Meadows) to accommodate the crowds, as was the first campground, completed in 1937, at Big Meadows.

Park-owned recreational areas (such as picnic areas) were augmented by privately owned facilities. When the park opened, existing operations at Skyland and Panorama, as well as the Spotswood Tearoom, continued to function under agreements with the National Park Service. However, with the flood of tourists that accompanied the opening of Skyline Drive, there was a concern that the existing commercial operations would not be sufficient, and the National Park Service began plans to expand tourist facilities.

In December 1932, Chief Landscape Architect Thomas Vint visited the park and recommended that facilities for food, gasoline stations, and souvenirs be developed at four or five locations along the drive, and that overnight facilities, with more formal restaurants, should be located at Skyland and Big Meadows. He also recommended that all of the concessions be placed in the hands of a single concessionaire. However, due to internal disagreement within the National Park Service and to the fact that bids had to be advertised multiple times, it was February 1937 before a concessionaire was selected. A contract was finally signed with a group called Virginia Sky-Line, Inc., headed up by Richmond businessman Mason Magnum. Their contract, which ran for 20 years, permitted the company to "provide, establish, maintain and operate lodges and camps for visitors, and stores, cafeterias, barber shops, bathhouses, gasoline filling stations, automobile and saddle horse

---

<sup>94</sup>Paint analysis (Engle, 1994-95) indicates that the buildings at the Headquarters Maintenance area were originally a medium grey/brown.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 70

---

transportation facilities . . . <sup>95</sup> The contract called for Virginia Sky-Line to pay the National Park Service a fee of \$1,250 annually plus a percentage of the net profit over 6% of the invested capital. As part of their contract, Virginia Sky-Line took over operation of all of the existing commercial enterprises within the park.<sup>96</sup>

A year prior to the awarding of the contract, the National Park Service had unveiled ambitious plans calling for investments (by the prospective concessionaire) of up to \$1,750,000 for reconditioning existing facilities, and constructing large new facilities at Big Meadows and four other locations. Smaller facilities were planned for Dickey Ridge, and six other locations. Included in this scheme were plans for a series of seven large "cabin colonies," including one at Big Meadows. Virginia Sky-Line, however, favored a more conservative approach. It first planned a central lodge and a few overnight cabins at Big Meadows. Soon thereafter, it agreed to additional "roadside stations" (including the one at Big Meadows) and three other buildings, including the new lodge at Dickey Ridge.

The first work accomplished by the concessionaire in 1937 was the "enlarging and installing of modern equipment" at the existing facilities which pre-dated the park. By 1938, the Big Meadows wayside was constructed. The Dickey Ridge facility, which included a dining room for 60 people as well as a dancing terrace, coffee shop, and service station, opened its doors in May 1938. Cabins were constructed and in use at Big Meadows by 1939 (however, 7 cabins rather than the planned 113 were actually constructed). The lodge at Big Meadows, which included both a restaurant accommodating 150 and 26 guest rooms, was also completed in 1939.

Most concessionaire buildings, including lodges, cabins, restaurants, commercial waysides and associated utility buildings, were designed by Richmond architect Marcellus Wright, Jr. Wright was born in 1907 in Henrico County, Virginia. His father, Marcellus E. Wright, Sr., also an architect, was a founding partner in what is today the Richmond architectural firm of Marcellus Wright, Cox & Smith. Like his father, Wright, Jr., attended the University of Pennsylvania, where he received a Bachelor's degree in Architecture in 1929 and a Master's in Architecture in 1930. After

---

<sup>95</sup>Lambert, *Administrative History*, p. 262.

<sup>96</sup>With the agreement, George Freeman Pollack's long official association with the Skyland development came to an end and in spite of his desire to stay on and manage Skyland for the new concessionaire he went into forced retirement. He requested and received permission to occupy two buildings (Massanutten Cottage and the nearby Annex) for the duration of his own and his wife's life.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 71

---

completing his education, he worked as a draftsman in his father's firm for a few years, then served as an engineer in Richmond for the WPA and Emergency Relief Administration, then in 1935-36 he traveled to Iraq and served as the architect for the Joint Assyrian [Archeological] Expedition. On his return, he became the architect for Virginia Sky-Line, a position he retained until 1940. In 1939, he brought the client with him when he returned to work with his father in the firm that then became Marcellus Wright & Son. During the war years he served as a major in the U.S. Army Corps of Engineers. After the war, he became a principal, then managing partner, in the architectural firm founded by his father (known later as Marcellus Wright & Partners, then Marcellus Wright, Cox, Cilimberg & Ladd). He was the architect for the New State Office Building (Richmond, 1955) and his primary works include Western State Hospital (Staunton, 1946-64) and Byrd Airport (Richmond, 1948-69). He became a fellow of the American Institute of Architects in 1956. His community service in the Richmond area included work with a variety of governmental and nonprofit organizations.

Mason Magnum, president of Virginia Sky-Line, was a personal friend of Wright's and was responsible for his coming to work at Shenandoah.<sup>97</sup> Prior to the major design work for the buildings, Wright did travel to some of the western parks to look at models for the Shenandoah buildings, but given the quite different location and program, apparently took little from these examples.<sup>98</sup> Instead, Wright studied the problem anew, and came up with design solutions that were most closely inspired by the setting, in particular, the area's topography. His major designs at Shenandoah -- as seen for instance at Big Meadows Lodge -- employ native materials and are marked by a small-scale domestic quality. In general, they are long narrow compositions that hug the ridge (and/or the drive) and are divided into a number of component parts that easily adjust to the topography of the site. They are sited to take advantage of important views into the valley.

In terms of materials, in addition to the native chestnut and local stone, Wright also typically employed glass blocks as accents (always near the main entrance of a building), as well as a unique

---

<sup>97</sup>For information in this section about Wright and his work at Shenandoah, see generally, transcript of oral interview with Wright conducted September 25, 1995. (Shen. Archives) In this interview, Wright states that the first work he did at Shenandoah was the recordation of existing pre-park buildings. These drawings have not yet been identified.

<sup>98</sup>This was consistent with National Park Service design theory, which emphasized that the appropriate solution for an individual park was a function of such features as the geography, local materials, and local historical design antecedents.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 72

---

material that was to come to typify roofing materials at the park, concrete shingles. As to these materials, Wright apparently heard of a local Richmond contractor who was producing the shingles, and thought that their fireproof qualities (given the distance of the site from fire stations) made their use appropriate at Shenandoah.<sup>99</sup> To support their weight, the buildings had to be designed with particularly heavy roof structures. Following Wright's introduction of their use, they were also employed in other buildings in the park designed by the National Park Service. According to Wright, his use of glass blocks was also strictly utilitarian; they served to provide light in areas where for one reason or another he did not want to have a regular window.

Wright was given a relatively free hand in both the designing of the buildings and their exact siting.<sup>100</sup> There was an easy cooperative working relationship between himself, Virginia Sky-Line, and the National Park Service which made getting the approval of all parties an easy process. He made biweekly visits to the site to review construction progress. Between times, National Park Service personnel kept their eye on construction. The company apparently had its own small construction crew for smaller buildings, but contracted out larger facilities.<sup>101</sup> Wright's involvement at Shenandoah effectively ended around 1939 when most of the buildings were completed.<sup>102</sup>

---

<sup>99</sup>The specifications for the Big Meadow lodge indicate that the likely supplier was the Hendricks Coal Company of Richmond, VA. Concrete shingles on National Park Service buildings were made by CCC labor.

<sup>100</sup>Plans, however, indicate that revisions were made to Wright's plans by the concessionaire. For instance, a barrel-vaulted ceiling was substituted for a ceiling which was open to the beams at the Dickey Ridge Lodge.

<sup>101</sup>Benson, "The Skyline Drive," p. 8.

<sup>102</sup>One major unknown about Wright's buildings relates to the role of the firm of Barber & McMurry, Knoxville, TN in the design of the Big Meadows and Dickey Ridge Lodges. Plans for both buildings show the firm as "Consulting Architects." Although the firm is still operating, no information has been located about their precise role in the design of the Shenandoah buildings. The firm was founded in 1915, and in the 1930s had a diverse practice with a particular emphasis on large domestic projects, churches, and schools. In 1936, the firm was involved in the design of the administration building for Great Smoky Mountains National Park so at least at that time the firm had an on-going relationship with the National Park Service.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 73

---

## WAR AND POST-WAR PARK ADMINISTRATION, WWII to 1950

The war years brought a number of major changes to the park and to the National Register boundary addition area. One of the most significant was that the plentiful New Deal labor and money that had largely built the park abruptly ended. Between 1940 and 1949 no new funds were appropriated for buildings or physical improvements at the park.<sup>103</sup> The number of CCC participants had started to decline for a number of years before the war as an increasing number of enrollees were employed in defense-related industries. However, all CCC work programs were ordered to cease as of July 15, 1942, and enrollees were put to work closing the operations. As discussed below, park officials sought to replace some of the lost help with Civilian Public Service camps staffed by conscientious objectors.

Another major change that resulted from the war was a vast decline in the number of park visitors. The level of more than a million visitors per year achieved in 1937 soon fell as gas rationing was implemented. In May 1942, visitation was down by 75%, and by the middle of the war, the number of visitors was one twentieth of the level before the war.<sup>104</sup> Facilities at the park shut their doors one by one. By July 1942, Big Meadows Lodge closed, and two months later all commercial operations had ceased. Although some visitors came to the park on buses, pleasure driving was banned, and shortages -- as well as gas and tire rationing -- provided further disincentives to travel to the park.

The war had other, indirect, effects on the boundary addition area. Concerned that Washington could be a bombing target, the Smithsonian Institution shipped a substantial proportion of its collection to the Headquarters area of the park in November 1942. Items came from the collections of what are now the Natural History, American History, and Air and Space Museums.<sup>105</sup> There were two major categories of collections that were moved. The first was the nation's irreplaceable "national treasures." In this category were the "Star Spangled Banner" (the flag that was immortalized in Francis Scott Key's poem that, set to music, became the national anthem) and George Washington's uniform and sword. The second major category of items transferred were

---

<sup>103</sup>Page News & Courier, 5 May 1949, Shenandoah National Park Archives, Shenandoah National Park, VA.

<sup>104</sup>Lambert, *Administrative History*, p. 298.

<sup>105</sup>Information relating to the Smithsonian materials was provided by Don Kloster, a curator of the American History Museum's military collection.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 74

---

those needed to form the nucleus of a new national museum in the event that the Washington facilities were destroyed. In this category were thousands of natural history specimens. Also among the items shipped to the park were over 300 patent models.

Most of the Smithsonian's collections apparently were stored in the warehouse (HQ-0406) at the Headquarters area.<sup>106</sup> There, the large storage room was altered to control the humidity. (Despite this, there were apparently problems with the deterioration of the bird collections.) Park items that were originally stored in the area were moved to HQ-0401, which had been retrofitted by the Smithsonian for the purposes. (A dirt floor was replaced with a concrete one and the open bays in the front of the building were filled in.) The Smithsonian also paid for the construction of HQ-0409 (now the Gas & Oil House) to house a "power plant" to heat the warehouse. The power plant could not be acquired, and the building was used for storage instead; the stone veneer was never completed.<sup>107</sup> The area was patrolled by four Smithsonian guards who used HQ-0409 as a shelter. Carl Mitman, a Smithsonian employee familiar with collections management, relocated to the area to oversee the collection. Construction work on both of the buildings was done by Civilian Public Service workers.<sup>108</sup> The Smithsonian's collection was returned to Washington in November 1944.

The initiation of a Civilian Public Service (CPS) camp at Shenandoah cushioned somewhat the blow of losing CCC labor. CPS camps provided public service in civilian work as an alternative to military service for conscientious objectors (COs). The camp (CPS 45), housed at old CCC Camp 10 at Pinnacles, operated from August 1942 to June 1946. The camp had between 75 and 130 men and was operated by the Mennonite Central Committee. The duties of CPS workers at Shenandoah were similar to those of the CCC at the park, and included fire protection, construction of trails, roads, utilities, and park structures, erosion control, and planting. Within the area included in this nomination, in 1943 they completed the renovation of the former technical service quarters at CCC

---

<sup>106</sup>NARA, RG 79, Entry 62, Boxes 11 and 12, "Records Relating to CPS Camps 1941-48" (at NARA II, College Park, MD).

<sup>107</sup>An oil and gas building had long been planned for the spot where HQ-0409 was located and plans for the alterations to the warehouse show that the heater building would be used in the future as a gas and oil building.

<sup>108</sup>NARA, RG 79, Entry 62, Boxes 11 and 12, "Records relating to CPS Camps 1941-48," (at NARA II, College Park, MD).

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 75

---

camp NP-12 at Piney River for use as the North District ranger's station.<sup>109</sup> Around 1943, CPS workers also were involved in the construction of the oil and gas storage building, at the Headquarters area, that was constructed for use by the Smithsonian, and made alterations in HQ-0401 to accommodate materials moved out of the warehouse building.

With the end of the war in 1945, travel was once again possible, and the number of visitors to the park did gradually rise, although the level of visitorship never regained its preeminent pre-war position relative to other national parks. Virginia Sky-Line reopened some facilities in September 1945 and the rest of the facilities in the spring of 1946. By 1949, visitation had regained its pre-war million-visitor level. In terms of construction at the park, the war and post-war period marked a period of quietude. It was not until the Mission 66 program (see below) was instituted that any major changes to the built environment of the park took place.

### Architecture

In the early years of the war, a minimal amount of work was done to complete buildings that had already been started. Within the area included in this nomination, the only new construction was completed in the Headquarters area. A number of buildings in the area were completed in the early war years, and renovation work was done on at least one of the older buildings in the Headquarters area in the early 1940s. In addition to the completion of the sandstone-covered Administration and utility buildings, three additional residences were built at Headquarters. These were small side-gable houses with wood siding that blended well with the pre-park structures on the site. These, as well as many of the utility buildings, were designed by "Hop" Baughan, one of the local National Park Service planners who was trained as an architect. In general, however, no new funding was available for construction, and many materials were so scarce that construction was difficult.

With the transfer of items from the Smithsonian to the warehouse at the Headquarters area, a simple concrete-block "Gas and Oil" building was constructed. Due to wartime shortages it was built using materials on hand. Its design is similar to a "Gas and Oil" building constructed at Big Meadows four years earlier. The building was intended to have a stone veneer similar to a number of the other nearby buildings. Although the veneer was never added, metal masonry wall ties to attach the veneer still exist on the exterior of the building.

---

<sup>109</sup>According to a CPS report, the technical service quarters building was selected as the new site of the North District's ranger station only as "a temporary expedient." NARA, RG 79, Finding Aid 166, Entry 62 (NARA II, College Park, MD).

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 76

---

After the war, with the increase in visitors, existing tourist facilities soon became strained, and the National Park Service pushed Virginia Sky-Line to build additional facilities including some at Big Meadows. Virginia Sky-Line, however, balked at making such a large commitment of capital so near the expiration of their contract, and a new 20-year contract was drawn up and signed in June 1952. By the late 1940s, the first multi-unit "cottages" were constructed at Big Meadows. The design was sympathetic with, if not totally within, the rustic stylistic vein. They were designed by the Richmond firm of Louis Ballou and Charles C. Justice.

Of the buildings that were to follow, many were a product of the National Park Service's Mission 66 planning initiative. In answer to the lack of money and development that had come with the war and post-war period, throughout the National Park Service planning began in the 1950s to have "a program which, if followed, will see the National Park system adequately developed and adequately staffed by 1966, the 50th anniversary year of the Service . . ." <sup>110</sup> Housing was recognized as one of the critical needs in the parks, and many of the buildings constructed under the Mission 66 program both in the boundary addition area and throughout the Park System were to house park employees. <sup>111</sup> The National Park Service developed three standardized house plans to fill the need. <sup>112</sup> In these designs, the traditional rustic style, which had become almost synonymous with National Park Service architecture, gave way to cheaper and faster-to-build modern designs. <sup>113</sup> The standard design used in Shenandoah could be considered a typical suburban ranch-style dwelling. It was a one-story house with three bedrooms, one and one-half baths, a utility room, living and dining rooms, and a carport. Roof types and materials, window styles, and exterior finishes, all could be adjusted to fit the particular setting without affecting the particular design. Variety was achieved by moving the carport or entrance. There are a total of eight houses in the park constructed using the Mission 66 standardized plans, six of which are within the boundary addition, at the Headquarters area. All have been determined non-eligible for the National Register.

---

<sup>110</sup>Department of Interior Annual Report, 1955, quoted in Lambert, *Administrative History*, p. 314.

<sup>111</sup>Throughout the Park System, 2,000 new houses for park employees were constructed.

<sup>112</sup>See *Shenandoah National Park Determination of Eligibility for National Register Context Statement for Mission 66 Program*.

<sup>113</sup>Under Congressional limits, the house plans were restricted in size (less than 1,200 square feet) and cost (less than \$18,000). The house plans were also touted as permitting rapid turnaround time to the builder once a location was selected.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 77

---

Later construction, including that of the large Byrd Visitor Center (1966) at the Big Meadow Wayside area, has been of modern design. The new construction has not been consistent with, or sympathetic to, the design of the majority of the buildings within the historic district.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 78

---

## CHRONOLOGY OF MAJOR CONSTRUCTION/DEVELOPMENT BY AREA

### Big Meadows

#### 1935

" A preliminary plan of Big Meadows presented to Mr. Peterson for comments. At present time the plan is being revised according to suggestions made in his conference with Superintendent [of the Park, J.R.] Lassiter."<sup>114</sup>

#### 1936

The 1936 master plan shows far less development than was eventually to occur at Big Meadows (it did not include, for instance, the wayside development, the subheadquarters area, or the campground).

Grading on main entrance road and spur to cabins completed in the spring. Entrance road to lodge roughed out in July.

[August]"The sub-headquarters area for Central section of Park is being proposed in the Big Meadows area and will be incorporated in the Cabin Camp plan. A quick rough staking [sic] job will be done by Branch of Engineering to find if grade of approach drive is practical and the revised plan will be submitted for approval . . . WPA forces have commenced excavation for water reservoir and lines."<sup>115</sup>

"On the first of October, Messrs. [Thomas C.] Vint, Oliver G. Taylor, [Kenneth] McCarter and [Paul V.?] Brown accompanied Superintendent Lassiter and [Harvey] Benson to the site of the proposed development. The plan for the campground was inspected on the ground and signed. The following day it was approved by the Director. The following week, sod was stripped from the entrance drive and a bulldozer put to work grading out the roadway. On the inspection trip mentioned above, the

---

<sup>114</sup>"Report of Harvey P. Benson, Assistant Landscape Architect, 3/1935 to 4/1935 in Shenandoah National Park, Report of Branch of Plans and Design Field Office Luray, Virginia." NARA RG 79, Finding Aid 166, Entry 30 (NARA II, College Park, MD.)

<sup>115</sup>Report of Harvey P. Benson, August 1936.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 79

---

party concurred in the site selected for sub-headquarters area and oil station [wayside]." <sup>116</sup>

**1937**

The 1937 master plan for Big Meadows now shows the wayside area and subheadquarters development area.

[February - March] "Sewer line to campground area is nearly completed. No work has been done on campground development except cleanup of dead timber. The two comfort stations have been laid out, but no work has been attempted. However, preparations are being made in assembling all necessary timber, fixtures, and plumbing supplies so that when good weather is encountered the work can be started and continued without interruptions. The carpenter shop for Sub-Headquarters are [sic] as shown on working plan 2011 approved 1/6/37 is underway. The excavation and forms for foundation are completed and the pouring of concrete will take place when cold weather subsides. . . . Stripping and trusking [sic] of sod from the entrance road of the Sub-Headquarters road has been completed. Grading will be started as soon as ground can be worked." <sup>117</sup>

September, revised drawings for the Blacksmith Shop/Storage Shed, Repair Shop, and Garage at the subheadquarters completed.

Picnic Area completed.

**1938**

Petersburg, Bridesburg, Blacksburg, Lynchburg, and Mountain View Cottages completed.

According to the Master Plan overleaf: "Seven double cabins [were] completed in 1937 [sic] by concessionaire to house four people per cabin . . . Each cabin has bed rooms 11'4" x 13'10", toilet and shower and fireplace . . . Estimated cost is about \$1500 each." Proposed features include 33 cabins for the initial development, and another 80 under "ultimate development." Another proposed improvement was, "Host House (Lodge) estimated cost \$85,000" with lobby, lounge, dining hall, kitchen, souvenir shop, toilets, tap room, 14 rooms with showers and fireplaces, 14 rooms with toilets, 4 employees quarters.

---

<sup>116</sup>Report of Harvey P. Benson, October 1936.

<sup>117</sup>Report of Harvey P. Benson, February 20 to March 20, 1937.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 80

---

"Development of the first campground for trailers and tents was finished in 1937 [sic] at Big Meadows. Popular approval of the newly completed area was indicated when, five minutes after the opening of the grounds, a camper appeared. There are 50 places provided for trailers and 20 for tents, and all the necessary facilities for convenient camping have been made available by the two standard comfort stations, a laundry and shower building, 30 fire places, 45 tables, and six water fountains. It has been interesting to observe the use made of tent space against trailer areas, the percentage to date being about four to one in favor of the former."<sup>118</sup>

"By spring of [1938] new roadside stations were constructed at Big Meadows . . . and at Elkwallow . . . Both of these stations, of attractive design and fitting harmoniously into the landscape, are situated far enough from the Drive, with all parking and service facilities in the rear, not to encroach too seriously on the scenic value of the motorway, but they still are readily accessible to the traveler. At both locations there are parking areas for 50 automobiles; and light lunches, gasoline and souvenirs may be obtained."<sup>119</sup>

"Marcellus Wright, Jr., architect for the concessionaire, brought in advance prints of the partially completed Lodge Building for a preliminary consultation. The working drawings should be completed in a few days and made ready for approvals . . . Although the gas pumps were in operation on Sunday, April 13, the [Wayside] concession building was not opened until April 23. . . Six stone drinking fountains are being installed [at the campground] as a part of Job No. 109. Obliteration of the old Appalachian and sodding in various areas are other jobs being carried on at the present time. As soon as logs and lumber are forthcoming from the saw mill, it is planned to start Job No. 186, Construction of Checking Station, and Job No. 185, Construction of Laundry and Sewer Building."<sup>120</sup>

"Of the seven new double cabins now being constructed by the concessionaire, three are completed, furnished, and ready for occupancy. The other four will probably be finished in about two weeks. The Lodge plans are now practically finished and ready for approval. It is not known whether this building will be constructed by force account under Colonel Smith or whether it will be let to

---

<sup>118</sup>Benson, *Skyline Drive*, p. 9.

<sup>119</sup>Benson, *Skyline Drive*, p. 8.

<sup>120</sup>Harvey P. Benson, Monthly Narrative Report to Regional Landscape Architect, March 20 to April 20, 1938. (Available at Shenandoah National Park Archives.)

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 81

---

contract . . . Six fountains, ten underground garbage pails, and six waste baskets have been installed in the camping area. Ten new tables have been built and placed at various camp sites . . . Job No. 186, Construction of Checking Station, [has] been started . . . The carpenter shop, warehouse, and garage are now occupied. The blacksmith shop is under construction with part of the framing finished . . . Footings have been done for the Gas and Oil house."<sup>121</sup>

### 1939

The 1939 Master Plan shows that major improvements have been completed since the last master plan. These include two comfort stations, the checking station, and a laundry/shower at the campground, seven cabins, six buildings at the subheadquarters, the wayside building and the comfort station at the picnic grounds.

"In July, 1939, the Virginia Sky-Line Company finished extensive construction work on the lodge at Big Meadows about one mile northwest of the Drive. Of native stone and chestnut, the building rambles more than 300 feet in length and rests soundly on the edge of an escarpment which affords interesting views of the valley and distant mountain ranges. A large dining room, accommodating 150 guests and finished entirely in native chestnut, is oriented so that diners may enjoy far-reaching views of the surrounding countryside. In addition to a large lobby and lounge, 26 guest rooms (all with baths and some with fireplaces), have been provided.

"The lodge is virtually the beginning of the development proposed by the operator in the vast area at Big Meadows, although seven two-room cabins had been completed the previous year. There is sufficient room for 150 to 200 cabins if the demand arises for such an increase in lodging facilities, and adequate areas have been planned for riding horse stables, game courts, outdoor theater, community building and museum."<sup>122</sup>

### 1940

The Master Plan for the area dated 1/1/1940 shows a number of unexecuted features. A recreational area located on the west side of Big Meadows Road, slightly to the south and west of the cabin loop was planned. This area was to include a central parking area surrounded by a museum, tennis

---

<sup>121</sup>Harvey P. Benson, Monthly Narrative Report to Regional Landscape Architect, April 20 to May 20, 1938. (Available at Shenandoah National Park Archives.)

<sup>122</sup>See Benson, "Skyline Drive."

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 82

---

courts, and an amphitheater. In addition, a large stables area with paddock was to be located to the east of the present location.

**1941 - present**

Piedmont Cottage BM-0115 1941

Blackrock, Hawksbill Cottages completed c.1946

Double Top Cottage completed 1959

Employee Quarters completed 1961-6

Rapidan Cottage completed 1963

Byrd Visitors Center completed 1966

Amphitheater completed c.1978

**Dickey Ridge**

**1936**

"On October 1, 1936, Messrs. Vint, Taylor, McCarter visited the Park to formulate recommendations for . . . Roadside Comfort Stations, and Oil Station locations . . . The following locations were decided upon Comfort Stations: Gasoline Station Dickey Hill Development . . . Oil Station Locations: Dickey Hill or Gravelly Springs.<sup>123</sup>

**1938**

Picnic Grounds (including comfort station) completed.

"[During 1937] the operator began construction of a somewhat larger unit at Dickey Ridge, on the Drive five miles south of Front Royal. The concession building, opened to the public in May, 1938, stands just off the Drive where views of a 300-degree arc command the adjacent lowland country. The building contains a dining room for 60 persons, and an outdoor dancing terrace, in addition to

---

<sup>123</sup>Report of Harvey P. Benson, October 1936.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 83

---

a coffee shop and a gasoline station. There are parking facilities for 110 automobiles."<sup>124</sup>

"The Concessionaire has begun construction on the north wing, a recently approved extension. . . . It was a mistake to approve this extension until a study for service yard and entrance was made. As the building now exists, there is no place on either of the three sides where a small yard can be installed properly without obstruction on desirable views . . . Without prior approval of any kind, the Concessionaire has constructed a semi-circular terrace on the west and has begun a small terrace on the north side of the new addition . . . The picnic grounds, Job No. 177, with about 1/2 day's grading will be ready to receive the base stone on roads and parking areas."<sup>125</sup>

"The concession building is being rapidly completed for the opening on May 28. . . . The road loop to the cabin site has been graded and is now ready to receive the stone."<sup>126</sup>

### 1939

"Later in 1939 twelve cabins of native chestnut, containing from two to four rooms each with either private or joint baths, were built with total accommodations for 60 guests"<sup>127</sup> [These cabins were moved to the Lewis Mountain, Skyland, and Elkallow areas.]

## Headquarters

### 19th Century

Superintendent House/Center for Resources completed.

### 1916

Residence completed.

---

<sup>124</sup>Benson, *Skyline Drive*, p. 8.

<sup>125</sup>Harvey P. Benson, Monthly Narrative Report to Regional Landscape Architect, March 20 to April 20, 1938. (Available at Shenandoah National Park Archives.)

<sup>126</sup>Harvey P. Benson, Monthly Narrative Report to Regional Landscape Architect, April 20 to May 20, 1938. (Available at Shenandoah National Park Archives.)

<sup>127</sup>Benson, *Skyline Drive*, p. 8.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 84

---

**1935**

"After making several sketch plans for the headquarter's Area at Thornton Gap two were selected because of their topographical relationship; I spent the early part of the month drawing these two schemes in a more presentable manner . . ."<sup>128</sup>

**1936**

The 1936 Master Plan shows the Headquarters area on a site to the east of its current location, directly on Skyline Drive. Although the layout of the area is slightly different from what was ultimately constructed, the plan and the final product are very similar.<sup>129</sup>

**1937**

The 1937 master plan shows the Headquarters at its current location, although no specific plans for its development are included.

**1938**

A PWA allotment for a \$50,000 addition to the Administration Building and a \$20,000 addition to the utility buildings at Headquarters is approved.<sup>130</sup>

Work begins on the Administration Building and warehouse in the Headquarters maintenanc area.

**1939**

The 1939 master plan shows a detailed plan of the Headquarters area at its present location and in its current configuration.

**1940**

Equip.Storage/Workshop/Carpentry-Welding (HQ-0401), Equipment Shed (HQ-0403), Warehouse

---

<sup>128</sup>Report of Wallace G. Atkinson, Junior Landscape Architect, 3/1935 to 4/1935 in Shenandoah National Park Report of Branch of Plans and Design Field Office, Luray, Virginia.

<sup>129</sup>No documentary evidence has been located on how the location of the Headquarters area was selected. However, according to oral history sources, a primary reason for its location was the adverse winter weather on the Drive. Unlike contiguous areas in the park, the selected site was accessible by car twelve months a year.

<sup>130</sup>"Beltsville P.W.A Grants Rescinded," *Washington Star*, September 23, 1938.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 85

---

(HQ-0406) completed.

Administration Building completed.

**1941**

Employees Residences (HQ-0203, HQ-0204) and accompanying garages completed.

**1942**

Sign Shop (HQ-0426) completed.

Employee Residence (HQ-0208) and garage completed.

**1943-present**

Gas & Oil Storage Building completed 1943.

Employee Residences completed 1959.

**Piney River**

**1935**

CCC Camp NP-12 moved from Sperryville to Piney River/Rattlesnake Point.<sup>131</sup>

Naturalist's Office completed

Maintenance Office/Station completed

**1937**

Maintenance/Equipment Shed completed

**1943**

CPS workers dismantle most of the CCC camp buildings and complete alterations to the Technical Service Quarters for use as North District Ranger Station. According to the CPS report, "The building was given to us by the Army when the camp was demolished. It lends itself well to

---

<sup>131</sup>NARA, RG 79, Finding Aid 166, Entry 62 (NARA II, College Park, MD).

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 8 Page 86

---

alteration for use as a ranger station, very much needed in this district, until the permanent facilities are made available. The proposed station is located strategically for fire protection as well as general administration. It is only a mile from the Hogback fire tower and two miles from the Elkwallow tavern and picnic ground. Facilities are available for storage of road maintenance, as well as ranger, equipment . . . We wish to stress the fact that this is purely a temporary expedient and the work undertaken will involve only that necessary to make the building livable."<sup>132</sup>

Ranger Office completed 1948

**Simmons Gap**

Mission/Residence constructed 1925.

Gas/Oil Building completed 1934.

Fire Cache completed 1937.

Maintenance Shed completed 1937.

Storage Shed completed 1939.

Maintenance Shop completed 1939.

---

<sup>132</sup>NARA, RG 79, Finding Aid 166, Entry 62 (NARA II, College Park, MD).

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 9 Page 87

---

## BIBLIOGRAPHY

### Published Sources

Horace M. Albright, "My Trips With Harold Ickes," *Washington History*, Spring 1990, p.39.

Benson, Harvey P. "The Skyline Drive," *The Regional Review*, February. 1940.

"Beltsville P.W.A Grants Rescinded," *Washington Star*, September 23, 1938.

Cohen, Stan. *The Tree Army: A Pictorial History of the Civilian Conservation Corps, 1933-1942*.  
Missoula, Montana: Pictorial Histories Publishing Company, 1980.

Connors, John. A. *Shenandoah National Park: An Interpretive Guide*. Blacksburg, Virginia: The  
McDonald and Woodward Publishing Company, 1988.

Floyd, Tom. *Lost Trails and Forgotten People*. Vienna, Virginia: The Potomac Appalachian Trail  
Club, 1981.

Good, Albert. *Park and Recreation Structures*. (Part 1) Washington, D.C.: National Park Service,  
1938.

Good, Albert. *Park Structures and Facilities*. Washington, D.C.: National Park Service, 1935.

Hiltz, Andy, ed. *Appalachian Trail Guide to Shenandoah National Park With Side Trails*, 11th  
edition. Vienna, Virginia: The Potomac Appalachian Trail Club, 1994.

Lambert, Darwin L. *Herbert Hoover's Hideaway*. Luray, Virginia: Shenandoah Natural History  
Association, 1971.

Lambert, Darwin L. *The Undying Past of Shenandoah National Park*. Boulder, Colorado: Roberts  
Rinehart, Inc. Publishers, 1989.

McClelland, Linda. *Presenting Nature: The Historic Landscape Design of the National Park Service*.  
Washington, D.C.: National Park Service, United States Department of the Interior, 1993.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 9 Page 88

---

National Park Service. *Portfolio of Comfort Stations and Privies*. Washington, D.C.: National Park Service, 1934.

National Park Service. *Portfolio of Park Structures*. Washington, D.C.: National Park Service, 1934.

Otis, Allison, William D. Honey, et al., *The Forest Service and Civilian Conservation Corps: 1933-42*, U.S. Department of Agriculture, Forest Service, 1986.

Pollock, George Freeman. *Skyland: The Heart of the Shenandoah National Park*. Virginia: The Chesapeake Book Company, 1960.

Reeder, Jack and Carolyn Reeder. *Shenandoah Heritage: The Story of the People Before the Park*. Washington, D.C.: The Potomac Appalachian Trail Club, 1978.

Reeder, Jack and Carolyn Reeder. *Shenandoah Secrets: The Story of the Park's Hidden Past*. Washington, D.C.: The Potomac Appalachian Trail Club, 1991.

Reeder, Jack and Carolyn Reeder. *Shenandoah Vestiges: What the Mountain People Left Behind*. Washington, D.C.: The Potomac Appalachian Trail Club, 1980.

Short, C.W., and R. Stanley-Brown. *Public Buildings: A Survey of Architecture of Federal and Other Governmental Bodies . . .* Washington, D.C.: General Printing Office, 1939.

Smith, Dorothy Noble. *Recollections: The People of Blue Ridge Remember*. Virginia: McClure Printing Co., 1983.

Wilson, Richard Guy, ed., *Victorian Resorts and Hotels*. Philadelphia: The Victorian Society, 1982.

Unpublished Sources and Oral Interviews

Baughan, G.L."Hop." Oral interview with Carol Hooper, Robinson & Associates, Inc., September 21, 1995.

Determination of Significance Forms (Multiple Buildings). Shenandoah National Park Administrative Files, Shenandoah National Park, Virginia.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 9 Page 89

---

- Engle, Reed L. "Skyland Historic District National Register Nomination [draft], 1995.
- Hoffman, Michael A. "A Synopsis of Patterns in Time: Human Adaptation in the Blue Ridge from 7000 B.C. to 1930 A.D." Prepared for the Shenandoah National Park, 1979.
- Horning, Audrey J. "From Hollow to Valley and Back Again: Historical Anthropology of Nicholson Hollow in Regional Context." Paper presented at "After the Backcountry: Rural Life and Society in the Nineteenth Century Valley of Virginia" conference, March 1995.
- Kloster, Don. Telephone interview with Carol Hooper, Robinson & Associates, Inc., November 1995.
- Lambert, Darwin. "Shenandoah National Park: Administrative History 1924-1976." Luray, Virginia, 1979. Photocopy.
- Maddex, Lee R., et al. "Skyline Drive Historic District National Register Nomination," 1996.
- McClelland, Linda Flint. "Historic Park Landscapes in National and State Parks National Register of Historic Places Multiple Property Nomination," 1995.
- Paige, John C. "The Civilian Conservation Corps and the National Park Service, 1933-1942: An Administrative History." National Park Service, United States Department of the Interior, 1985. Photocopy.
- Park Building Survey. [Various Structures in Shenandoah National Park]. Administrative Files Shenandoah National Park, Virginia.
- Romola, Linda and Jacob Hoogland. "Simmons Gap Mission--Community Hall or Parish House National Register of Historic Places Nomination Form" [draft], 1983.
- Shenandoah National Park. "1973 Sellars Report." Administrative Files. Shenandoah National Park, Virginia.
- Shenandoah National Park. "Report on the Old Mill and Tavern Located near Swift Run Gap." Administrative Files. Shenandoah National Park, Virginia.
- Shenandoah National Park. Individual Building Data Cards (Various dates). Administrative Files

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 9 Page 90

---

Shenandoah National Park, Virginia.

Simmons, Dennis Elwood. "The Creation of Shenandoah National Park and the Skyline Drive, 1924-36" Ph.D Dissertation, University of Virginia, 1978.

Steere, Edward. "Historical Study of Park." United States Department of the Interior. National Park Service, Administrative Files Shenandoah National Park, Virginia.

United States Department of the Interior. National Park Service. "General Management Plan and Development Concept Plan for Shenandoah National Park, Virginia." Prepared by the Denver Service Center, 1983.

Wright, Marcellus, Jr. Oral interview with Carol Hooper, Robinson & Associates, Inc., September 25, 1995.

Plans, Maps, etc.

Shenandoah National Park. Master Plans. 1936, 1937, 1938, 1939.

Architectural Drawings (various) Shenandoah National Park. National Park Service, Denver Service Center, Technical Information Center.

"Protestant Episcopal Mission Activities: 1904-10," (Lot 6986), Prints and Photographs Division, Library of Congress.

Shenandoah National Park Archives, Photographic Collection. Shenandoah National Park, Virginia.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 10 Page 91

---

A	Headquarters Administration Building	17.728840.4282645
B	Headquarters Residential Area	17.728750.4282760
C	Headquarters Superintendent's House Area	17.728940.4282500
D	Headquarters Maintenance Area	17.728900.4283000
E	Dickey Ridge Visitor Center	17.742490.4306040
F	Dickey Ridge Picnic Grounds	17.742630.4305600
G	Piney River Ranger Stat.	17.735260.4292380
H	Big Meadows Wayside	17.723280.4266000
I	Big Meadows Lodge	17.723110.4267410
J	Big Meadows Campground	17.723550.4267500
K	Big Meadows Picnic Area	17.723400.4267500
L	Big Meadows Maintenance Area	17.723620.4266380
M	Simmons Gap Ranger Stat./ Maintenance Area	17.707880.4241750

(Note: See USGS maps for full listing of UTM's for each area)

Verbal Boundary Description

This boundary addition to the Skyline Drive Historic District includes five areas located adjacent to, or near, the Skyline Drive. They include: the Headquarters area (including the administration, residential, Superintendent's house, and maintenance subareas), the Dickey Ridge area (including the visitor center, former cabin area, and picnic grounds), the Piney River ranger station/maintenance area, the Big Meadows area (including the Wayside, the Lodge, the campground, the picnic area, and the maintenance subareas), and the Simmons Gap ranger station/maintenance area. Within the five areas, the boundary is defined as 125 feet on either side of the centerline of all National Park Service-constructed or -used circulation roads and parking areas that were in place 1950. Specifically, the roads and parking areas within the boundaries of the nominated area include:

Headquarters area

- Parking areas located off of Rt. 211 and to the west of the Administration Building
- "Headquarters Road"
- Residential area access road and loop
- Superintendent's residence area access road
- Maintenance area access road and internal roads

Big Meadows Area

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 10 Page 92

---

- Parking area for wayside
  - "Big Meadow Road"
  - Maintenance area access road and internal roads
  - Camping and picnic area access road
  - Picnic area loop and parking areas
  - Campground loops
  - Lodge access circle
  - Lodge parking areas
  - Lodge loop (leading back to Big Meadows Road)
- Dickey Ridge Area
- Dickey Ridge road
  - Visitor Center parking area
  - Cabin area access drive
  - Picnic area access road (from Skyline Drive)
- Simmons Gap
- Access road from Skyline Drive and spurs
- Piney River
- Access road from Skyline Drive and spurs

### Boundary Justification

The boundaries of the nominated area were designed to be consistent with the boundaries of the original Skyline Drive nomination (i.e., an area 125 feet on either side of Skyline Drive and ancillary roads). The boundaries encompass most built resources in five developed areas of the park.<sup>133</sup> Sections of these areas not included in this nomination are significantly removed from other resources and if included in the nomination would contain exclusively noncontributing resources .

One area included in this nomination (Headquarters) is discontinuous with the rest of the area included in the original nomination. The area between the headquarters area and the rest of the park, although outside the park boundaries, has always been within the park's legislative boundaries. Under National Register Bulletin 21, discontinuous districts are appropriate where "elements are spatially discrete, space between the elements is not related to the significance of the district; and

---

<sup>133</sup>Where the boundary falls within, or immediately adjacent to, historic buildings described in this nomination the buildings should be considered to be included in the nomination.



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number 10 Page 93

---


visual continuity is not a factor in the significance." The Headquarters area was never contiguous to the rest of the park and is spatially discrete from it. The area between the Headquarters area and the Skyline Drive is not directly related to the significance of the district. Visual continuity is not a factor in the district's significance. Because all of the criteria are satisfied, a discontinuous district is appropriate in this case.

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County,  
VA

Section number Sketch Plan Page 103




Key Map: Headquarters

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number Sketch Plan Page 104




Key Map: Big Meadows

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County,  
VA

Section number Sketch Plan Page 105




Key Map: DICKEY RIDGE

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County,  
VA

Section number Sketch Plan Page 106




Key Map: Simmons Gap

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County,  
VA

Section number Sketch Plan Page 107



Key Map: Piney River

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo Page 94

---

All photographs are of:

SKYLINE DRIVE HISTORIC DISTRICT (Boundary Addition)

VDHR File Number: 093-0001

Carol Hooper, photographer

All negatives are stored with the Department of Historic Resources, Richmond, VA.

LOCATION/COUNTY: Headquarters  
Administration Area, Page County  
DATE: 1995  
VIEW OF: Administration Building (HQ-0101) south elevation; view looking north  
NEG. No.: 15367  
PHOTO 1 OF 62

LOCATION/COUNTY: Headquarters  
Administration Area, Page County  
DATE: 1995  
VIEW OF: Detail, Administration Building (HQ-0101) south elevation; view looking east  
NEG. No.: 15367  
PHOTO 2 OF 62

LOCATION/COUNTY: Headquarters  
Administration Area, Page County  
DATE: 1995  
VIEW OF: Administration Building (HQ-0101) interior; view of foyer  
NEG. No.: 15369  
PHOTO 3 OF 62

LOCATION/COUNTY: Headquarters  
Residential Area, Page County  
DATE: 1995  
VIEW OF: Residence (HQ-0217) east elevation; view looking west  
NEG. No.: 13569  
PHOTO 4 OF 62

LOCATION/COUNTY: Headquarters  
Residential Area, Page County  
DATE: 1995  
VIEW OF: Residence (HQ-0208) east elevation; view looking west  
NEG. No.: 13569  
PHOTO 5 OF 62

LOCATION/COUNTY: Headquarters  
Residential Area, Page County  
DATE: 1995  
VIEW OF: Garage (HQ-0310) west elevation; view looking east  
NEG. No.: 13569  
PHOTO 6 OF 62

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo Page 95

---

LOCATION/COUNTY: Headquarters  
Residential Area, Page County  
DATE: 1995  
VIEW OF: Residence (HQ-0202) north  
elevation; view looking south  
NEG. No.: 15369  
PHOTO 7 OF 62

LOCATION/COUNTY: Headquarters  
Superintendent's Residence Area, Page  
County  
DATE: 1995  
VIEW OF: Superintendent's Residence  
(HQ-0218) north and west elevations; view  
looking east  
NEG. No.: 15369  
PHOTO 8 OF 62

LOCATION/COUNTY: Headquarters  
Maintenance Area, Page County  
DATE: 1996  
VIEW OF: Maintenance Area; view looking  
north  
NEG. No.: 15429  
PHOTO 9 OF 62

LOCATION/COUNTY: Headquarters  
Maintenance Area, Page County  
DATE: 1996  
VIEW OF: Warehouse (HQ-0406) south  
and east elevations; view looking northwest  
NEG. No.: 15429  
PHOTO 10 OF 62

LOCATION/COUNTY: Headquarters  
Maintenance Area, Page County  
DATE: 1996  
VIEW OF: Gas & Oil Storage Building  
(HQ-0409) north and west elevations; view  
looking south  
NEG. No.: 15429  
PHOTO 11 OF 62

LOCATION/COUNTY: Headquarters  
Maintenance Area, Page County  
DATE: 1995  
VIEW OF: Equipment Storage and  
Workshop (HQ-0401) south elevation; view  
looking north  
NEG. No.: 15369  
PHOTO 12 OF 62

LOCATION/COUNTY: Headquarters  
Maintenance Area, Page County  
DATE: 1995  
VIEW OF: Equipment Storage Shed (HQ-  
0403) east elevation; view looking west  
NEG. No.: 15369  
PHOTO 13 OF 62

LOCATION/COUNTY: Headquarters  
Maintenance Area, Page County  
DATE: 1995  
VIEW OF: Workshop Garage (HQ-0422)  
east elevation; view looking west  
NEG. No.: 15369  
PHOTO 14 OF 62



United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo Page 96

---

LOCATION/COUNTY: Headquarters  
Maintenance Area, Page County  
DATE: 1996  
VIEW OF: Maintenance Building (HQ-  
0457) west elevation; view looking southeast  
NEG. No.: 15429  
PHOTO 15 OF 62

LOCATION/COUNTY: Big Meadows  
Wayside Area, Madison County  
DATE: 1995  
VIEW OF: Wayside Building (BM-0113)  
north elevation; view looking south  
NEG. No.: 15367  
PHOTO 16 OF 62

LOCATION/COUNTY: Big Meadows  
Wayside Area, Madison County  
DATE: 1995  
VIEW OF: Service Station (BM-0374)  
north elevation; view looking south  
NEG. No.: 15367  
PHOTO 17 OF 62

LOCATION/COUNTY: Big Meadows  
Wayside Area, Madison County  
DATE: 1995  
VIEW OF: Byrd Visitor Center (BM-2302)  
south elevation; view looking north  
NEG. No.: 15367  
PHOTO 18 OF 62

LOCATION/COUNTY: Big Meadows  
Campground Area, Madison and Page  
Counties  
DATE: 1995  
VIEW OF: Campground Contact Station  
(BM-0705) north and west elevations; view  
looking east  
NEG. No.: 15369  
PHOTO 19 OF 62

LOCATION/COUNTY: Big Meadows  
Campground Area, Madison and Page  
Counties  
DATE: 1996  
VIEW OF: General view of campground  
NEG. No.: 15429  
PHOTO 20 OF 62

LOCATION/COUNTY: Big Meadows  
Campground Area, Madison and Page  
Counties  
DATE: 1996  
VIEW OF: Drinking Fountain  
NEG. No.: 15429  
PHOTO 21 OF 62

LOCATION/COUNTY: Big Meadows  
Picnic Area  
DATE: 1995  
VIEW OF: Comfort Station (BM-0507)  
south and east elevations; view looking north  
NEG. No.: 15369  
PHOTO 22 OF 62

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo Page 97

---

LOCATION/COUNTY: Big Meadows  
Lodge Area, Page County  
DATE: 1995  
VIEW OF: Lodge (BM-0114) southeast  
elevation; view looking northwest  
NEG. No.: 15366  
PHOTO 23 OF 62

LOCATION/COUNTY: Big Meadows  
Lodge Area, Page County  
DATE: 1995  
VIEW OF: Lodge (BM-0114) southeast  
elevation; view looking northwest  
NEG. No.: 15366  
PHOTO 24 OF 62

LOCATION/COUNTY: Big Meadows  
Lodge Area, Page County  
DATE: 1995  
VIEW OF: Lodge (BM-0114) detail of  
northwest elevation  
NEG. No.: 15366  
PHOTO 25 OF 62

LOCATION/COUNTY: Big Meadows  
Lodge Area, Page County  
DATE: 1995  
VIEW OF: Lodge (BM-0114) interior; view  
of lounge  
NEG. No.: 15366  
PHOTO 26 OF 62

LOCATION/COUNTY: Big Meadows  
Lodge Area, Page County  
DATE: 1995  
VIEW OF: Lodge (BM-0114) interior; view  
of Dining Room looking north  
NEG. No.: 15366  
PHOTO 27 OF 62

LOCATION/COUNTY: Big Meadows  
Lodge Area  
DATE: 1995  
VIEW OF: Blacksburg Cottage (BM-0152)  
northeast and southeast elevations; view  
looking west  
NEG. No.: 15366  
PHOTO 28 OF 62

LOCATION/COUNTY: Big Meadows  
Lodge Area  
DATE: 1996  
VIEW OF: Lynchburg Cottage (BM-0155)  
southwest and southeast elevations; view  
looking north  
NEG. No.: 15429  
PHOTO 29 OF 62

LOCATION/COUNTY: Big Meadows  
Lodge Area  
DATE: 1995  
VIEW OF: Piedmont Cottage (BM-0115)  
east elevation; view looking west  
NEG. No.: 15366  
PHOTO 30 OF 62

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo \_\_\_\_\_ Page 98 \_\_\_\_\_

---

LOCATION/COUNTY: Big Meadows  
Lodge Area  
DATE: 1995  
VIEW OF: Cottage B (BM-1157) north and  
west elevations; view looking northeast  
NEG. No.: 15366  
PHOTO 31 OF 62

LOCATION/COUNTY: Big Meadows  
Lodge Area  
DATE: 1995  
VIEW OF: Rapidan Cottage (BM-0344)  
southeast elevation; view looking northwest  
NEG. No.: 15366  
PHOTO 32 OF 62

LOCATION/COUNTY: Big Meadows  
Maintenance Area, Madison County  
DATE: 1995  
VIEW OF: General View of Maintenance  
Area; view looking south  
NEG. No.: 15369  
PHOTO 33 OF 62

LOCATION/COUNTY: Big Meadows  
Maintenance Area, Madison County  
DATE: 1996  
VIEW OF: Gas/Oil Building (BM-0416)  
north and west elevation; view looking south  
NEG. No.: 15365  
PHOTO 34 OF 62

LOCATION/COUNTY: Big Meadows  
Maintenance Area, Madison County  
DATE: 1996  
VIEW OF: Blacksmith Shop (BM-0412)  
north and west elevation; view looking east  
NEG. No.: 15365  
PHOTO 35 OF 62

LOCATION/COUNTY: Big Meadows  
Maintenance Area, Madison County  
DATE: 1995  
VIEW OF: Warehouse (BM-0415) west  
elevation; view looking east  
NEG. No.: 15369  
PHOTO 36 OF 62

LOCATION/COUNTY: Big Meadows  
Maintenance Area, Madison County  
DATE: 1995  
VIEW OF: Equipment Storage Building  
(BM-0411) west elevation; view looking east  
NEG. No.: 15369  
PHOTO 37 OF 62

LOCATION/COUNTY: Big Meadows  
Maintenance Area, Madison County  
DATE: 1995  
VIEW OF: Repair Shop/Garage (BM-0410)  
west elevation; view looking east  
NEG. No.: 15369  
PHOTO 38 OF 62

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo Page 99

---

LOCATION/COUNTY: Big Meadows  
Maintenance Area, Madison County  
DATE: 1995  
VIEW OF: Stables Area (BM-1158, 0321);  
view looking south  
NEG. No.: 15369  
PHOTO 39 OF 62

LOCATION/COUNTY: Big Meadows  
Maintenance Area, Madison County  
DATE: 1996  
VIEW OF: Office/Ranger's Quarters (BM-  
0214) south and east elevations; view looking  
west  
NEG. No.: 15365  
PHOTO 40 OF 62

LOCATION/COUNTY: Dickey Ridge  
Area, Warren County  
DATE: 1995  
VIEW OF: Visitor Center (Lodge) (DR-  
2301) east elevation; view looking west  
NEG. No.: 15367  
PHOTO 41 OF 62

LOCATION/COUNTY: Dickey Ridge  
Area, Warren County  
DATE: 1995  
VIEW OF: Visitor Center (Lodge) (DR-  
2301) west elevation; view looking east  
NEG. No.: 15367  
PHOTO 42 OF 62

LOCATION/COUNTY: Dickey Ridge  
Area, Warren County  
DATE: 1995  
VIEW OF: Drinking Fountain, Picnic Area  
NEG. No.: 15367  
PHOTO 43 OF 62

LOCATION/COUNTY: Simmons Gap  
Area, Greene County  
DATE: 1995  
VIEW OF: Mission\Residence (SG-0711)  
west and south elevations; view looking  
north  
NEG. No.: 15369  
PHOTO 44 OF 62

LOCATION/COUNTY: Simmons Gap  
Area, Greene County  
DATE: 1995  
VIEW OF: Mission\Residence (SG-0711)  
north elevation; view looking south  
NEG. No.: 15369  
PHOTO 45 OF 62

LOCATION/COUNTY: Simmons Gap  
Area, Greene County  
DATE: 1995  
VIEW OF: Gas/Oil Building (SG-0431)  
west and north elevation; view looking  
southeast  
NEG. No.: 15369  
PHOTO 46 OF 62

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo Page 100

---

LOCATION/COUNTY: Simmons Gap  
Area, Greene County  
DATE: 1995  
VIEW OF: Maintenance Shed (SG-0448)  
west elevation; view looking east  
NEG. No.: 15369  
PHOTO 47 OF 62

LOCATION/COUNTY: Simmons Gap  
Area, Greene County  
DATE: 1995  
VIEW OF: Storage Shed (SG-0449) north  
and west elevations; view looking east  
NEG. No.: 15369  
PHOTO 48 OF 62

LOCATION/COUNTY: Piney River Area,  
Page and Warren Counties  
DATE: 1995  
VIEW OF: General View; view looking  
north  
NEG. No.: 15367  
PHOTO 49 OF 62

LOCATION/COUNTY: Piney River Area,  
Page and Warren Counties  
DATE: 1995  
VIEW OF: Maintenance Office /CCC  
Technical Office (PR-0712) west elevation;  
view looking east  
NEG. No.: 15367  
PHOTO 50 OF 62

LOCATION/COUNTY: Piney River Area,  
Page and Warren Counties  
DATE: 1995  
VIEW OF: Maintenance Office /CCC  
Technical Office (PR-0712) east elevation;  
view looking west  
NEG. No.: 15367  
PHOTO 51 OF 62

LOCATION/COUNTY: Piney River Area,  
Page and Warren Counties  
DATE: 1996  
VIEW OF: Maintenance/Equipment Shed-  
CCC (Pr-0437) south and west elevations;  
view looking north  
NEG. No.: 15429  
PHOTO 52 OF 62

LOCATION/COUNTY: Piney River Area,  
Page and Warren Counties  
DATE: 1995  
VIEW OF: Naturalist's Office-CCC (PR-  
0439) south elevation; view looking north  
NEG. No.: 15367  
PHOTO 53 OF 62

LOCATION/COUNTY: Piney River Area,  
Page and Warren Counties  
DATE: 1996  
VIEW OF: Maintenance Building (PR-  
4101) southeast and northeast elevations;  
view looking southwest  
NEG. No.: 15429  
PHOTO 54 OF 62

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo Page 101

---

**HISTORIC PHOTOGRAPH**

LOCATION/COUNTY: Headquarters  
Administration Area  
DATE: 8/12/1940  
VIEW OF: Administration Building  
SOURCE: Shenandoah National Park  
Archives  
NEG. No.: 15365  
PHOTO 55 OF 62

**HISTORIC PHOTOGRAPH**

LOCATION/COUNTY: Headquarters  
Maintenance Area, Page County  
DATE: 9/10/1940  
VIEW OF: General View of Maintenance  
Area  
SOURCE: Shenandoah National Park  
Archives  
NEG. No.: 15365  
PHOTO 56 OF 62

**HISTORIC PHOTOGRAPH**

LOCATION/COUNTY: Big Meadows  
Area  
DATE: No Date (circa late 1930s)  
VIEW OF: Wayside Building west  
elevation; view looking east  
SOURCE: Shenandoah National Park  
Archives  
NEG. No.: 15365  
PHOTO 57 OF 62

**HISTORIC PHOTOGRAPH**

LOCATION/COUNTY: Big Meadows Area  
DATE: 3/30/1936  
VIEW OF: Big Meadows Road  
SOURCE: Shenandoah National Park  
Archives  
NEG. No.: 15365  
PHOTO 58 OF 62

**HISTORIC PHOTOGRAPH**

LOCATION/COUNTY: Big Meadows Area  
DATE: No Date (circa late 1930s)  
VIEW OF: Campground Area; view looking  
east  
SOURCE: Shenandoah National Park  
Archives  
NEG. No.: 15365  
PHOTO 59 OF 62

**HISTORIC PHOTOGRAPH**

LOCATION/COUNTY: Big Meadows Area  
DATE: 5/2/1940  
VIEW OF: Cabins Area  
SOURCE: Shenandoah National Park  
Archives  
NEG. No.: 15365  
PHOTO 60 OF 62

**HISTORIC PHOTOGRAPH**

LOCATION/COUNTY: Big Meadows Area  
DATE: 4/13/1940  
VIEW OF: Maintenance Area; view looking  
SOURCE: Shenandoah National Park  
Archives  
NEG. No.: 15365  
PHOTO 61 OF 62

United States Department of the Interior  
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES  
CONTINUATION SHEET

Skyline Drive Historic District (Boundary Increase), Page County, VA

Section number photo Page 102

---

**HISTORIC PHOTOGRAPH**

LOCATION/COUNTY: Piney River Area,  
Page and Warren Counties


DATE: February 1943

VIEW OF: CCC Camp NP-12 (General  
View of Area)

SOURCE: Shenandoah National Park  
Archives

NEG. No.: 15365

PHOTO 62 OF 62




SKYLINE DRIVE  
 HISTORIC DISTRICT  
 (BOUNDARY ADDN)  
 Headquarters Area  
 Page County, VA

UTM References

1. 17.729050 4283100
2. 17.729175 4282950
3. 17.729175 4282720
4. 17.728725 4282440
5. 17.728600 4282520
6. 17.728550 4282875





32'30"

SKYLINE DRIVE  
HISTORIC DISTRICT  
(BOUNDARY ADDITION)

Big Meadow Area,  
4268

Madison & Page  
Counties, VA

UTM References;

1. 17.723350.4267500
2. 17.723570.4267500
3. 17.723700.4267280
4. 17.723780.4267100
5. 17.723740.4266100
6. 17.723220.4265740
7. 17.722900.4266880
8. 17.723000.4267290

4267


4266

4265000m N.

25' 726 727 INTERIOR—GEOLOGICAL SURVEY RESTON, VIRGINIA—1989 728000mE 78° 22'30" 38° 30'

ROAD CLASSIFICATION

Heavy-duty	—————	Light-duty	-----
Medium-duty	- - - - -	Unimproved dirt	.....
		U. S. Route	State Route



BIG MEADOWS, VA.


38078-E4-TF-024

1965  
PHOTOREVISED 1979  
DMA 5361 III SW—SERIES V834

Boundary lines shown in purple compiled from latest information available from the controlling authority


MADISON  
VA 22656






(FLETCHER)  
5360 IV NW

SCALE 1:24 000



UTM GRID AND 1979 MAGNETIC NORTH DECLINATION AT CENTER OF SHEET



CONTOUR INTERVAL 40 FEET  
 DOTTED LINES REPRESENT 20-FOOT CONTOURS  
 NATIONAL GEODETIC VERTICAL DATUM OF 1929

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS  
 FOR SALE BY U.S. GEOLOGICAL SURVEY DENVER COLORADO 80225 OR RESTON VIRGINIA

381 N NE  
(STRASBURG)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

742

78° 15'  
38° 52' 30"

FRONT ROYAL 4.5 MI.

740000m E

2.7 MI TO U.S. 740

FRONT ROYAL 5 MI

12' 30"

SKYLINE DRIVE  
HISTORIC DISTRICT  
(BOUNDARY ADDITION)

Dickey Ridge Area,  
Warren County, Va

UTM References:

4305


1. 17.742380.4306200

2. 17.742575.4305950

3. 17.742850.4305560

4. 17.742680.4305300

5. 17.742300.4306000



KYLE DRIVE  
HISTORIC DISTRICT  
BOUNDARY ADDN.)  
Simmons Gap Area,  
Kingham &  
Greene Cos, VA

UTM References:  
707650 4241900  
708360 4241675  
708160 4241450  
707850 4241770

5260 / SW  
MC GAHEYSVILLE

4242

17'30"

1/4 MI 1 1/4 1/2 1/4

4239

220 000 FEET  
(NORTH)

